

IN THE DISTRICT COURT OF THE FIFTH JUDICIAL DISTRICT OF THE STATE OF IDAHO,
IN AND FOR THE COUNTY OF TWIN FALLS

IN RE THE GENERAL ADJUDICATION
OF RIGHTS TO THE USE OF WATER FROM
THE SNAKE RIVER BASIN WATER SYSTEM.

CIVIL CASE NUMBER: 39576

RECEIVED
FEB 26 1990

Ident. Number: A63-20677
Date Received: ~~2/06/1990~~ 2-26-90
Receipt No: W009582
Received By: _____

Department of Water Resources
Western Regional Office

**NOTICE OF CLAIM TO A WATER RIGHT
ACQUIRED UNDER STATE LAW**

1. Name: SUNNYRIDGE HTS. PROP. OWN. ASSN. INC. 208-467-4176
Address: C/O 4106 JESSE LANE
NAMPA, ID 83686

2. Date of Priority: AUG 06, 1959

3. Source: GROUNDWATER Trib. to:

4. Point of Diversion:

Township	Range	Section	1/4 of	1/4 of	1/4	Lot	County
02N	02W	10	NW	NE			CANYON

5. Description of diverting works:
WELL, PUMP, & PIPELINES

6. Water is used for the following purposes:

Purpose	From	To	C.F.S.	(or)	A.F.A.
IRRIGATION	03/15	11/15	0.520		
DOMESTIC	01/01	12/31	0.180		

7. Total Quantity Appropriated is:
0.700 C.F.S. (and/or) A.F.A.

8. Total consumptive use is 91.0 Acre Feet Per Annum.

9. Non-irrigation uses:
DOMESTIC, INTERNAL USE FOR 17 HOMES

10. Place of Use:

Township	Range	Section	1/4 of	1/4	Lot	Use	Acres
02N	02W	10	NE	NE		IRR	1.0
			NW	NE		IRR	23.0

A63-20677

Page 1

Date: 02/06/90

MICROFILMED
SEP 03 1992

10. Place of Use: Continued

Township	Range	Section	1/4 of	1/4	Lot	Use	Acres
02N	02W	10	SW	NE		IRR	1.0
			SE	NE		IRR	1.0
Section Acres							26.0
Total Acres							26.0

11. Place of use in counties: CANYON

12. Do you own the property listed above as place of use? YES

13. Other Water Rights Used:

BOISE-KUNA & NAMPA-MERIDIAN IRRIGATION DISTRICTS

14. Remarks:

EACH LOT = 2 ACRES, ESTIMATED THAT 1.5 ACRES PER LOT IRRIGATED.
DOMESTIC RATE OF FLOW IS FROM IDWR DOMESTIC CHART. ACTUAL
IRRIGATION IS 25.5 ACRES IF ASSUME 1.5 ACRES/LOT IRRIGATED.
DOMESTIC USE OCCURS IN SAME QUARTER-QUARTERS AS IRRIGATION.
CLAIMANT NAME IS SUNNYRIDGE HEIGHTS PROPERTY OWNERS ASSOCIATION,
INC.

15. Basis of Claim: BENEFICIAL USE

16. Signature(s)

(a.) By signing below, I/We acknowledge that I/We have received, read and understand the form entitled "How you will receive notice in the Snake River Basin Adjudication." (b.) I/We do _____ do not X wish to receive and pay a small annual fee for monthly copies of the docket sheet.

Number of attachments: 1

For Organizations:

I do solemnly swear or affirm that I am President Richard Brooke of Sunnyside Prop. Owners that I have signed the foregoing document in the space below as President of Sunnyside Prop. Owners and that the statements contained in the foregoing document are true and correct.

Signature of Authorized Agent

President of Sunnyside Properties Owners Ass.
Title and Organization

2-23-90

Date

State of Idaho)
County of Canyon) SS.

Subscribed and sworn (or affirmed) before me this 23 day
of February 19 90

Terrell M. Horne
Notary Public

Seal

Residing at Mountain, Idaho
My Commission Expires 5-11-94




5/44

10 day 2

44

PLAT SHOWING SUNNY RIDGE HEIGHTS

IN THE
NE 1/4 OF SECTION 10, T.2N., R.2W., B.M.
CANYON COUNTY, IDAHO




Prepared by:
JOHNSON AND UNDERKOFER
Consulting Engineers
1022 12th Avenue South
Nampa, Idaho

LEGEND

- Set Brass Cap in Conc.
- Set 5/8" x 30" Rebar
- Set 1/2" x 24" Rebar
- Canal and Drain Easement
- Water Line Easement
- Utility Easement
- Building Setback Line

MICROFILMED
SEP 03 1992

CURVE DATA				
CURVE	RADIUS	DEFECT	TAN	LENGTH
C-1	20.00'	90°00'	20.00'	31.42'
C-2	339.30'	25°00'	75.00'	147.81'
C-3	358.30'	25°00'	81.65'	160.70'
C-4	358.30'	25°00'	88.30'	173.79'
C-5	715.58'	12°00'	75.00'	149.45'
C-6	743.58'	12°00'	78.15'	158.73'
C-7	773.24'	12°00'	81.31'	168.02'
C-8	804.60'	12°00'	84.47'	177.31'
C-9	834.60'	12°00'	87.63'	186.60'
C-10	864.60'	12°00'	90.79'	195.89'
C-11	80.00'	36°32'	16.87'	32.17'
C-12	50.00'	90°00'	50.00'	78.54'
C-13	50.00'	90°00'	50.00'	78.54'
C-14	71.35'	6°00'	40.84'	81.01'
C-15	358.30'	12°30'	43.62'	84.90'



05/24/2006

IDAHO DEPARTMENT OF WATER RESOURCES
PRELIMINARY RECOMMENDATION OF WATER RIGHTS ACQUIRED UNDER STATE LAW

RIGHT NUMBER: 63-20677

NAME AND ADDRESS: SUNNYRIDGE HTS PROP OWN ASSN INC
4106 JESSE LN
NAMPA ID 83686

SOURCE: GROUND WATER

TRIBUTARY:

QUANTITY: 0.380 CFS
91.800 AFY

PRIORITY DATE: 08/06/1959

POINT OF DIVERSION:

T02N R02W S10 NWNE Within CANYON County

PURPOSE AND
PERIOD OF USE:

<u>PURPOSE OF USE</u>	<u>PERIOD OF USE</u>	<u>QUANTITY</u>
DOMESTIC	01/01 12/31	0.180 CFS 10.80 AFY
IRRIGATION	03/01 11/15	0.200 CFS 81.00 AFY

Domestic use is for 18 homes.

PLACE OF USE: IRRIGATION Within CANYON County

T02N R02W S10	NENE	1.30	T02N R02W S10	NWNE	13.50
T02N R02W S10	SWNE	3.20			

DOMESTIC Within CANYON County

T02N R02W S10	NENE	T02N R02W S10	NWNE
T02N R02W S10	SWNE		

18 ACRES TOTAL

OTHER PROVISIONS NECESSARY FOR DEFINITION OR ADMINISTRATION OF THIS WATER RIGHT:

This partial decree is subject to such general provisions necessary for the definition of the rights or for the efficient administration of the water rights as may be ultimately determined by the Court at a point in time no later than the entry of a final unified decree. Section 42-1412(6), Idaho Code.

EXPLANATORY MATERIAL: BASIS OF CLAIM - Beneficial Use

Use of this right is combined with water from Nampa Meridian Irrigation District.

Use of this right is combined with water from Boise-Kuna Irrigation District.



Idaho Department of Water Resources

63-20677

T02N R02W S10



- Point of Diversion
- ▭ Place of Use
- ▭ Sections
- ▭ Quarter Quarter

Total irrigated
acres = 18



500 0 500 Feet

IDWR

Prepared by: Sandy Egbert
Date: May 24, 2006
1987 NAAP Photography

Field Exam Date 5/9/2006

STATE OF IDAHO
DEPARTMENT OF WATER RESOURCES RECEIVED
ADJUDICATION FIELD REPORT

MAY 22 2006

Prior to Field Exam

WATER RESOURCES
WESTERN REGION

- ☐ Copy of Claim, claim has been signed, sealed, and dated by notary?
- ☐ Check fees paid
- ☐ Well logs (if needed)
- ☐ Copy of topo or NAPP
- ☐ Check of Govt. Lots, if needed, Govt. Plat/Tax lot information
- ☐ Check POD & POU overlap, see below – include overlapping right for exam
- ☐ Evidence of Priority – if none, talk with claimant

CLAIMANT INFORMATION – verify contact information is complete

Claim No(s) 63 - 20677

Owner: Sunnyridge Heights Property Owners Assn., Inc. Phone No. _____

Current Address: 4106 Jesse Ln, Nampa, Id 83686 (208) 467-4176

☒ No change NAME IS THE SAME

☐ NEW OWNER

☐ No change Address

☒ NEW ADDRESS

☒ How long owned property? Katrina moved there 2 yrs. ago (plat map was not date stamped)

Accompanied by: Katrina Bowman 4213 Jesse Ln, Nampa, Id.

PRIORITY DATE 83686 (208) 442-5572 (contact person)

- ☐ No change – Complete evidence submitted or not necessary
- ☐ Incomplete – Claimant should be asked when water was first used and submit proof of date.
- ☐ Priority date is acceptable/within mandatory filing dates?

Priority date, per claimant, is: 8/6/1959

(If priority date, based on your exam, seems questionable, explain below.)

IDEQ sanitary survey shows well constructed in 1958, but no well log is available

Source: groundwater Tributary to _____

- ☐ No Change – SAME SOURCE
- ☐ Source found is different than claimed: _____

POINT OF DIVERSION

- ☒ No change
- ☐ POD found is different than claimed: _____
- ☐ If different, when did POD change? _____

DIVERSION AND DELIVERY SYSTEM

Points of Diversion:

0006659
A 0002118

ID #	Govt Lot #	1/4	1/4	1/4	Sec.	Twp.	Rge.	County	Method of Determination/Remarks GPS ID
			NW	NE	10	2N	2W	Canyon	N 43° 31.47.1 W 116.33.34.9498

Description of diverting works

8" casing, unknown depth (estimate 80' from surrounding wells)
4" discharge to 4" PVC main running north + south, on
(galvanized steel) the eastern edge of Jesse Ln + resident property lines.

OVERLAP REVIEW

Other water rights with the same point of diversion: None

Does overlap add acres or uses to existing system, increase rate of flow or volume, or other? Explain:

WATER USES

☐ No change

☒ Different Uses

Use Domestic From 01/01 To 12/31 Amount 0.18 CFS 84.0 AFA

* Use Irrigation From 3/15 To 11/15 Amount 0.48 CFS 84.0 AFA

Use _____ From _____ To _____ Amount _____ CFS _____ AFA

TOTAL VOLUME – Groundwater only

☐ Incomplete on claim, the total is, Amount _____ CFS _____ AFA

☐ Changes found, the new total is, Amount _____ CFS _____ AFA

☐ More than 1" per Acre? Yes _____ (claimant must complete excess flow sheet)

NON-IRRIGATION USES:

☒ No change

☐ Changes Exam found: Domestic # of homes _____ Stock # _____

Types _____ Additional comments: _____

PLACE OF USE:

☒ No Change

☐ Changes shown below:

Place of Use			NE				NW				SW				SE				Totals
TWP	RGE	SEC	NE	NW	SW	SE	NE	NW	SW	SE	NE	NW	SW	SE	NE	NW	SW	SE	
																			24.0

Overlap with other water rights: None

Does overlap increase rate of flow, volume, additional acres, different source for same acres? Explain:

Delivery System Narrative: 8" casing, 7.5Hp submersible well (estimating 83' depth + 50' static from IDWR well driller logs in the area) 4" galvanized steel discharge to 4" PVC main running north & south on the east side of Jesse Ln on the edge of the residents property line. Branched off to 2" PVC + 1 1/4" PVC to residents for irrigation. Each resident has their own individual sprinkling system or faucets w/ hose + sprinkler system for irrigating their lawns + gardens.

Well or Diversion Identification No GPS ID	Motor Make	Hp	Motor Serial No.	Pump Make	Pump Serial No. or Discharge size
E0006659 / A0002112	No tag		No tag	No tag	4 1/2" galvanized steel

FLOW MEASUREMENTS:

Attach appropriate documents

NARRATIVE/REMARKS/COMMENTS

This system is a regulated public water system under the jurisdiction of Garma Delmore at Southwest District Health Dept. 455-5403. A copy of their enhanced sanitary survey is attached. The current certified water system operator is Sandy Koch / Analytical Laboratories 342-5515.

An IDWR tag was issued prior to confirming one had already been issued by IDEQ (no tag was seen on the premises during the inspection).

- Supplemental water: Boise - Kuna Irrigation (some can flood irrigate with canal that runs along the east side of the subdivision, running north & south). POD is located in a cinder block housing with a flat roof, directly south of 4106 Jesse Lane (between 4106 & 4118 Jesse Ln.)
- Other contacts for this water system: Andy Housh 465-7829 & Jim Ebers 466-5342
- Two houses drilled their own wells, but not sure if they were on this water system or not, or if on this system were taken off
- Directions: I 84 to Nampa, south on 12th St past Greenhurst, east on Locust, south on Jesse Ln. (Lot 5 Block 2)

AFTER EXAM THE FILE SHOULD CONTAIN:

- ☒ Completed claim checklist
- ☒ Photographs of POD's and POU
- ☒ GPS readings
- ☒ Completed map and or GIS layout showing POD's and POU

DATE EXAM CONDUCTED: 5/22/06

FIELD EXAMINER: Sandy Hemenway

THEORETICAL PUMP FLOW CALCULATIONS

Formula:

$$Q_{cfs} = [(Hp)(8.814)(Eff)] \div [Lift + (psi \times 2.308)]$$

$$Hp = \text{Horsepower} = \underline{7.5}$$

$$Eff = \text{Efficiency} = \underline{.70} \quad (\text{Usually } 70\%)$$

$$\text{Lift: (Static Level + Assumed Draw down)}$$

$$\text{Static Water Level} = \underline{17} \text{ ft.}$$

$$\text{Assumed Draw down} = + \underline{14} \text{ ft.}$$

$$\text{Lift} = \underline{31}$$

OR

$$\text{Measured Dynamic Water Level} = \underline{\hspace{2cm}} \text{ ft.}$$

$$psi = \text{Operating Pressure} = \underline{40}^{\text{assumed}} \text{ psi}$$

$$Q_{cfs} = \left[\frac{7.5}{Hp} \times 8.814 \times \frac{.70}{Eff} \right] \div \left[\frac{31}{Lift} + \left(\frac{40}{psi} \times 2.308 \right) \right] \quad 92.32$$

$$Q_{cfs} = \left[\underline{46.2735} \right] \div \left[\underline{123.32} \right]$$

$$Q_{cfs} = \underline{.375} \text{ cfs}$$

130 gpm = 29 cfs
↓
from well log.

PERMIT NO. _____

Claim No. & Name: A63-20677 Sunnyridge Hts. Property

Date of Inspection: 5/9/2006

Field Inspector: Sandy Hemenway

Measurements/Calculations:

Irrigation:

Confirmed acres irrigated: 24.0 acres x 0.02cfs = **0.48 cfs** (see lot/house size calculations below)

Season 3/15 - 11/15 = 246 days

Required V.i.r = allowable acres under permit x requirement IDWR chart (figure 2)=

24.0 acres x 3.5 = **84.0 afa**

Potential V.d.r. = max. allowable cfs x permit season x 1.9835 =

0.48 x 246 x 1.9835 = **234.2 afa**

Well Capacity:

well depth: estimate at 83' (from IDWR Driller Reports in the area)

static: estimate at 50' (from IDWR Driller Reports in the area)

static + 10' = 60' lift

psi = estimate 40psi for irrigation, since gauge broken)

$Q = (8.8) (7.5Hp) (eff. 0.70) / (2.31) [(40psi)+(60'lift)] = 46.2/231 = 0.20 cfs$

Domestic Maximum Instantaneous Water Requirement Exhibit 12:

18 houses = **0.18cfs**

Lot Sizes from Plat Map:

Block 1	lot #1	241.68x163.77	Block 2	lot #1	236.17x146.90
	lot #2	100.00x165		lot #2	166.00x304.81
	lot #3	102.00x245.50		lot #3	335.75x165.00
	lot #4	80.00x245.50		lot #4	189.37x220.00
	lot #5	163.65x195.24		lot #5	160.63x298.10
	lot #6	159.62x274.69		lot #6	180.00x187.17
	lot #7	166.73x317.37		lot #7	190.01x307.04
	lot #8	245.43x317.37		lot #8	305.00x307.04
	lot #9	80.02x348.15			
	lot #10	327.05x315.7			

Total Property: 1,077,311.431


House Sizes from 1750-1780 Square Feet:

average 1765 sq ft x 18 homes = **31770 sq ft**

Acres Irrigated:

total square ft property 1077311.431 - sq footage for 18 homes 31770 / 43,560 = **24.0 acres**

***Looking at the capacity of the well, and the demand for domestic and irrigation, this system would need the maximum allowable amount, plus supplemental water to meet their external demand. Alternative daily watering would be highly recommended.






5/9/2006

POD:

Located on
Lot 5 Block 2
Between
4106 + 4118
Jesse Ln.
in the
"Water Line
Easement"
area



Housing
for well
(cinderblock
6'9" x 8'9" x 2'9")
above ground



Gauge shows
82 psi (no
sure if works)

undetermined
brand or
size of
pressure
tank

5/9/2006 Sunnyside Property Owners 63-20677
S.H.



63-20677 Sunnyridge Property Owners
5/9/2006 S.H.



POU:

18 houses
(connections)
2 acres
each
houses
1750-1780
sq. ft. each


4" pvc
main
running
north +
south, on
the
eastern
edge of
Jesse Ln.
& resident
property
lines
(according
to plat map)

5/9/2006 Sunnyridge Heights Property Owners 63-20677
S.H.

Idaho Department of Water Resources

Claim Number: 63-20677
Legal: T02N, R02W, S10
Reviewed By:

-  Point of Diversion
-  Place of Use
-  Section Lines
-  Quarter Quarter Lines





10

● = POD □ = outlined area is POD
 = Not POD

63-20677 Sunnyside Property Owners

Contact Person: Katrina Bowman
4213 Jesse Ln,
Nampa, Id. 83686
(208) 442-5572

Southwest District Health (Idaho PHD #3)

Sanitary Survey Report for Public Drinking Water Systems

SYSTEM ADMINISTRATIVE INFORMATION		PWS Number: 3140122
System Name: Sunnyridge Property Owners		County: Canyon
System Contact: Jim Ebberts		Contact Phone: Kim - 941-0469 / 466-5342
System Contact Address: 3914 Jessie Lane, Nampa, Idaho 83686		
Location of System: Lot 5 Block 2		
Legally Responsible Party: Sunnyridge Property Owners		
Population Served: 53	Number of Connections: 18	Water Rates: \$ 15/ month
SANITARY SURVEY INFORMATION		
Information obtained from: Jim Ebberts		Date of Survey: January 10, 2002
System Representative(s): Jim Ebberts		
Last Sanitary Survey Report Dated: May 5, 1994		Other:
Deficiencies shown on last survey report: 1. NO2/NO3 overdue 2. PbCu overdue		
Inspector: Jami Delmore		

2 private wells drilled - so
they might not be on system
any longer
(possibly 16
connections)
not sure

SERVICE INFORMATION
Violations, MCL, SNC: None
Complaints (Quality, Pressure): None
Certified Operator (Name, Date certified): Jim Ebberts (grandfathered)
Certified Operator Mailing Address: same as contact
Water Usage (MGD): ?
Water Production (MGD): ?

Notes:

Under *Water Usage*, write down "Actual Daily Demand", "Average Daily Demand", and "Maximum Daily Demand" if known.

Under *Water Production*, write down "Actual Daily Production", "Average Daily Production", and "Total Design Production Capacity" if known.

Service Information and Survey Findings

System Name: Sunnyridge Property Owners

PWS No: 3140122

DISTRIBUTION SYSTEM

Looped? No	Meters? No	# of hydrants? None	Pressure Reducing Valves? None
Pressure:	Static (psi):	Operating (psi):	Min. > 20 psi? <i>gauge showed 82 psi</i>
Booster stations? None	How many? <i>(circled)</i>	Output (gpd)?	Horsepower of each? <i>(possibly broken)</i>
Water main size(s): 3/4" 1" 1 1/4" <u>1 1/2"</u> 2" 2 1/4" 2 1/2" 3" 4" 6" 8" 10" 12"			
Water main type: <u>Galvanized Steel</u> Ductile Iron PVC Copper Other:			
Frequency of water main breaks: Longer than 5 years ago		Mains disinfected after service? Yes	
Valve maintenance program? No	Flushing program? No	Cross-connection control program? No	Map of system available? No

Comments?

REQUIREMENTS

1. Above ground check valve.
2. Flow meter.
3. Blow out valves at the "dead end(s)" of the main lines.

RECOMMENDATIONS

1. Consider hiring an engineer to re-design well house. There is no easy way to maintain pressure tank and lines when they are buried in concrete. A major change of this type would require prior approval of DEQ. If a serious problem develops, there could be a major delay in repairing problem due to the time it would take to remove concrete. Also, there is a risk of further damage as the concrete was being excavated.

COMMENTS

- ☐ New pump and some pipes changed about 6 months before. (Davis Well Drilling normally does maintenance.)

*should be
4" PVC
reducing
to 2" PVC
then
1 1/4" to
residents*

Groundwater Source

System Name: Sunnyridge Property Owners

PWS No: 3140122

WELL LOT	Location: Lot 5 Block 2 <i>between 4106 + 4118 Jesse Ln</i>		Adequate well lot? <i>N/A on water line easement</i>
Fenced and locked? No	Safe from flooding? Yes	Safe from fire? Yes	Lot Ownership? Easement
Distance to nearest:	Septic system: 100'	Sewer line (50'): N/A	Livestock (50'): >300
	Surface water: >200	Contaminated storage: None known	Other:

BUILDING	Size (W*L*EaveHt): 6'9" x 8'9" x 2'9"		Material: Concrete
Structurally safe? Yes	Safe from fire? Yes	Yard Lighting? No	Locking door? Yes
Ventilation? No	Heating? No	Floor drain? No	To sump? No
Indoor lighting? No	Roof Hatch? Yes	Non-potable storage? No	
Fire extinguisher? No	Safe and clean? Yes	Comments: Pipe opening (overflow?)	

Tag # A0002112 +

WELL HEAD	Tag number: E0006659	In well field, how many wells?	
Back-up source? No	Back-up power? No	Well head seal? Yes	Pitless adapter? No
Well casing:	Diameter: 8"	6" above floor? 35"	12" above ground? Yes
Casing vent:	Downturned? No	Screened? Ripped	18" above ground? Yes
Well log? No	Date constructed: 1958	Depth of well: Unknown	Depth of screen: Unknown
	Static water level: Unknown	Well capacity (gpd): Unknown	Surface seal depth: Unknown
Comments:			

4"

DISCHARGE LINE	Pipe size (in): 4 1/4"	Material: Galvanized Steel	Isolation valve? Yes
Flow meter? <i>No Yes</i>	Pressure gauge? Yes	Sample tap? No	Check Valve? No
Pressure relief valve? No	Pump-to-waste connection? No		Surge Valve? No
Pump control valve? Unknown	Air relief (vacuum) valve? (required for turbine pumps) None		

dedicated location on plat map

Meter Read 46704.1 gallons

Groundwater Source

System Name: Sunnyridge Property Owners

PWS No: 3140122

PUMP(S)			
Pump type:	Submersible? Yes	Turbine?	Other:
Pump info:	Brand: Unknown	Horsepower: 7.5	Output (gpm): Unknown
Drawdown (ft): Unknown	Variable power supply?	Depth of pump (bowl) setting (ft):	
Turbine pumps only:	Type of lubrication:	Water pre-lube?	Food grade oil?

BLADDER PRESSURE TANK(S) N/A			
Brand:	Model:	Rated Pressure (psi):	How many?
Brand:	Model:	Rated Pressure (psi):	How many?
Cycle rate (<10-15/hr):	Excessive?	Tanks properly supported?	Tanks in good condition?

NON-BLADDER PRESSURE TANK(S) Buried in concrete			
Volume (gal): Unknown	Volume 10 times pump capacity? Unknown	Rated pressure (psi): Unknown	
Appurtenances: Unknown	Sight glass? No	Air compressor? Unknown	Drain? Unknown
Cycle rate (<10-15/hr): Unknown	Excessive?	Tank properly supported?	Tank in good condition? Unknown
Requirements for systems built after 1985:		ASTM stamp?	Air relief valve?

NON-SWTR WATER TREATMENT N/A			
Reason for treatment:	Taste/odor?	Corrosion control?	MCL violation?
	Other:	Description:	
Treatment method:	Oxidation?	Filtration?	Ion exchange?
	Chemical passivation?	Sequestering?	Aeration?
	Membrane (RO)	Carbon adsorption?	
Operation:	Chemical/media used?	Point of application:	Dosage?
Maintenance:	Qualified personnel?	Contract?	Frequency?
Monitoring:	Parameter:	Frequency:	Records?
Process performing adequately?		Equipment in good condition?	

replaced w/ pressure tank (unable to read model # + brand name)

Groundwater Source

System Name: Sunnyridge Property Owners

PWS No: 3140122

DISINFECTION FOR GW SOURCES N/A			
Disinfectant used:	Gas Chlorine?	Hypochlorite?	Other:
Purpose:	Taste and odor control?	System protection?	Other:

GAS CHLORINATION N/A		Is chlorine gas used as a disinfectant?	
Venting:	Discharge fan near floor?	Discharge above grade & outside?	Discharge isolated from other vents?
	Inlet vent near ceiling?	All vents louvered?	One complete air change per minute?
Cylinders:	Chained?	Scales provided?	Auto switchover?
	Flow proportioning?		
Building:	Separated, sealed room?	Inspection window on door?	Warning sign on door?
	Fan/light switches outside?	Panic hardware?	Wind sock?
	Room heated?	Isolated floor drain?	All gas lines within disinfection room?
Emergency response:	Notify Fire Dept?	Trained personnel?	Leak repair kit for ton cylinders?
Standby equipment ready?		Other:	

SWTR HYPOCHLORITE DISINFECTION N/A		Is hypochlorite used as a disinfectant?	
Type of disinfectant:	Sodium hypochlorite (liquid)?	Calcium hypochlorite (solid)?	On-site generation?
	Brand:	Concentration(%):	
Feeder control:	Manual?	Automatic?	Proportioning?
Siphon control:	Positive pressure?	Vacuum relief?	Air gap?
Day tanks:	Capacity (<30 hrs):	Level gauge?	Covered?
Building:	Separate room?	Warning sign on door?	Kept dry?
	Room heated?		
Standby equipment ready?		Other:	

Storage and Distribution

System Name: Sunnyridge Property Owners


PWS No: 3140122

STORAGE FACILITY N/A			Location:	
Type:	Elevated?	Height:	Surface?	Buried?
Capacity (gal):	Material: Steel	Concrete	Wood	Other:
Year constructed:	Configuration:	Floats on system?	Flow through?	
Overflow?	Terminates at least 6" above ground?		Safe discharge?	Screened?
Ladder?	10' above ground?		Restricted access?	Good condition?
Vent downturned?	Screened?		Access hatch seal tight and overlapping?	
Tank coating:	Good condition?	NSF approved?	Type:	
Pump in reservoir?	Horsepower:	Output (gpm):	Ladder in tank?	
Drain?	No connection between sewer and drain?			Above grade?
Isolation valve?	Cleaning frequency:	Disinfected after service?	Cracks or openings?	
Comments:				




Sunnyridge Property Owners
PWS #3140122


Well house



Discharge Line/Valve
Power Box



Well
Discharge line




Pipe outlet
Overflow?




Isolation valves for
distribution lines



Well



Power Box
Discharge line



Pressure Valve

Old pump

Part of ladder

PLAT SHOWING SUNNY RIDGE HEIGHTS

IN THE
NE 1/4 OF SECTION 10, T.2N., R.2W., B.M.
CANYON COUNTY, IDAHO

200 150 100 50 0 100 200
SCALE IN FEET

Prepared by:
JOHNSON AND UNDERKOFFER
Consulting Engineers
1022 12th Avenue South
Nampa, Idaho

LEGEND


- Set Brass Cap in Conc.
- Set 5/8" x 30" Rebar
- Set 1/2" x 24" Rebar
- Canal and Drain Easement
- Water Line Easement
- Utility Easement
- Building Setback Line

SUNNY RIDGE
ROAD
N 0° 15' E
1322.4'

BASIS OF BEARING



CURVE	RADIUS	DEFLECT	TAN	LENGTH
C-1	80.00'	80° 00'	78.00'	31.42'
C-2	324.30'	28° 00'	78.00'	147.41'
C-3	348.30'	28° 00'	81.43'	160.70'
C-4	368.30'	28° 00'	84.85'	169.70'
C-5	388.30'	28° 00'	88.27'	178.94'
C-6	408.30'	28° 00'	91.69'	188.18'
C-7	428.30'	28° 00'	95.11'	197.42'
C-8	448.30'	28° 00'	98.53'	206.66'
C-9	468.30'	28° 00'	101.95'	215.90'
C-10	488.30'	28° 00'	105.37'	225.14'
C-11	508.30'	28° 00'	108.79'	234.38'
C-12	528.30'	28° 00'	112.21'	243.62'
C-13	548.30'	28° 00'	115.63'	252.86'
C-14	568.30'	28° 00'	119.05'	262.10'
C-15	588.30'	28° 00'	122.47'	271.34'



Fee: _____

Receipt No.: 2794

Date: 4-9-87

SOUTHWEST DISTRICT HEALTH DEPARTMENT
INDIVIDUAL SUBSURFACE DISPOSAL FORM

Installation shall comply with all requirements of Health District
and/or State of Idaho Sewage Disposal Rules, Regulations and Standards. 6+5B2

Application: _____

Property owner: Reed Robert

Address: 4116 Sossie Ln

New ☐ Replacement ☒ Lot size _____

of Bedrooms 4 Septic tank 1000 gal

Effective area 300 sq. ft.

Type: Trench ☒ Bed ☐ Pit ☐ R.S. ☐ Mod ☐

Soil textural classification A

Soil profile provided 105

Static water table depth 010 ft.

Depth to lava 010 ft.

Water supply: Private ☐ Public ☒

Installer: Gene Thompson

Applicant: Gene Thompson

(signature)

Permit: Issued ☒ By Gene Thompson

Date 4/14/87

Inspection report:

Septic tank 27.5 gal Mfr 1

Stand pipe 24" Manhole depth 36 ins

Absorption area & dimensions 300' x 2'

Gravel 14 yds Depth under pipe 3 ft/in

Depth to pipe 3.5 ft/in

Installer: Gene Thompson

Inspected by Gene Thompson

Complies with minimum requirements ☒

Date 4/14/87

Remarks: CALL FOR TEST HOLE INSPECTION
APPOINTMENT—

Caldwell 459-0744 Payette 642-9321
Emmett 365-6371 Weiser 549-2370


The size of the drainfield will be
determined at the time the test hole is
inspected.

Legal description


South of house and East of Sossie Ln

Site location

Diagram showing location & dimensions



MAY 11 1987



**Southwest District
Health Department**
920 Main Street
Caldwell, Idaho 83605

Caldwell 454-7608
Payette 642-9321
Murphy 495-2421
Nampa 465-8402

Emmett 365-6371
Weiser 549-2370
Homedale 337-4641

JUN 22 1995

For Office Use Only
Document Number 10334

Site Eval. Charge _____
Receipt # _____
Date _____

Permit Fee 90
Receipt # 12736
Date 6/21/95

Legal Description T2N R2W Sec 10 Sunnyridge
Site Location: South on Power line to Locust
W on Locust to Jesse Ln
(Between Sunnyridge and power line)

**INDIVIDUAL SUBSURFACE SEWAGE
DISPOSAL APPLICATION/PERMIT**

Property Owner Le Dell Stevenson
Property Address 4109 Jesse Ln
City Nampa County 1400
Phone 467 7100
Applicant Signature [Signature]
☐ New ☒ Replacement Lot Size A+
of Bedrooms 3 Flow 250 Gal. (300)
Septic Tank 1000 Eff. Area 400 Sq.Ft.
Type: ☒ Standard ☐ Alternate ☒ Bed
☐ Trench ☐ Pit ☐ Other
Soil Texture Classification: a2B
Test Hole Evaluation Results:

0-5 - Tight Soil (silt + Hard pan)

5 → a2B

*Back w/ sand to 6" of pipe *

Drainfield Distance from Adjacent Wells Community ft.
Distance to Temporary Surface Water 50' ft.
Distance to Permanent Surface Water >300' ft.
Static Water Table Depth >10' ft.
Licensed Installer NDIS (5094)
Site Evaluation Inspection:

[Signature] 011 6-29-95
EHS Signature EHS Code Date


The size of the drainfield will be determined at the time of the site inspection.

Septic Tank: 1000 gal. Mfr. Existing
Standpipe _____ manhole depth 24" ins
Absorption area: 420 sq.ft.
Dimensions: Width 12' ft. Length 35' ft.
Gravel: 13 yds Depth under pipe 6" ft./in.
Depth to pipe 60" ins. Dist. to well >100' ft. (Community)
Licensed installer
or owner installed N. DRAIN / [Signature]
Final EHS Approval

[Signature] 011 6-29-95
EHS Signature EHS Code Date

Date	<u>6-29-95</u>	<u>6-29-95</u>	
Travel	<u>020</u>	<u>030</u>	
Inspect	<u>015</u>	<u>030</u>	

Permit Issued [Signature] 011 6-29-95
EHS Signature EHS Code Date
This application must be signed by a licensed Environmental Health Specialist before it is considered a valid permit.
(Valid for 1 year)



Jessie Ln
[Signature] well
Variance granted due to depth of existing system
Remarks: 12' x 34' Req. - will back fill
w/ sand to within 6" of pipe.
Sand was not possible

Installation shall comply with all applicable rules, regulations, and standards.
NOTE: This is not a building permit, a building permit may be required by the County or City.

S WEST DISTRICT HEALTH DEPT. MENT
INDIVIDUAL SUBSURFACE DISPOSAL FORM

Installation shall comply with all requirements of Health District
and/or State of Idaho Sewage Disposal Rules, Regulations and Standards.

Application:

LL B1 Sunnyridge Hts
Legal Description

Name George Cotton

Address 4119 Jessie Lane Nampa

New ☐ Replacement ☒ Lot size

Funding: Govt. Covent. Other

of bedrooms 3 Septic tank gal.

Effective area sq.ft.

Type: Trench Bed Pit ☒ R.S. Mod.

Percolation rate min./inch

Soil profile provided

Static water table depth ft.

Depth to lava ft.

Water supply: Private Public ☒

Installer

Applicants signature

Site Location

Diagram showing location & dimension

For Health Dept. Use Only

Permit issued ☐ by:

Date:

Inspection report:

Bill Pd. Rect. # No fee

Billing address

Septic tank existing gal. Manfg.

Stand pipe Manhole depth inches

Absorption area & dimensions (if other than
above) 400 ft²

Gravel 26 yds. Depth under pipe 10 ft./in.

Depth to pipe 4 ft./in.


Installer

Inspected by

Complies with minimum requirements

Date 10/5/83

Remarks:



FIELD EXAM REQUEST

Water Right No. 63-20677 and a little information about 63-7717

Claimant: Sunnyridge Heights Property Owners
Sunnyridge Sub

*made separate, since
exams could not be
scheduled in the same
day*

POD:

Verify location of POD – mark any corrections on map
What is the capacity of the system?

POU:

Verify POU – mark any corrections on map
Verify irrigated acres *2 acre lots*

PONDS:

None

EVIDENCE OF PRIORITY:

I have evidence in file

OTHER QUESTIONS:

supplemental water:

Are they using any surface water

Flood irrigate w/ Boise Keena Irrigation

Verify number of homes on the system – they claimed 17 homes

Is irrigation just lawns or other areas too?

*canal runs along
east side of subdivision
running north + south*

*verified
annually
w/DEQ
fee assessments
to be 18 connections (homes)*

While you are in the area I need a little information on 63-7717. It is licensed for 2 points of diversion in the same QQ but the claim says there is only 1 POD. Could you find out which is correct? According to the tax lot data Mr. Castagneto still lives at the same address. I tried to call but they haven't returned my call. You don't need to take any measurements – I just need to know how many wells and where they are.

RETURN TO SANDY E.

L PROPERTY INQUIRY

```
+++++
01 6R27114-001- -0 208-00 N SCH131+ 25 .01
+++++
SUNNYRIDGE SUB #2 WATER CORP +
+
+
+
+
4013 IVY DR +
NAMPA ID 83686 +
+++++
10-2N-2W NW SUNNY RIDGE SUB #2 8245 + TOTAL .01
WELL LOT ++++++
+ SURVEY INST
+ DRAIN DR VALUE APPR SAM
+ CLASS REAP 01 MAN UNIT 0
FLETCHER DR, NA Pg 140 + PARCEL 6R08245000WLT0 H/O N C/B N
+ PRIOR ACCOUNT 5R27114-001- -0
+ 02 MH on Property NO
MODE:F ACTION: COMPANION SHEET INQUIRY TRQK361

01 ACCOUNT: 6R27114-001- -0 AREA 208-00 DRAIN VALUE CLASS H/O N
SEC 10 TWN 2N RNG 2W QTR NW CITY/SUB 08245 BLK 000 LOT WLT0
OWNERSHIP MUST BE 'C' FOR CURRENT OR 'P' FOR PREVIOUS
OWNERSHIP C OWNERSHIP P
SUNNYRIDGE SUB #2 WATER CORP

MAILING ADDRESS LEGALS
4013 IVY DR 10-2N-2W NW SUNNY RIDGE SUB #2 8245
NAMPA ID 83686 WELL LOT
SITE ADDRESS
FLETCHER DR NA
COMMENTS REMARKS

PRIOR ACCOUNT 5R27114001 0
PARCEL 08245000WLT0 SRVY
INSTR ACRES .01
SPLIT YR DOCUMENT
```

L PROPERTY INQUIRY

```

+++++
01 6R27170-000- -0 208-00 N SCH131+ 25 .63
+++++
SUNNYRIDGE SUB #3 WATER CORP +
+
+
+
+
4013 IVY DR +
NAMPA ID 83686 +
+++++
10-2N-2W NW SUNNY RIDGE SUB #3 8247 + TOTAL .63
WELL LTS 1 & 2 ++++++
+ SURVEY INST
+ DRAIN DR VALUE APPR SAM
+ CLASS REAP 01 MAN UNIT 0
FAIR LN, NA Pg 176D + PARCEL 6R08247WLT0010 H/O N C/B N
+ PRIOR ACCOUNT 5R27170-000- -0
+ 02 MH on Property NO
MODE:F ACTION: COMPANION SHEET INQUIRY TRQK361

01 ACCOUNT: 6R27170-000- -0 AREA 208-00 DRAIN VALUE CLASS H/O N
SEC 10 TWN 2N RNG 2W QTR NW CITY/SUB 08247 BLK WLT LOT 0010
OWNERSHIP MUST BE 'C' FOR CURRENT OR 'P' FOR PREVIOUS
OWNERSHIP C OWNERSHIP P
SUNNYRIDGE SUB #3 WATER CORP

MAILING ADDRESS LEGALS
4013 IVY DR 10-2N-2W NW SUNNY RIDGE SUB #3 8247
NAMPA ID 83686 WELL LTS 1 & 2
SITE ADDRESS
FAIR LN NA
COMMENTS REMARKS

PRIOR ACCOUNT 5R27170000 0
PARCEL 08247WLT0010 SRVY
INSTR ACRES .60
SPLIT YR DOCUMENT

```

IDAHO DEPARTMENT OF WATER RESOURCES
ADJUDICATION CLAIM POU REVIEW REPORT
ADJUDICATION CLAIM NUMBER: 63-20677

03/30/2006

1

Right #	Type	Twp	Rge	Sec	QQ	Q	Lot	Purpose of Use	Acres/Total	Name
4806	Claim	02N	02W	10	NE	NE		IRRIGATION	1/5	AFINE RELK
20677	Claim	02N	02W	10	NE	NE		IRRIGATION	1/26	SUNNYRIDGE HTS PROP OWN ASSN II
28271	Claim	02N	02W	10	NE	NE		IRRIGATION	5/5	M CHARLENE MORGAN
4878	Water Right	02N	02W	10	NE	NE		IRRIGATION	3/3	GENE E CLARK
4878	Claim	02N	02W	10	NE	NE		STOCKWATER		GENE E CLARK
20448	Water Right	02N	02W	10	NE	NE		STOCKWATER		AFINE RELK
25869	Water Right	02N	02W	10	NE	NE		STOCKWATER		SUSAN J TACKETT
26201	Water Right	02N	02W	10	NE	NE		STOCKWATER		JO ANNE KAY ANDERSON
27376	Water Right	02N	02W	10	NE	NE		STOCKWATER		JEFF CUNDIFF
27680	Water Right	02N	02W	10	NE	NE		STOCKWATER		AARON E DANIEL
28261	Water Right	02N	02W	10	NE	NE		STOCKWATER		NEWELL T MORGAN
4878	Claim	02N	02W	10	NE	NE		DOMESTIC		GENE E CLARK
20448	Water Right	02N	02W	10	NE	NE		DOMESTIC		AFINE RELK
23995	Water Right	02N	02W	10	NE	NE		DOMESTIC		WILBUR T MONROE
25869	Water Right	02N	02W	10	NE	NE		DOMESTIC		SUSAN J TACKETT
25989	Water Right	02N	02W	10	NE	NE		DOMESTIC		ROY H PIERCE
26201	Water Right	02N	02W	10	NE	NE		DOMESTIC		JO ANNE KAY ANDERSON
26930	Water Right	02N	02W	10	NE	NE		DOMESTIC		VEARL G WOLFE
27376	Water Right	02N	02W	10	NE	NE		DOMESTIC		JEFF CUNDIFF
27537	Water Right	02N	02W	10	NE	NE		DOMESTIC		O KENT LEONARD
27680	Water Right	02N	02W	10	NE	NE		DOMESTIC		AARON E DANIEL
28261	Water Right	02N	02W	10	NE	NE		DOMESTIC		NEWELL T MORGAN
4806	Claim	02N	02W	10	NW	NE		IRRIGATION	4/5	AFINE RELK
20677	Claim	02N	02W	10	NW	NE		IRRIGATION	23/26	SUNNYRIDGE HTS PROP OWN ASSN II
4806	Water Right	02N	02W	10	NW	NE		IRRIGATION	5/5	JOHN RELK
23169	Water Right	02N	02W	10	NW	NE		STOCKWATER		EDNA E ALLEN
23169	Water Right	02N	02W	10	NW	NE		DOMESTIC		EDNA E ALLEN
4710	Claim	02N	02W	10	SW	NE		IRRIGATION	3/3	MARGARET R DROULARD

IDAHO DEPARTMENT OF WATER RESOURCES
ADJUDICATION CLAIM POU REVIEW REPORT
ADJUDICATION CLAIM NUMBER: 63-20677

03/30/2006

2

Right #	Type	Twp	Rge	Sec	QQ	Q	Lot	Purpose of Use	Acres/Total	Name
20677	Claim	02N	02W	10	SW	NE		IRRIGATION	1/26	SUNNYRIDGE HTS PROP OWN ASSN II
23721	Claim	02N	02W	10	SW	NE		IRRIGATION	2.3/2.3	PATRICIA L PACKARD
4710	Water Right	02N	02W	10	SW	NE		IRRIGATION	3/3	MARGARET R DROULARD
23721	Claim	02N	02W	10	SW	NE		STOCKWATER		PATRICIA L PACKARD
23520	Water Right	02N	02W	10	SW	NE		STOCKWATER		ELISABETH ILIN
26120	Water Right	02N	02W	10	SW	NE		STOCKWATER		TAMARA BUSNARDO
26979	Water Right	02N	02W	10	SW	NE		STOCKWATER		ROMOLO BUSNARDO
28091	Water Right	02N	02W	10	SW	NE		STOCKWATER		JAMES M HILL
28215	Water Right	02N	02W	10	SW	NE		STOCKWATER		DARLENE NELSEN
4710	Claim	02N	02W	10	SW	NE		DOMESTIC		MARGARET R DROULARD
23721	Claim	02N	02W	10	SW	NE		DOMESTIC		PATRICIA L PACKARD
5042	Water Right	02N	02W	10	SW	NE		DOMESTIC		NAMPA SCHOOL DISTRICT # 131
23520	Water Right	02N	02W	10	SW	NE		DOMESTIC		ELISABETH ILIN
26120	Water Right	02N	02W	10	SW	NE		DOMESTIC		TAMARA BUSNARDO
26257	Water Right	02N	02W	10	SW	NE		DOMESTIC		FREDRIC BIRKELAND
26405	Water Right	02N	02W	10	SW	NE		DOMESTIC		DOUGLAS J GARDNER
26571	Water Right	02N	02W	10	SW	NE		DOMESTIC		BOBBY J DOTY
26979	Water Right	02N	02W	10	SW	NE		DOMESTIC		ROMOLO BUSNARDO
27405	Water Right	02N	02W	10	SW	NE		DOMESTIC		HELEN L HEATH
28091	Water Right	02N	02W	10	SW	NE		DOMESTIC		JAMES M HILL
28215	Water Right	02N	02W	10	SW	NE		DOMESTIC		DARLENE NELSEN
20677	Claim	02N	02W	10	SE	NE		IRRIGATION	1/26	SUNNYRIDGE HTS PROP OWN ASSN II
12512	Water Right	02N	02W	10	SE	NE		IRRIGATION	2.6/2.6	DAVID L DYKSTRA
26198	Water Right	02N	02W	10	SE	NE		STOCKWATER		BARBARA ALDRICH
27009	Water Right	02N	02W	10	SE	NE		STOCKWATER		DOLORES J ALDRICH
28646	Water Right	02N	02W	10	SE	NE		STOCKWATER		RICHARD T RAWLINGS
20586	Water Right	02N	02W	10	SE	NE		DOMESTIC		THOMAS R WASKOW
20760	Water Right	02N	02W	10	SE	NE		DOMESTIC		PATRICIA M JONES

IDAHO DEPARTMENT OF WATER RESOURCES
ADJUDICATION CLAIM POU REVIEW REPORT
ADJUDICATION CLAIM NUMBER: 63-20677

03/30/2006

3

Right #	Type	Twp	Rge	Sec	QQ	Q	Lot	Purpose of Use	Acres/Total	Name
26198	Water Right	02N	02W	10	SE	NE		DOMESTIC		BARBARA ALDRICH
27009	Water Right	02N	02W	10	SE	NE		DOMESTIC		DOLORES J ALDRICH
27712	Water Right	02N	02W	10	SE	NE		DOMESTIC		G EDWARD LINDHOLM
28310	Water Right	02N	02W	10	SE	NE		DOMESTIC		DARLENE J MATHEWS
28646	Water Right	02N	02W	10	SE	NE		DOMESTIC		RICHARD T RAWLINGS
29730	Water Right	02N	02W	10	SE	NE		DOMESTIC		TRACY W MORTENSON

RECEIVED

SEP 13 1995

WATER RESOURCES
WESTERN REGION

Sept. 12, 1995

*Department Of Water Resources
Western Region
2735 Airport Way
Boise, ID 83705-5082*

To Whom It May Concern:

In regards to Claim # A63-20677, I have inclosed a copy of the Well Log And Report which states the date the well was completed. To the best of my knowledge the well drilled has been used for the seventeen homes on Jessie Lane as well as the twenty six acres of irrigation water.

*Thank You,
LaDelle Stephenson*

A handwritten signature in cursive script that reads "LaDelle Stephenson". The signature is fluid and matches the typed name above it.

*LaDelle Stephenson
Sectretary/Sunnyridge Heights Prop. Owners Assn. Inc
4109 Jessie Lane
Nampa, ID 83686*

RECEIVED
SEP 13 1995WATER RESOURCES
WESTERN REGIONWELL LOG AND REPORT OF THE
STATE RECLAMATION ENGINEER OF IDAHORECEIVED
JAN 28 1960
Department of ReclamationPermit No. _____ Well No. _____ County CanyonOwner Kenneth DroulandAddress Sunny Ridge Subdivision Nampa Rt. # 4Driller Marlin WittAddress Nampa, Idaho *Dave Marlin Witt 466-9667*Well location 14 1/4 - 15 1/4 Sec. 10, T. 2 N/S, R. 2 E/WSize of drilled hole 8"

Locate well in section

NW 1/4	NE 1/4
SW 1/4	SE 1/4

Total depth of well 215Give depth to standing water from the ground 17' Water temp. _____ °Fahr.On "Pumping Test" delivery was 130 g.p.m. or _____ c.f.s. Drawdown was 14 feet.Size of pump and motor used to make test Air CompressorLength of time of test 4 hours _____ minutes.

If flowing well, give flow _____ c.f.s. or _____ g.p.m. and of shut off pressure _____

If flowing well, described control works _____

(TYPE AND SIZE OF VALVE, ETC.)

Water will be used for subdivisionWeight of casing per lineal foot 28.55 lbs.Thickness of casing 3/32 Casing material Steel

(STEEL, CONCRETE, WOOD, ETC.)

Diameter, length and location of casing 8" x 200 0 - 200(CASING 12" IN DIAMETER OR LESS, GIVE INSIDE DIAMETER;
CASING OVER 12" IN DIAMETER, GIVE OUTSIDE DIAMETER)

CASING RECORD

Diam. Casing	From Feet	To Feet	Length	Remarks—seals, grouting, etc.
8"	0	200	200	Sealed in clay --- 8" x 10' screen in the bottom, sealed with lead packer

Number and size of perforations _____ located _____ feet to _____ feet from ground

Date of commencement of well _____ Date of completion of well 7/16/59



State of Idaho

DEPARTMENT OF WATER RESOURCES

Western Region, 2735 Airport Way, Boise, Idaho 83705-5082 - (208) 334-2190

FAX (208) 334-2348

PHILIP E. BATT
GOVERNOR

KARL J. DREHER
DIRECTOR

July 7, 1995

A63-20677
SUNNYRIDGE HTS PROP OWN ASSN 1
C/O 4106 JESSE LANE

Re: Claim No(s). A63-20677

NAMPA

ID 83686

Dear Claimant(s):

In the past, you submitted the above referenced claim(s) in the Snake River Basin Adjudication. Enclosed is a computer generated print-out of the claim(s) for your reference only; this print-out is **NOT** to be returned or re-filed. You have indicated when this claim was filed that the water right(s) was based on either a "Statutory Claim" or "Beneficial Use" of the water. Water rights of this type are established by the historical use of water for a beneficial purpose, dating back to the time the water was first used, this date being the "Priority Date" as shown on the enclosed print-out. Your claim(s) has not been confirmed by a previous filing with the Department of Water Resources since there is no decree, license, or permit on file to verify the use of this water. For this reason, the Department is under a legal requirement to gather evidence from claimants supporting the date of priority for claims based on historical beneficial use of water. Any other claims you may have filed, that are not listed above, do not require evidence of priority be submitted at this time.

Enclosed is a pamphlet entitled "Evidence of Priority" which describes why evidence of the priority date is necessary along with examples of types of evidence that can be submitted to fulfill this requirement. If no evidence is submitted, or we do not hear from you within the time limit below, your priority date, as claimed, may not be recommended to the Court for decree. This could jeopardize your water use under this right(s), if water availability problems arise in the future. It is our goal to decree the historical water rights within the Snake River Basin as accurately as possible. Field exams to verify claims in this area are now being conducted by Department personnel. Please contact this office as soon as possible to schedule a field exam appointment convenient for you.

The required evidence supporting the priority date(s) must be submitted by September 1 1995, referencing all documents with the corresponding claim number(s). If you have any questions not covered by this letter, or the enclosed pamphlet, please call the Western Region office shown above.

Adjudication Section
Department of Water Resources
Western Region Office

lh
Enclosures

9-12-95
Lic. of Assn.
called - will submit
copy of well log
& personal statement
of her knowledge
of use of
well - kw