



State of Idaho

DEPARTMENT OF WATER RESOURCES

Northern Region, 7600 N. Mineral Drive, Suite 100 • Coeur d'Alene, Idaho 83815

Phone: (208) 762-2800 • Fax: (208) 762-2819 • Web Site: www.idwr.idaho.gov

C. L. "BUTCH" OTTER
Governor

DAVID R. TUTHILL, JR.
Director

June 12, 2009

Hayden Village LLC
14816 Jadestone Dr
Sherman Oaks CA 91403

COPY

Re: Notice of Claim No. 95-10644

Dear Mr. Glickman:

After the initial review of the Notice of Claim submitted to the Department for the farm house on the Hayden Village property, it was found that the quantity of water claimed in items 6 & 7 were left blank. Because your Notice of Claim is a legal document, the Department cannot complete these items for you.

Please enter an amount in cfs (cubic feet/second) in items 6 and 7, initial the changes and send the Notice back to this office. The driller's report estimated a rate of 0.04 cfs.

Also, a priority date of 4/15/1965 was claimed but the driller's report attached to the Notice says the well was completed on 9/25/1978. In order for the Department to recommend a 1965 priority we will need evidence or an explanation of this discrepancy.

Please do not hesitate to contact this office if you have any questions regarding this matter.

Sincerely,

Gregory J. Taylor
Stream Channel Protection Specialist

COPY

IN THE DISTRICT COURT OF THE FIFTH JUDICIAL DISTRICT OF THE STATE OF IDAHO, IN AND FOR THE COUNTY OF TWIN FALLS

IN RE THE GENERAL ADJUDICATION
OF RIGHTS TO THE USE OF WATER FROM
THE COEUR D' ALENE-SPOKANE RIVER
BASIN WATER SYSTEM

CIVIL CASE NUMBER: 49576

Ident. Number 75-10644Date Received: 6/8/09Receipt No: 11020 847Received By: AT.

NOTICE OF CLAIM TO A WATER RIGHT ACQUIRED UNDER STATE LAW

Please type or print clearly

1. Name of Claimant (s) [REDACTED] / Hayden Village, LLC Phone (818) 784 9114
 Mailing Address 14816 Jadestone Dr. Sherman Oaks CA ZIP 91403
Street or Box City State
 2. Date of Priority (Only one (1) per claim) 4/15/1965
Month Day Year (YYYY)

3. Source of water supply (Check one) Ground Water (✓) or Other () (a) _____
 which is tributary to (b) Spokane River

4. a. Location of Point of Diversion is: Township 51N, Range 4W, Section 2,
SE, 1/4 of SE, 1/4 Govt. Lot _____, BM., County of Kootenai

Parcel (PIN) no. 049510020020

Additional points of diversion if any: _____

If available, GPS Coordinates 515776 E, 5292623N

b. If instream flow, beginning point of claimed instream flow is:

Township _____, Range _____, Section _____, _____, 1/4 of _____, 1/4

Govt. Lot _____, BM., County of _____

ending point is: Township _____, Range _____, Section _____, _____, 1/4 of _____, 1/4

Govt. Lot _____, BM., County of _____

5. Description of existing diversion works (Dams, Reservoirs, Ditches, Wells, Pumps, Pipelines, Headgates, Etc),
including the dates of any changes or enlargements in use, the dimensions of the diversion works as constructed
and as enlarged and the depth of each well. _____

Submersible pump located in well. Pump size not determined. Well log attached.

SCANNED

JUN - 8 2009

6. Water is claimed for the following purposes:

(both dates are inclusive MM-DD) (cfs) (acre feet)

For Domestic purposes from 1/1 to 12/31 amount _____ or _____

For _____ purposes from _____ to _____ amount _____ or _____

For _____ purposes from _____ to _____ amount _____ or _____

For _____ purposes from _____ to _____ amount _____ or _____

7. Total quantity claimed (a) _____ (cfs) and/or (b) _____ (acre feet)

8. Non-irrigation uses; describe fully (eg. Domestic: Give number of households served; Stockwater: Type and number of livestock, Etc.) One household

9. Description of place of use:

a. If water is for irrigation, indicate acreage in each subdivision in the tabulation below.

b. If water is used for other purposes, place a symbol of use (example: D for Domestic) in the corresponding place of use below. See instructions for standard symbols.

Twn	Rng	Sec	NE				NW				SW				SE				Totals
			NE	NW	SW	SE	NE	NW	SW	SE	NE	NW	SW	SE	NE	NW	SW	SE	
51N	4W	2																D	

Parcel (PIN) no(s). _____ Total number of acres irrigated _____

10. In which county (ies) are lands listed above as place of use located? Kootenai

11. Do you own the property listed above as place of use? Yes (✓) No ()
If your answer is No, describe in Remarks below the authority you have to claim this water right.

12. Describe any other water rights used at the same place and for the same purposes as described above.

An additional claim is being made for irrigation of 92 acres of land under license 95-2169 _____ or None ()

13. Remarks: This claim is for an existing farm house that is located on the Hayden Village property that is irrigate under 95-2169


COPY

Last Name Hayden Village Identification No. _____

SCANNED

Map of Project: Attach aerial photograph or topographic map showing clearly the point of diversion, place of use, section number, township, and range number, unless unavailable. Otherwise sketch the elements above on the grid below.

Scale: 2 Inches equals 1 mile



Last Name ~~Chickman~~ Hayden Village Identification No. _____

SCANNED

JUN - 8 2009

14. Basis of Claim (Check One) Beneficial Use (✓) Posted Notice () License () Permit () Decree ()

Court _____ Decree Date _____ Plaintiff v. Defendant _____

If applicable provide IDWR Water Right Number _____

15. Signature(s)

(a.) By signing below, I/We acknowledge that I/We have received, read and understand the form entitled "How you will receive notices in the Coeur d'Alene-Spokane River Basin Adjudication." (b.) I/We do () do not () wish to receive and pay a small annual fee for monthly copies of the docket sheet.

Number of attachments: 2

For Individuals: I/We do solemnly swear or affirm under penalty of perjury that the statements contained in the foregoing document are true and correct.

Signature of Claimant (s) _____ Date: _____
_____ Date: _____

For Organizations: I do solemnly swear or affirm under penalty of perjury that I am

Manager of Hayden Village, LLC
Title Organization

that I have signed the foregoing document in the space below as

Manager of Hayden Village, LLC
Title Organization

and that the statements contained in the foregoing document are true and correct.

Signature of Authorized Agent Roy Glickman Date June 8, 2009

Title and Organization Hayden Village, LLC by Roy Glickman, Manager

16. Notice of Appearance:

Notice is hereby given that I, _____, will be acting as attorney at law of behalf of the claimant signing above, and that all notices required by law to be mailed by the director to the claimant signing above should be mailed to me at the address listed below.

Signature _____ Date _____


Address _____

COPY

Last Name Hayden Village, LLC Identification No. _____

SCANNED

JUN - 8 2009



QUANTUM Engineering and Geologic Consulting*

ENGINEER: Jim De Smet
DRAWN BY: Jim De Smet
DATE: 5/28/09
SCALE: 1"=2000'
SHEET NO:

Site Vicinity Map
Hayden Village, LLC
T51N, R4W, Sec 2
Kootenai County, Idaho

USE TYPEWRITER OR
BALL POINT PEN

State of Idaho
Department of Water Resources

WELL DRILLER'S REPORT

State law requires that this report be filed with the Director, Department of Water Resources within 30 days after the completion or abandonment of the well.

1. WELL OWNER Name <u>Henry Nagel</u> Address <u>1703 Havercraft Canyon Drive</u> <u>Idaho 83814</u> Owner's Permit No. <u>95-78-N-117</u>		7. WATER LEVEL Static water level <u>313</u> feet below land surface Flowing? ☐ Yes ☐ No G.P.M. flow <u>15</u> Temperature _____ ° F. Quality _____ Artesian closed-in pressure _____ p.s.i. Controlled by ☐ Valve ☐ Cap ☐ Plug																																																																																																												
2. NATURE OF WORK ☒ New well ☐ Deepened ☐ Replacement ☐ Abandoned (describe method of abandoning)		8. WELL TEST DATA ☐ Pump ☐ Bailer ☐ Other Discharge G.P.M. Draw Down Hours Pumped																																																																																																												
3. PROPOSED USE ☒ Domestic ☐ Irrigation ☐ Test ☐ Other (specify type) ☐ Municipal ☐ Industrial ☐ Stock ☐ Waste Disposal or Injection		9. LITHOLOGIC LOG																																																																																																												
4. METHOD DRILLED ☒ Cable ☐ Rotary ☐ Aug ☐ Other		<table border="1"><thead><tr><th rowspan="2">Hole Diam.</th><th colspan="2">Depth</th><th rowspan="2">Material</th><th rowspan="2">Water Yes/No</th></tr><tr><th>From</th><th>To</th></tr></thead><tbody><tr><td>6"</td><td>0</td><td>38</td><td>SAND, GRAVEL, ROCKS</td><td></td></tr><tr><td></td><td>38</td><td>52</td><td>SANDY CLAY, GRAVEL</td><td></td></tr><tr><td></td><td>52</td><td>76</td><td>SAND, GRAVEL</td><td></td></tr><tr><td></td><td>76</td><td>97</td><td>SAND, COARSE GRAVEL</td><td></td></tr><tr><td></td><td>97</td><td>98</td><td>BOULDER</td><td></td></tr><tr><td></td><td>98</td><td>101</td><td>COARSE GRAVEL</td><td></td></tr><tr><td></td><td>101</td><td>102</td><td>BOULDER</td><td></td></tr><tr><td></td><td>102</td><td>104</td><td>COARSE GRAVEL</td><td></td></tr><tr><td></td><td>104</td><td>105</td><td>BOULDER</td><td></td></tr><tr><td></td><td>105</td><td>150</td><td>SAND, COARSE GRAVEL</td><td></td></tr><tr><td></td><td>150</td><td>151</td><td>SAND, G. 104</td><td></td></tr><tr><td></td><td>151</td><td>200</td><td>SAND, GRAVEL</td><td></td></tr><tr><td></td><td>200</td><td>224</td><td>COARSE SAND</td><td></td></tr><tr><td></td><td>224</td><td>269</td><td>SAND, GRAVEL</td><td></td></tr><tr><td></td><td>269</td><td>291</td><td>COARSE SAND</td><td></td></tr><tr><td></td><td>291</td><td>315</td><td>med. sand</td><td>X</td></tr><tr><td></td><td>315</td><td>334</td><td>COARSE SAND, GRAVEL</td><td>X</td></tr><tr><td></td><td>334</td><td>339</td><td>SAND, GRAVEL</td><td>X</td></tr><tr><td></td><td>339</td><td>340</td><td>GRAVEL, CLAY & GRANITE</td><td>X</td></tr><tr><td></td><td>340</td><td>359</td><td>Fine sand</td><td>X</td></tr></tbody></table>		Hole Diam.	Depth		Material	Water Yes/No	From	To	6"	0	38	SAND, GRAVEL, ROCKS			38	52	SANDY CLAY, GRAVEL			52	76	SAND, GRAVEL			76	97	SAND, COARSE GRAVEL			97	98	BOULDER			98	101	COARSE GRAVEL			101	102	BOULDER			102	104	COARSE GRAVEL			104	105	BOULDER			105	150	SAND, COARSE GRAVEL			150	151	SAND, G. 104			151	200	SAND, GRAVEL			200	224	COARSE SAND			224	269	SAND, GRAVEL			269	291	COARSE SAND			291	315	med. sand	X		315	334	COARSE SAND, GRAVEL	X		334	339	SAND, GRAVEL	X		339	340	GRAVEL, CLAY & GRANITE	X		340	359	Fine sand	X
Hole Diam.	Depth		Material		Water Yes/No																																																																																																									
	From	To																																																																																																												
6"	0	38	SAND, GRAVEL, ROCKS																																																																																																											
	38	52	SANDY CLAY, GRAVEL																																																																																																											
	52	76	SAND, GRAVEL																																																																																																											
	76	97	SAND, COARSE GRAVEL																																																																																																											
	97	98	BOULDER																																																																																																											
	98	101	COARSE GRAVEL																																																																																																											
	101	102	BOULDER																																																																																																											
	102	104	COARSE GRAVEL																																																																																																											
	104	105	BOULDER																																																																																																											
	105	150	SAND, COARSE GRAVEL																																																																																																											
	150	151	SAND, G. 104																																																																																																											
	151	200	SAND, GRAVEL																																																																																																											
	200	224	COARSE SAND																																																																																																											
	224	269	SAND, GRAVEL																																																																																																											
	269	291	COARSE SAND																																																																																																											
	291	315	med. sand	X																																																																																																										
	315	334	COARSE SAND, GRAVEL	X																																																																																																										
	334	339	SAND, GRAVEL	X																																																																																																										
	339	340	GRAVEL, CLAY & GRANITE	X																																																																																																										
	340	359	Fine sand	X																																																																																																										
5. WELL CONSTRUCTION Diameter of hole <u>6</u> inches Total depth <u>359</u> feet Casing schedule: ☒ Steel ☐ Concrete Thickness <u>3/8</u> inches Diameter <u>6</u> inches From <u>12</u> feet To <u>340</u> feet Was casing drive shoe used? ☒ Yes ☐ No Was a packer or seal used? ☒ Yes ☐ No Perforated? ☐ Yes ☒ No How perforated? ☐ Factory ☐ Knife ☐ Torch Size of perforation _____ inches by _____ inches Number _____ From _____ To _____ perforations _____ feet _____ feet perforations _____ feet _____ feet perforations _____ feet _____ feet Well screen installed? ☒ Yes ☐ No Manufacturer's name <u>Johnson</u> Type <u>Stainless</u> Model No. _____ Diameter <u>6</u> Slot size <u>20</u> Set from <u>338</u> feet to <u>359</u> feet Diameter _____ Slot size _____ Set from _____ feet to _____ feet Gravel packed? ☐ Yes ☒ No Size of gravel _____ Placed from _____ feet to _____ feet Surface seal depth <u>20'</u> Material used in seal ☐ Cement grout ☒ Pudding clay ☐ Well cuttings Sealing procedure used ☐ Slurry pit ☐ Temporary surface casing ☒ Overbore to seal depth		10. Work started <u>8-15-78</u> finished <u>9-25-78</u>																																																																																																												
6. LOCATION OF WELL Sketch map location must agree with written location.  Subdivision Name _____ Lot No. _____ Block No. _____ County <u>Kootenai</u> <u>SW 1/4 NE 1/4 Sec. 2 T. 52 S. R. 4 E W</u>		11. DRILLER'S CERTIFICATION Firm Name <u>E. A. Holmes Drilling Co.</u> Firm No. <u>105</u> Address <u>5401 Pine St. Spokane Wa.</u> Date <u>10/2/78</u> Signed by (Firm Official) <u>William Hays</u> and <u>Donald L. Paul</u> (Operator)																																																																																																												

USE ADDITIONAL SHEETS IF NECESSARY FORWARD THE WHITE COPY TO THE DEPARTMENT

SCANNED

1111 - 8 7000