

IN THE DISTRICT COURT OF THE FIFTH JUDICIAL DISTRICT OF THE STATE OF IDAHO, IN AND FOR THE COUNTY OF TWIN FALLS

IN RE THE GENERAL ADJUDICATION
OF RIGHTS TO THE USE OF WATER FROM
THE COEUR D'ALENE-SPOKANE RIVER
BASIN WATER SYSTEM

CIVIL CASE NUMBER: 49576

Ident. Number 95-13477Date Received: 1-22-10Receipt No: NO 23451 CReceived By: cm

NOTICE OF CLAIM TO A WATER RIGHT

ACQUIRED UNDER STATE LAW

For Domestic and/or Stockwater Purposes

Where Daily Use is less than 13,000 gallons per day

RECEIVED

JAN 22 2010

IDWR / NORTH

1. Name of Claimant(s) Joe Threadgill Phone (208) 772 9446

Mailing Address 17141 E. Hayden Lake Rd. Hayden ID 83835
Street or Box City State

2. Date of Priority: (Only one per claim) 4/11/2000
Month/Day/Year (YYYY)

3. Source of water supply (Check one) Ground Water (✓) or Other () (a) _____
which is tributary to (b) _____

4. Location of Point of Diversion is: Township 51N, Range 3W, Section 11,
SE 1/4 of SW 1/4, or Govt. Lot _____ BM. County of Kootenai;

Parcel (PIN) no. 035920010040Additional points of diversion if any: NoneIf available, GPS coordinates: 524801 E, 5291179 N, UTM 11

5. Description of diverting works (Wells, Pumps, Spring boxes, Pipelines, Etc.) including the dates of any changes or enlargements in use, the dimensions of the diversion works as constructed and as enlarged and the depth of each well.

Submersible pump to a pressure tank in home for domestic and 1/2 acre or less of irrigation

6. Water is claimed for the following: (limited to Domestic and/or Stockwater uses. See page 1 of the instructions.)

For Domestic purposes from 1/1 to 12/31 amount 0.02 cfs () or AFY ()

For _____ purposes from _____ to _____ amount _____

7. Total Quantity claimed 0.02 cfs (✓) or AFY ()

8. Non-irrigation uses. Describe fully. (eg. Domestic: give number of households served if single ownership;

Stockwater and Number of livestock) One single family residence

COPIED
JAN 22 2010

9. Location of Place of Use is: Township 51N, Range 3W, Section 11,
SE 1/4 of SW 1/4, Govt. Lot _____ BM. Parcel (PIN) no. _____
 for (Check One) Domestic ☒ Stock ☐ Domestic and Stock ☐ If different than shown in Item 4

Additional places of use, if any _____

10. In which county (ies) are lands listed above as place of use located? Kootenai

11. Do you own the property listed above as place of use? Yes (✓) No ()

If the answer is No, describe in Remarks below the authority you have to claim this water right.

12. Describe any other water rights used at the same place and for the same purposes as described above.

_____ or None (✓)

13. Remarks:
Quantum Engineering is an authorized agent for the owner

Existing use falls under domestic exemption and no water right has been filed for this use.

14. Basis of Claim (Check One) Beneficial Use (✓) Posted Notice () License () Permit () Decree ()

Court _____ **Decree Date** _____ **Plaintiff v. Defendant** _____

If applicable provide IDWR Water Right Number _____

15. Signature(s)

(a.) By signing below, I/We acknowledge that I/We have received, read and understand the form entitled "How you will receive notices in the Coeur d'Alene-Spokane River Basin Adjudication." (b.) I/We do () do not () wish to receive and pay a small annual fee for monthly copies of the docket sheet.

Number of attachments: 2

For Individuals: I/We do solemnly swear or affirm under penalty of perjury that the statements contained in the foregoing document are true and correct.

Signature of Claimant (s) Jim Pichler Date: 12/17/09

Date: _____

For Organizations: I do solemnly swear or affirm under penalty of perjury that I am

_____ of _____,
Title Organization

that I have signed the foregoing document in the space below as

_____ of _____,
Title Organization

and that the statements contained in the forgoing document are true and correct.

Signature of Authorized Agent _____ Date _____

Title and Organization Quantum Engineering and Consulting, S. 2641 Silver Beach Loop, Coeur d'Alene,
Idaho, 83814


16. Notice of Appearance:
Notice is hereby given that I, _____, will be acting as attorney at law of behalf of the claimant signing above, and that all notices required by law to be mailed by the director to the claimant signing above should be mailed to me at the address listed below.

Signature _____ Date _____

Address _____

Last Name Identification No.

SCANNED
JAN 7 2 2010



0 500 1500 2500 3500 4500 FT



QUANTUM Engineering and Geologic Consulting*

ENGINEER: Jim De Smet

DRAWN BY: Jim De Smet

DATE: 11/30/09

SCALE: 1"=1000' (approx)

SHEET NO.:

Joe Threadgill Well
T51N, R3W, Sec 11
Kootenai County, Idaho

IDAHO DEPARTMENT OF WATER RESOURCES

WELL DRILLER'S REPORT

APR 19 2000

Office Use Only			
Inspected by			
Twp	Rge	Sec	
1/4	1/4	1/4	
Lat:	:	Long:	:

1. WELL TAG NO. D0013060

Drilling Permit No:

Other IDWR No.

763850

IDWR/North

2. OWNER:

Name Joe Threadgill

Well Number:


8

Address 1410 Lincoln Way

City Coeur d'Alene State ID Zip 83814

3. LOCATION OF WELL by legal description

sketch map location must agree with written location



Twp. 51 ☒ North or ☐ South

Rge. 3 ☐ East or ☒ West

E Sec. 11 1/4 SE 1/4 SW 1/4

Gov't Lot County KOOTENAI

Lat: : Long: :

Address of Well Site

City Hayden Lake

(Give at least name of road + Distance to Road or Landmark)

Lt. Bk. Sub. Name

4. USE:

☒ Domestic ☐ Municipal ☐ Monitor ☐ Irrigation

☐ Thermal ☐ Injection ☐ Other

5. TYPE OF WORK check all that apply (Replacement, etc.)

☒ New Well ☐ Modify ☐ Abandonment ☐ Other

6. DRILL METHOD

☒ Air Rotary ☐ Cable ☐ Mud Rotary ☐ Other

7. SEALING PROCEDURES

SEAL/FILTER PACK		AMOUNT		METHOD
Material	From	To	Sacks or Pounds	
well seal				
BENTONIT	0	43	7 bags	overbore

Was drive shoe used? ☒ Y ☐ N Shoe Depth(s) 43

Was drive shoe seal tested? ☐ Y ☐ N How?

8. CASING/LINER:

Diameter	From	To	Gauge	Material	Casing	Liner Welded	Threaded
4	-5	240	.160	PVC	☐	☒	☐
6	2	43	.250	steel	☒	☐	☒

Length of Headpipe Length of Tailpipe

9. PERFORATIONS/SCREENS

☒ Perforations Method skill saw

☐ Screens Screen Type

From	To	Slot Size	Number	Diameter	Material	Casing	Liner
200	240	1/8 x 4	170	4	PVC	☐	☒

10. STATIC WATER LEVEL OR ARTESIAN PRESSURE:

30 ft. below ground Artesian pressure lb.

Depth flow encountered ft. Describe access port or control devices:

11. WELL TESTS:

☐ Pump ☐ Bailer ☐ Air ☐ Flowing Artesian

Yield gal./min.	Drawdown	Pumping Level	Time
10		240	1 1/2 hrs

Water Temp. 49 Bottom Hole Temp 49

Water Quality test or comments: good

Depth first Water encountered 55

12. LITHOLOGIC LOG:(Describe repairs or abandonment)

				Water	
Bore Diam	From	To	Remarks: Lithology, Water Quality, Temperature	Y	N
8	0	16	topsoil clayish w/cobbles	☐	☒
8	16	43	granite decomp brown soft	☐	☒
6	43	55	granite white & green med	☐	☒
6	55	60	granite green & brown w/w apx 1-2 ap	☒	☐
6	60	210	granite figreen & white med	☐	☒
6	210	220	granite fractured green & black w/w ap	☒	☐
6	220	240	granite green & white soft	☐	☒

Completed Depth 240 (Measurable)
Date: Started 4/10/00 Completed 4/11/00

13. DRILLER'S CERTIFICATION

I/We certify that all minimum well construction standards were complied with at the time the rig was removed.

Firm Name H2O WellService, Inc. Firm No. 448

Firm Official Date 4-18-00

and Supervisor or Operator Date 4-18-2000

(Sign Once if Firm Official and Operator)

Louie Hanner

51N 3W 11