

IN THE DISTRICT COURT OF THE FIFTH JUDICIAL DISTRICT OF THE
STATE OF IDAHO, IN AND FOR THE COUNTY OF TWIN FALLS

IN RE THE GENERAL ADJUDICATION
OF RIGHTS TO THE USE OF WATER FROM
THE COEUR D' ALENE-SPOKANE RIVER
BASIN WATER SYSTEM

CIVIL CASE NUMBER: 49576

Ident. Number 95-16522

Date Received: 11/17/11

Receipt No: N 028 5896 No 28600

Received By: [Signature]

RECEIVED

NOV 17 2011

NOTICE OF CLAIM
TO A WATER RIGHT
ACQUIRED UNDER STATE LAW

IDWR/NORTHERN

Please type or print clearly

1. Name of Claimant (s) Avista Corporation Phone (509) 495-2571

Mailing Address PO Box 3727 Spokane WA ZIP 99220-3727
Street or Box City State

2. Date of Priority (Only one (1) per claim) 1922
Month Day Year (YYYY)

3. Source of water supply (Check one) Ground Water (✓) or Other () (a) _____
which is tributary to (b) _____

4. a. Location of Point of Diversion is: Township 50N, Range 5W, Section 4,
SW, 1/4 of NE, 1/4 Govt. Lot _____, BM., County of Kootenai

Parcel (PIN) no. 50N05W - 042300

Additional points of diversion if any: _____

If available, GPS Coordinates N47°42.586 W116° 57.895

b. If instream flow, beginning point of claimed instream flow is:

Township _____, Range _____, Section _____, _____, 1/4 of _____, 1/4

Govt. Lot _____, BM., County of _____

ending point is: Township _____, Range _____, Section _____, _____, 1/4 of _____, 1/4

Govt. Lot _____, BM., County of _____

5. Description of existing diversion works (Dams, Reservoirs, Ditches, Wells, Pumps, Pipelines, Headgates ,Etc), including the dates of any changes or enlargements in use, the dimensions of the diversion works as constructed and as enlarged and the depth of each well. The 1922 domestic water system for the Post Falls Hydro Electric Development (HED) that provided water supply to the operators' homes and power house consisted of a well, water storage tank and flume (see attached Post Falls Power Sta. - Domestic Water Tank Plan dated 10/12/1922). A replacement well was drilled in May 1984, to a depth of 203' (see attached 1984 well log and 10/24/1984 Water Supply Plan). The 1922 water storage and well, which is still visible was taken out of service once the new well system was completed. In 2008, a replacement pump was installed (see attached 6/2/2008 specifications.)

6. Water is claimed for the following purposes:

(both dates are inclusive MM-DD) (cfs) (acre feet)

For Domestic purposes from 01/01 to 12/31 amount 0.08 or 3.8

For Fire Protection purposes from 01/01 to 12/31 amount _____ or _____

For ----- purposes from _____ to _____ amount _____ or _____

For ----- purposes from _____ to _____ amount _____ or _____

7. Total quantity claimed (a) 0.08 cfs (cfs) and/or (b) 3.8 AF (acre feet)

8. Non-irrigation uses; describe fully (eg. Domestic: Give number of households served; Stockwater: Type and number of livestock, Etc.) Domestic use is for the power house and two homes, incl. irrigation of lawns & gardens.

9. Description of place of use:

- If water is for irrigation, indicate acreage in each subdivision in the tabulation below.
- If water is used for other purposes, place a symbol of use (example: D for Domestic) in the corresponding place of use below. See instructions for standard symbols.

Twn	Rng	Sec	NE				NW				SW				SE				Totals
			NE	NW	SW	SE	NE	NW	SW	SE	NE	NW	SW	SE	NE	NW	SW	SE	
50N	5W	4			D/1	D													1

Parcel (PIN) no(s) 50N05W - 042300 Total number of acres irrigated up to 1

10. In which county (ies) are lands listed above as place of use located? Kootenai

11. Do you own the property listed above as place of use? Yes (✓) No ()
If your answer is No, describe in Remarks below the authority you have to claim this water right.

12. Describe any other water rights used at the same place and for the same purposes as described above.
Water Right License No. 95-08432 with priority date of 1/30/1984, subject to beneficial use of 1922. or None ()

13. Remarks: Water Right License No. 95-08432 was applied for and obtained in 1984 when the replacement domestic well was drilled. The domestic water supply records of use date back to 1922. The Post Falls HED has a priority date of 1907. The historical beneficial use right for the domestic supply were established before 1963, which also includes domestic irrigation of lawns/gardens of up to 1/2 acre for each of the two homes, and fire suppression as needed. NOTE: The historic and current place of use for the domestic supply includes the SW1/4NE1/4 of Sect. 4 (location of homes) and the SE1/4NE1/4 of Sect.4 (location of power house).

ATTACHMENTS TO CLAIM:

- 10/12/1922 Post Falls Power Sta. - Domestic Water Tank plan;
- 10/24/1984 Post Falls HED Domestic Water Supply Plan, incl. 1984 well log for 203' replacement well;
- Water Right License No. 95-0843 (Priority date 1/30/1984); 4. Site Maps; and 5. Claim 95-4518 - priority 1907.

Last Name Avista Corporation Identification No. _____

14. Basis of Claim (Check One) Beneficial Use () Posted Notice () License () Permit () Decree ()

Court _____ Decree Date _____ Plaintiff v. Defendant _____

If applicable provide IDWR Water Right Number 95-08432

15. Signature(s)

(a.) By signing below, I/We acknowledge that I/We have received, read and understand the form entitled "How you will receive notices in the Coeur d'Alene-Spokane River Basin Adjudication." (b.) I/We do () do not () wish to receive and pay a small annual fee for monthly copies of the docket sheet.

Number of attachments: five (5)

For Individuals: I/We do solemnly swear or affirm under penalty of perjury that the statements contained in the foregoing document are true and correct.

Signature of Claimant (s) _____ Date: _____

_____ Date: _____

For Organizations: I do solemnly swear or affirm under penalty of perjury that I am

Linda M. Kiefer of Avista Corporation,
Title Organization

that I have signed the foregoing document in the space below as

Environmental Resource Specialist of Avista Corporation,
Title Organization

and that the statements contained in the foregoing document are true and correct.

Signature of Authorized Agent [Signature] Date Nov. 16, 2011

Title and Organization Environmental Resource Specialist for Avista Corporation

16. Notice of Appearance:

Notice is hereby given that I, _____, will be acting as attorney at law of behalf of the claimant signing above, and that all notices required by law to be mailed by the director to the claimant signing above should be mailed to me at the address listed below.

Signature _____ Date _____

Address _____

Last Name Avista Corporation Identification No. _____

* FOR DOMESTIC WATER -
RIGHT CLAIM - AUSTACORP.

५२-८

ELEVATION


ENDING SHOWN FOR
SCALE, 1/8" =
FOOT NO DOOR SILENTERS
IF STRIPS REQUIRED

DOOR

16"

24"


36"




NOTE: THE PROPORTION OF CARBONATED FILLER IN CONCRETE MUST BE ADJUSTED ACCORDING TO THE EXISTING CEMENT-BINDER RATIO. IS
STANDARD.

**POSTFALLS POWER STA.
POWER HOUSE
DOMESTIC WATER TANK
THE WASHINGTON WATER POWER COMPANY
BOSTON, WASHINGTON**



SCANNED
NOV 21 2011





JUNCTION BOX AT
BASE OF SERVICE POLE



WIRING DIAGRAM (CABINET IN WELL PIT)
NEMA 1 MOTOR STARTER



SYSTEMC CONTROLS PANEL (ROSS PARK BLDG.



POST FALLS DOMESTIC PUMPING SCHEMATIC DIAGRAM

WELL DATA

DRILLED MAY, 1984
DEPTH 203 FEET
PUMP SETTING 175 FEET
STATIC WATER LEVEL 102 FEET
PUMPING WATER LEVEL 135 FEET

- 1 18 ARMY - TANK LEVEL SERVICE CIRCLE PAPER AND CLOSING
- 2 18 ARMY - WILL PAPER MORE EXPENSES
- 3 SET 1811 - TO OTHER AFTER FIVE SERVICE CIRCLE, THERE IS NO
- 4 SET 1811 - TO CLOSING AFTER WILL INCREASES FROM A PAPER TO
- 5 SET 1811 - TO CLOSING AFTER WILL INCREASES FROM A PAPER TO

NOV 21 2011

DATE	5-16-85	APPROVED
DRAWN BY	K. ZIMT	<i>B. Wenzel</i>
CHECKED BY	DECKER	7-20-85
DESIGNED BY	MORRIS	E-30552
SCALE	AS SHOWN	
PROJECT NO.	WET JIN	
SHEET NO.	OF 1	

REFERENCE DRAWINGS

PIPING & PUMPHOUSE LOCATION PLAN & DETAIL	C-31838
DOMESTIC WATER TANK	A-745
ELECTRIC DISTRIBUTION MAP	E-24330
PUMPHOUSE VAULT	E-32185

58125-3


MATERIAL LIST

- 1) 2" GALVANIZED PIPE
- 2) 2" GATE VALVE
- 3) 2" THREADED UNION
- 4) 2" 2" 2" 3/4" TEE
- 5) 2" 2" 1" TEE
- 6) 2" 2" 1/2" TEE W/PRESSURE GAUGE
- 7) 2" 2" 2" TEE
- 8) 3" 5" CORN. LING
- 9) FLOW SWITCH - UNIVERSAL SERIES TWO TOWER 125 V AC 15 AMP
- 10) AUXILIARY CONTROL PANEL - STSIC CONTROLS
- 11) 119 GAL WOOD WELL-2-TROUL TANK
- 12) 24" DIA X 61 7/8" HIGH, 30-50 PSIG PRESSURE SWITCH FSD, 250 CONNECTED TO TEE W/PRESSURE GAUGE


NOTE:

ALL CONNECTIONS ARE GALVANIZED THREADED


PLAN VIEW




ROOF




EAST WALL ELEVATION




SOUTH WALL ELEVATION



WEST WALL ELEVATION



NORTH WALL ELEVATION



REFERENCE DRAWINGS

PURHOUSE LOCATION - PLAN & DETAILS
PURHOUSE FITTING & SCHEMATIC DIAGRAM

FILE: STRUCTURES AND IMPROVEMENTS

POST FALLS H.E.D. DOMESTIC WATER SUPPLY PURHOUSE VAULT	
3/4" x 1'-0" 07-19-88 07/20/18	AVISTA CORP SPOKANE, WASHINGTON APPROVED [Signature] 07/20/18
07/20/18 07/20/18 07/20/18	E-32185

SCANNED
NOV 21 2011

STATE OF IDAHO
DEPARTMENT OF WATER RESOURCES
WELL DRILLER'S REPORT

State law requires that this report be filed with the Director, Department of Water Resources within 30 days after the completion or abandonment of the well.

ATTACHMENT B
pg 4 of 6 - AVISTA Corp.
POST FALLS HED
DOMESTIC WATER
RIGHT CLAIM

1. WELL OWNER Name <u>Washington Water Power</u> Address <u>P.O. Box 3727 Spokane, Washington</u> Owner's Permit No. <u>95-84-N-24</u>	7. WATER LEVEL Static water level <u>95</u> feet below land surface. Flowing? ☐ Yes ☒ No G.P.M. flow _____ Artesian closed-in pressure _____ p.s.i. Controlled by: ☐ Valve ☐ Cap ☐ Plug Temperature _____ of. Quality _____ <i>Describe artesian or temperature zones below.</i>																																																																												
2. NATURE OF WORK ☒ New well ☐ Deepened ☐ Replacement ☐ Abandoned (describe abandonment procedures such as materials, plug depths, etc. in lithologic log)	8. WELL TEST DATA ☒ Pump ☐ Baller ☐ Air ☒ Other _____ <table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th>Discharge G.P.M.</th> <th>Pumping Level</th> <th>Hours Pumped</th> </tr> </thead> <tbody> <tr> <td>1.3</td> <td>195</td> <td>4</td> </tr> <tr> <td> </td> <td> </td> <td> </td> </tr> <tr> <td> </td> <td> </td> <td> </td> </tr> </tbody> </table>	Discharge G.P.M.	Pumping Level	Hours Pumped	1.3	195	4																																																																						
Discharge G.P.M.	Pumping Level	Hours Pumped																																																																											
1.3	195	4																																																																											
3. PROPOSED USE ☒ Domestic ☐ Irrigation ☐ Test ☐ Municipal ☐ Industrial ☐ Stock ☐ Waste Disposal or Injection ☐ Other _____ (specify type)	9. LITHOLOGIC LOG <table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th rowspan="2">Bore Diam.</th> <th colspan="2">Depth</th> <th rowspan="2">Material</th> <th colspan="2">Water</th> </tr> <tr> <th>From</th> <th>To</th> <th>Yes</th> <th>No</th> </tr> </thead> <tbody> <tr> <td>8</td> <td>1</td> <td>25</td> <td>heavy gravel</td> <td></td> <td>x</td> </tr> <tr> <td>6</td> <td>25</td> <td>78</td> <td>sand & pea gravel</td> <td></td> <td>x</td> </tr> <tr> <td>6</td> <td>78</td> <td>92</td> <td>soft gray granite</td> <td></td> <td>x</td> </tr> <tr> <td>6</td> <td>92</td> <td>116</td> <td>hard gray "</td> <td></td> <td>x</td> </tr> <tr> <td>6</td> <td>116</td> <td>132</td> <td>soft brn granite</td> <td></td> <td>x</td> </tr> <tr> <td>6</td> <td>132</td> <td>136</td> <td>" white "</td> <td></td> <td>x</td> </tr> <tr> <td>6</td> <td>136</td> <td>144</td> <td>med hard "</td> <td></td> <td>x</td> </tr> <tr> <td>6</td> <td>144</td> <td>152</td> <td>" " brown granite</td> <td></td> <td>x</td> </tr> <tr> <td>6</td> <td>152</td> <td>170</td> <td>" " gray "</td> <td></td> <td>x</td> </tr> <tr> <td>6</td> <td>170</td> <td>185</td> <td>soft " "</td> <td></td> <td>x</td> </tr> <tr> <td>6</td> <td>185</td> <td>203</td> <td>hard gray "</td> <td></td> <td>x</td> </tr> </tbody> </table>	Bore Diam.	Depth		Material	Water		From	To	Yes	No	8	1	25	heavy gravel		x	6	25	78	sand & pea gravel		x	6	78	92	soft gray granite		x	6	92	116	hard gray "		x	6	116	132	soft brn granite		x	6	132	136	" white "		x	6	136	144	med hard "		x	6	144	152	" " brown granite		x	6	152	170	" " gray "		x	6	170	185	soft " "		x	6	185	203	hard gray "		x
Bore Diam.	Depth		Material	Water																																																																									
	From	To		Yes	No																																																																								
8	1	25	heavy gravel		x																																																																								
6	25	78	sand & pea gravel		x																																																																								
6	78	92	soft gray granite		x																																																																								
6	92	116	hard gray "		x																																																																								
6	116	132	soft brn granite		x																																																																								
6	132	136	" white "		x																																																																								
6	136	144	med hard "		x																																																																								
6	144	152	" " brown granite		x																																																																								
6	152	170	" " gray "		x																																																																								
6	170	185	soft " "		x																																																																								
6	185	203	hard gray "		x																																																																								
4. METHOD DRILLED ☒ Rotary ☐ Air ☐ Hydraulic ☐ Reverse rotary ☒ Cable ☐ Dug ☐ Other _____	10. Work started <u>3-23-84</u> finished <u>3-27-84</u>																																																																												
5. WELL CONSTRUCTION Casing schedule: ☒ Steel ☐ Concrete ☐ Other _____ Thickness _____ inches Diameter _____ inches + _____ feet To _____ feet Class _____ inches _____ inches _____ feet _____ feet _____ inches _____ inches _____ feet _____ feet Was casing drive shoe used? ☒ Yes ☐ No Was a packer or seal used? ☐ Yes ☒ No Perforated? ☒ Yes ☐ No How perforated? ☐ Factory ☐ Knife ☐ Torch Size of perforation <u>7/16</u> inches by _____ inches Number _____ From _____ To _____ _____ perforations _____ feet _____ feet _____ perforations _____ feet _____ feet _____ perforations _____ feet _____ feet Well screen installed? ☐ Yes ☒ No Manufacturer's name _____ Type _____ Model No. _____ Diameter _____ Slot size _____ Set from _____ feet to _____ feet Diameter _____ Slot size _____ Set from _____ feet to _____ feet Gravel packed? ☐ Yes ☒ No ☐ Size of gravel _____ Placed from _____ feet to _____ feet Surface seal depth <u>20</u> Material used in seal: ☐ Cement grout ☒ Bentonite ☐ Puddling clay ☐ _____ Sealing procedure used: ☐ Slurry pit ☒ Temp. surface casing ☐ Overbore to seal depth Method of joining casing: ☐ Threaded ☒ Welded ☒ Solvent Weld ☐ Cemented between strata Describe access port <u>well cap</u>	11. DRILLERS CERTIFICATION <u>ee</u> I/We certify that all minimum well construction standards were complied with at the time the rig was removed. Firm Name <u>Bronson Water Wells</u> Firm No. <u>360</u> Address <u>Box 1 Spirit Lake, ID.</u> Date <u>4-2-84</u> Signed by (Firm Official) <u>[Signature]</u> and (Operator) _____																																																																												
6. LOCATION OF WELL Sketch map location <u>must</u> agree with written location. <table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <td style="text-align: center;">N</td> <td colspan="4"></td> </tr> <tr> <td></td> <td style="text-align: center;">X</td> <td colspan="2"></td> <td></td> </tr> <tr> <td style="text-align: center;">W</td> <td></td> <td style="text-align: center;">E</td> <td colspan="2"></td> </tr> <tr> <td></td> <td></td> <td></td> <td style="text-align: center;">S</td> <td></td> </tr> </table> County <u>Kootenai</u> <u>4</u> <u>50N</u> <u>5W</u> <u>34</u> <u>1/4</u> <u>NE</u> <u>1/4</u> Sec. <u>4</u>, T. <u>50</u> N. N/S, R. <u>5</u> W. E/W. Subdivision Name _____ Lot No. _____ Block No. _____	N						X				W		E						S		SCANNED																																																								
N																																																																													
	X																																																																												
W		E																																																																											
			S																																																																										

SCANNED
NOV 21 2011

May 12, 2008

AAA Pump Service, Inc.
17 South Willow
Spokane Valley, WA 99206

CONSTRUCTION AGREEMENT

Post Falls HED / Replace Pump
C-2672 PO-08 080044

Furnish labor, materials, and equipment (fully operated and maintained) to replace the water pump and appurtenances for the Post Falls HED and the operator's housing water supply located on the Spokane River in Post Falls, Idaho.

Work on this project shall begin within five (5) calendar days after signing this Construction Agreement and shall be completed no later than Friday, May 30, 2008. Time is of the essence.

All work shall be done in accordance to Industry Standards and Avista's General Conditions for Contract Construction dated January, 1999, which are all hereby made a part of this Construction Agreement, and by direction of the Avista Representative on the job.

This work consists of the following:

Contractor shall remove and legally dispose of the existing submersible pump and pressure tank and appurtenances.

Contractor shall furnish and install the following:

- One (1) 8GS30422 Goulds 3 horsepower, submersible pump
- Three phase 230 volt - pumping 20+ GPM @ 290 TDH
- 168' of two inch (2") galvanized drop pipe
- 175' x 12-3 jacketed subwire
- One (1) 119 gallon steel pressure tank, pressure switch and gauge
- Two (2) 2" gate valves
- One (1) 2" filter with bleed off and spin down filter - FS2-24ST

Contractor understands and agrees to the terms and conditions of Avista Corporation's General Conditions and this Construction Agreement. Any alterations to these documents shall invalidate this Construction Agreement.

SCANNED
NOV 21 2011

STA CORP - DOMESTIC | ATTACHMENT B, pg 6 of 6
WATER RIGHT CLAIM | FOR POST FALLS HED

FOR POST FALLS HED

DOMESTIC WELL

(REPLACEMENT Pump)

June 2, 2008

INVOICE # 17529[illegible]

SCANNED
NOV 21 2011

State of Idaho
Department of Water Resources

WATER RIGHT LICENSE

WATER RIGHT NO. 95-08432

Priority: January 30, 1984

Maximum Diversion Rate:
Maximum Diversion Volume:¹

0.08 CFS
1.8 AF

This is to certify, that WASHINGTON WATER POWER CO.

E. 1411 MISSION AVE.

P.O. BOX 3727

SPOKANE, WA 99220

has complied with the terms and conditions of the permit, issued pursuant to Application for Permit dated January 30, 1984; and has submitted Proof of Beneficial Use on February 8, 1989. An examination indicates that the works have a diversion capacity of .160 cfs of water from a GROUNDWATER source, and a water right has been established as follows:

BENEFICIAL USE	PERIOD OF USE	RATE OF DIVERSION	ANNUAL VOLUME
DOMESTIC	01/01 to 12/31	0.08 CFS	1.8 AF

LOCATION OF POINT(S) OF DIVERSION:

SWNE, Sec. 4, Township 50N, Range 05W
KOOTENAI County

PLACE OF USE: DOMESTIC

TWN RGE SEC

50N 05W 4

SWNE

CONDITIONS/REMARKS:

1. The maximum diversion volume is defined as the maximum allowable volume of water that may be diverted annually from the source under this right. The use of water confirmed by this right is limited to the amount which can actually be beneficially used. The maximum diversion volume may be adjusted to more accurately describe the beneficial use or to implement accepted standards of diversion and use efficiency.
2. This water right is appurtenant to the described place of use.
3. This right is subject to all prior water rights and may be forfeited by five years of non-use.
4. Modifications to or variance from this license must be made within the limits of Section 42-222, Idaho Code, or the applicable Idaho law.
5. Domestic use is for 2 homes and restroom facilities at a powerhouse.

This license is issued pursuant to the provisions of Section 42-219, Idaho Code. Witness the seal and signature of the Director, affixed at Boise, this 11th day of JANUARY, 1991.

INDEXED

JAN 18 1991

Acting for R. Keith Higginson, Director


NOV 21 2011

Legend

- ▲ Well Site 1984 Replacement Well
- Place of Use
- Avista Parcel
- - - FERC Project Boundary
- - - NW Quarter Sections
- - - Township, Range



POST FALLS HED DOMESTIC WATER SUPPLY SITE MAP



0 300 600 Feet

1 inch = 300 feet

SCANNED
NOV 21 2011

STATE OF IDAHO
DEPARTMENT OF WATER RESOURCES

CLAIM TO A WATER RIGHT

ATTACHMENT E
AUSTA CORP.
DOMESTIC WATER
RIGHT CLAIM
pg 1 of 3

Under the provisions of Section 42-243, Idaho Code, any person using or claiming rights to the public waters of Idaho established by diversion and application to a beneficial use must file a claim with the Department of Water Resources on or before June 30, 1983. Exempted from this filing are single family domestic uses as defined in Section 42-230(d), Idaho Code. Also exempted are rights represented by a permit, license, decree, adjudicated right, or a previously filed claim.

The filing of this claim does not confirm the water right claimed but failure to file may result in forfeiture of a water right.

Notice is hereby given that The Washington Water Power Company

(Name of Claimant)

P. O. Box 3727, Spokane, Washington 99220

(Mailing Address)

Telephone No. (509) 489-0500

(Zip Code)

claims a right to the diversion and beneficial use of the surface or ground water. The extent and nature of said claim is as follows:

- (1) Date of priority: (When was the water first applied to a beneficial use) 1907

A claim is not acceptable on a ground water source with a priority later than March 25, 1963 or on a surface water source with a priority later than May 20, 1971. An exception is that a claim may be filed on single family domestic use from a ground water source.

- (2) Describe the source of water: (Name of stream, lake, spring, etc., or ground water)

Spokane River tributary to Columbia River

- (3) Describe the purpose for which the water has been used and the time during the year when you have used the right claimed:

(cfs, af)	(Domestic, Irrigation, Stock, Etc.)	(Both dates inclusive)	
		(Mo., Day)	(Mo., Day)
Quantity <u>4250 cfs</u>	Use <u>Elec. Power Generation</u>	Period of Use From <u>January 1</u>	To <u>December 31</u>
Quantity _____	Use _____	Period of Use From _____	To _____
Quantity _____	Use _____	Period of Use From _____	To _____
Quantity _____	Use _____	Period of Use From _____	To _____
Quantity _____	Use _____	Period of Use From _____	To _____

- (4) 4250 cfs TOTAL QUANTITY USED.
(cfs, af)

- (5) A) Point of diversion: (Location of point where water is diverted from its source)

SE 1/4 NE 1/4, Sec. 4 Twp. 50N Rge. 5 W. B.M., County of Kootenai
Additional points of diversion: _____

B) Describe means of diversion of water: (Pump and pipeline, well, diversion dam, reservoir, length of ditch and field, etc.). Give sizes and capacities: be as specific as possible. Describe any changes in the system and give the date of the

ATTACHMENT E
AUISTA CORP.
DOMESTIC WATER
RIGHT CLAIM pg 3 of 3

No. 8 - Remarks

The Washington Water Power Company claims the right to use all of the water of the Spokane River at Post Falls for water power purposes. The Company owns all of the land on which the Post Falls dams and water power works are located. The date of priority of such claim is June 1, 1871, which was confirmed March 3, 1891, by Act of Congress (26 Stat.989). A United States Patent was issued to Frederick Post for the land and water power at the Post Falls site. The Company has acquired the land and water power rights and has put to beneficial use the above quantities of water since 1907.

SCANNED
NOV 21 2011