

Consultants in
natural
resources and
the environment

Denver • Boise • Durango • Western Slope

**Response to SPF's Memorandum
Entitled "Response to IDWR Staff
Memo Regarding the Sufficiency of Water
Supply For Water Right Applications and
Transfers Along the I-84 Corridor,"
November 15, 2012**

Prepared for—

Idaho Power Company

Prepared by—

David B. Shaw and Norman C. Young

ERO Resources Corporation
3314 Grace Street
Boise, Idaho 83713
(208) 373-7983



ERO Resources Corp.
3314 Grace Street
Boise, ID 83703
(208) 373-7983
Fax: (208) 373-7985
www.eroresources.com
eroboise@eroresources.com

January 31, 2013

Mountain Home Corridor Response

January 31, 2013

This report is submitted on behalf of Idaho Power Company (IPCo) to further assist the Idaho Department of Water Resources (IDWR) and its hearing officer in reviewing the six applications for permit to appropriate ground water and two applications for transfer under consideration in the consolidated hearing (IDWR, January 24, 2012). SPF Water Engineering, LLC (SPF) submitted a memorandum (SPF, November 15, 2012) responding to the Idaho Department of Water Resources staff Memorandum (IDWR, May 31, 2012) on behalf of Mayfield Townsite LLC (Application for Permit No. 63-32499), Nevid LLC (Applications for Permit Nos. 61-12095 and 61-12096) and Mayfield Townsite/ARK Properties (Application for Permit No. 63-33344). The opinions and conclusions in SPF's memorandum relate to the three general questions used as the outline in this report.

The size, nature and arid location of the proposed projects provide added incentive to seek sound technical data and exercise appropriate technical methodology to insure that the estimate used to determine the adequacy of the water supply for the proposed projects is within the amount actually available and sustainable from the source of supply. Investors in the projects, purchasers of lots and homes, families that move into the new communities and those that presently rely upon the limited water resources in the area will be at risk if the estimate overstates the actual water supply. After the lots are sold, the houses, shops and other facilities are built and families have moved into the new community is not an acceptable time for determining that the estimate of water availability was too optimistic.

QUESTION NO. 1. Should IDWR's estimate of the volume of ground water available for appropriation in the consolidated hearing study area be increased?

SPF suggests a number of reasons for either increasing IDWR's estimate of the volume of ground water available for appropriation or for at least considering IDWR's estimate as conservatively low. ERO responds to SPF's suggested reasons as follows:

- a. Does upwelling geothermal water add to the supply?

SPF requests that IDWR's estimate of the average rate of annual recharge to the consolidated hearing study area be increased by 550 afa to include upwelling geothermal water (Page 2, Item No. 1 and Pages 7 and 8, Items No. 16 and 17).

Response: The basis for this request is a suggestion in a recent report (Welhan, February 2012, Page 2) that elevated temperatures in some wells may be caused by mixing of geothermal water originating outside of the consolidated hearing study area. An earlier study (IDWR, September 1976) found that elevated ground-water temperatures in southern Idaho, including wells in the study and comparison areas, are attributable to the upward movement of heat without always having an associated upwelling of heated ground water from sources of deep circulation.

Mountain Home Corridor Response

January 31, 2013

Welhan references the IDWR report, but concludes that water temperatures observed in shallow wells in the consolidated hearing study area are too high to exist without circulating water (Welhan, February 2012, Page 19). However, the 21-25° F range in temperature increase observed in shallow wells in the area is equal to 12-14° C rather than 38-45° C (final paragraph, Page 19, Welhan, February 2012). A 14° C temperature increase in a 600 feet deep well requires a temperature gradient of 76° C/km. This revised temperature gradient, though high, is consistent with that listed for some wells in and near the consolidated hearing study area in IDWR's earlier report (IDWR, 1976, for example see Pages 90 to 94).

If some or all of the elevated temperature is attributable to regional heat flow through conductivity and not entirely from mixing of upwelling geothermal water, the estimate of the percentage of geothermal water will be lower than Welhan suggested. Given the uncertainty regarding the volume, if any, of upwelling geothermal water, IDWR's recharge estimate is appropriately conservative in not including this factor.

- b. Should the estimate of ground water supply be increased if DCMI uses are not fully consumptive?

SPF requests that IDWR's estimate of the average rate of annual recharge to the consolidated hearing study area be increased by 180 afa because not all water diverted for "DCMI" purposes is consumptively used and some of the irrigation assumed by IDWR is on land without water rights (Page 2, Item No. 2 and Page 8, Item No. 18).

Response: IDWR's estimate of water availability should not be increased in reliance upon unconsumed water returning to the aquifer. The timely return to the regional aquifer in the consolidated hearing study area of water diverted but not consumed is not assured because of layers of fine sediment and other low permeability materials overlaying the regional aquifer. Such layers impede the downward movement of water and can encourage lateral movement potentially making the water unavailable for re-diversion by wells in the consolidated hearing study area.

The documents posted by IDWR for this matter include drillers' reports for some wells constructed in and near the area proposed for development (Item 9, Other EAC Logs). Attached are additional drillers' reports downloaded from IDWR's electronic record of drillers' reports for other wells in this area that IDWR did not include in the posted information for this matter. Most of these reports show that wells in the area penetrate a significant thickness of clay and other fine-grained materials above the water-producing zone developed by the well. Typically, the post-construction static water level is reported to be significantly above the level water was first encountered in the well. This confirms that the low permeability materials above the producing zone cover a significant area. Water percolating downward from the surface would have to overcome the hydraulic pressure of the producing zone to re-enter the regional aquifer, but the drillers' reports do not identify the extensive depth of saturated materials needed. Such conditions, described in some but not all drillers' reports in the consolidated hearing study area,

Mountain Home Corridor Response

January 31, 2013

indicate that hydrogeology of the consolidated hearing study area is complex and water once diverted may not have a direct path back to the aquifer. For this reason, water diverted from the regional aquifer should not be considered to be available for further diversion and use without information to accurately estimate the amount, timing and location of unconsumed water reaching the regional aquifer.

Further, IDWR's estimate should not be adjusted because some of the estimated water use occurred on land without valid water rights. Conversely, IDWR's estimate does not include water use on acres authorized to use water under valid existing rights that were not irrigated in 2011. IDWR assumed that long-term annual withdrawals of ground water can be accurately estimated from the use of water observed in the consolidated hearing study area in a single year instead of conservatively recognizing that diversion and use of ground water can occur under all valid water rights. This concept is particularly applicable to the consolidated hearing study area because rights found to be valid in the SRBA are unlikely to have been lost by abandonment or forfeiture in the relatively short time since the partial decrees were issued. In addition, holders of existing rights are motivated to use water to protect their water rights, at least in part, because of the demand created by the projects under consideration in the consolidated hearing. Accordingly, the full volume authorized by existing rights should be recognized when determining whether un-appropriated water is available for new uses.

Assuming all valid rights are fully used and that unconsumed water is not available for re-diversion from the aquifer, the volume of water available for appropriation for new uses is only 3,000 afa if the consolidated hearing study area is indeed a water source separated from the Cinder Cone Butte Critical Ground Water Area (CGWA) comparison area as implied by the separate estimates of water supplies for the two areas in IDWR's staff report (May 31, 2012). However, because information is not available to confirm that the areas are separate, the water supply is over-appropriated by 23,000 afa by existing and permitted uses (ERO, November 14, 2012, Table D).

c. Is the volume of evapotranspiration accurately estimated?

SPF expresses concern that, because the rate of evapotranspiration is the most uncertain parameter in the water budget, an overestimate of this parameter could result in a substantial underestimate of aquifer recharge (Page 2, Item No. 3). SPF does not suggest a more credible estimate for this parameter.

Response: IDWR used the best available data for estimating evapotranspiration in preparing its estimate. It is just as likely that the volume of evapotranspiration is too small, and hence the volume of aquifer recharge is too large in IDWR's estimate.

In the event that there is precipitation that exceeds evapotranspiration at times, reliable information is not available to estimate how much actually reaches the regional aquifer for use within the consolidated hearing study area. Precipitation in excess of evapotranspiration is retained in the soil profile to support vegetative growth during the

Mountain Home Corridor Response

January 31, 2013

growing season when precipitation is limited. This is particularly true for the generally southwest facing slopes of the recharge area that are likely to warm earlier than either Arrowrock or Anderson Ranch weather stations and are thus better able to use the early season moisture to exhibit higher evapotranspiration than at either weather station. All precipitation in excess of that needed for on-going evapotranspiration and to fill the root zone may not accrue as recharge to the regional aquifer because significant layers of sediment, previously discussed in this report, can prevent water from reaching the regional aquifer at a location to allow diversion and use within the consolidated hearing study area.

- d. Will failure to develop existing permits free up water for the pending applications?

SPF asserts that the net annual recharge is larger than IDWR's estimate if existing permits are not developed, but does not provide an estimate of the additional volume that will become available if the permits are not fully developed (Page 2, Item No. 5 and Page 9, Item No. 20).

Response: ERO identified only four active permits in the consolidated hearing study area (Table E, Page 37 and 38, ERO November 14, 2012). IDWR has now issued licenses confirming development of essentially the permitted amount for two of the permits (63-12447 Ark Properties/Mayfield Townsite and 63-12494 Danskin Properties). The remaining two permits (61-12090 Nevid and 63-32225 Intermountain Sewer) are associated with developments under consideration in the consolidated hearing. These permits, having priorities earlier in time than the pending applications for the same projects, can be expected to be fully developed before or in conjunction with developing the applications (if the applications are approved). There is no basis for concluding that the existing permits will not be fully developed to justify an increase in IDWR's estimate of net annual recharge.

- e. Is recharge greater than estimated in certain parts of the non-recharge area?

SPF suggests that portions of the "non-recharge area" may have greater infiltration rates than recognized in IDWR's recharge estimate (Page 7, Item 15). SPF does not provide an estimate of the land area involved or the increase in volume of recharge water that should be considered.

Response: IDWR describes the separation between the recharge and non-recharge areas as the 3,600-foot land surface contour representing the transition between the foothills and the plateau (IDWR, May 31, 2012, Page 5) and uses this as a boundary between areas of significant recharge potential and areas of limited recharge potential. This arbitrary separation of the recharge area from the non-recharge area makes it is as likely that infiltration rates are over estimated as under estimated.

Mountain Home Corridor Response

January 31, 2013

SPF observes that the beds of streams entering the non-recharge area can have high seepage rates. However, an increase in the estimate of recharge from precipitation falling directly on the non-recharge area is not justified because the portion of the area occupied by stream channels is insignificant compared to the entire non-recharge area. Percolation in stream channels in the non-recharge area of flow originating upstream in the area delineated as the recharge area is already included in the estimate of recharge for that area.

ERO reiterates its contention that the total volume of recharge in the non-recharge area should not be considered as water available for the developments under consideration in the consolidated hearing because most of the area is down gradient from the proposed development. All of the recharge is available only if the draw down resulting from ground water withdrawal for the developments is so severe as to reverse the gradient of the aquifer.

QUESTION NO. 2. Do ground water levels in the consolidated hearing study area behave differently than in the CGWA comparison area?

SPF points to ground water levels in the consolidated hearing study area that are more stable than those in the CGWA as a basis for asserting that ground water is available for the proposed projects and suggests the following as reasons why IDWR should give weight to this phenomenon to justify approval of the pending applications:

- a. Are results from recent, more extensive data collection efforts adequate to show that water levels are stable?

SPF notes that the more extensive collection of hydrologic data in the area for recent years indicates “relatively stable groundwater levels” (Page 6, Items 9 and 10).

Response: An abundance of data related to recent conditions during a period of above average precipitation does not substitute for a long-term record.

- b. Are ground water level decline problems only associated with a limited area, remote from the proposed development area?

SPF noted that the area of greatest ground water level declines is limited to the southern portion of the CGWA and that the affects of “approximately four decades” of pumping in the CGWA have not propagated into the portion of the consolidated hearing study area in which appropriations are sought (Pages 5 and 6, Item No. 8 and Page 11, Item No. 26).

Response: Existing ground water withdrawals in the CGWA are concentrated in the area noted by SPF, and as would be expected, ground water declines are also greater in this area. However, information and studies are available showing the spread of declines beyond the immediate area of pumping into the consolidated hearing study area. This information suggests that the rate of decline resulting from existing uses in the CGWA is

Mountain Home Corridor Response

January 31, 2013

increasing and that if ground water withdrawals are increased as proposed in the applications under consideration in the consolidated hearing, the rate of decline of ground water levels and the consequent impacts to the flow of Snake River will continue to increase.

IDWR's ground water change maps (IDWR, May 31, 2012 Page 7) show that ground water declines have migrated out of the CGWA into the consolidated hearing study area. These maps show that the area exhibiting the largest decline experienced more than 90 feet of decline in the latest decade compared to about 30 feet in the previous decade. This is because, at least in part, annual ground water pump withdrawals have not been at the maximum authorized rate every year during the four decades since development began (ERO, November 14, 2012 Pages 8 and 16). Figure 9 on Page 19 of IDWR's staff memorandum (IDWR, May 31, 2012) shows that the downward trend in ground water levels in the CGWA continues unabated decades after further development was halted.

The aquifer analysis done by ERO (ERO, November 14, 2012 Pages 18 and 19) shows ground water declines of more than 20 feet in a hypothetical observation well located north of I-84 on the boundary between IDWR's consolidated hearing study area and CGWA comparison area resulting from 20 years of withdrawals under existing rights. Adding the affects of using ground water during the same 20-year period as proposed in the applications under consideration in the consolidated hearing more than doubles the ground water level decline at this location.

The boundaries of the CGWA and the Mountain Home Ground Water Management area were drawn based upon information available to IDWR in the early 1980s. The continuing ground water declines and the spread of the declines beyond the boundaries justify a review to expand the boundaries.

- c. Can ground water declines to the extent now occurring in the CGWA be expected to occur in the area proposed for development?

SPF takes exception to IDWR's conclusion that ground water declines similar to those observed in the CGWA will occur in the consolidated hearing study area if the applications are approved. SPF notes that estimated withdrawals in the CGWA are about triple IDWR's estimate of recharge in the CGWA comparison area while the present withdrawals of ground water in the consolidated hearing study area are only a fraction of the estimated recharge to the consolidated hearing study area (Page 3, Item No. 8 and Page 12, Item No. 29). SPF calculated that the annual volume that will be depleted from the aquifer if the proposed projects are all fully developed is an additional 14,200 afa. This amount is double the average recharge estimate for the consolidated hearing study area aquifers (Pages 2 and 3, Item No. 6 and Pages 10 and 11, Item Nos. 23, 24 and 25).

Response: SPF's estimate of water required for the proposed uses is lower than the volumes authorized under the vested rights being transferred and its own volume estimates in reports filed on behalf of the applicants concerning the adequacy of the water

Mountain Home Corridor Response

January 31, 2013

supply for the requested projects. Table A, Page 31, of ERO's first report submitted in this matter indicates that a total of about 19,000 afa is sought by the applications pending in the consolidated hearing (ERO, November 14, 2012). In any case, IDWR is not authorized to issue permits for a quantity of water exceeding the average rate of future natural recharge whether exceeded by "only" twice the amount as asserted by SPF or the 10-fold amount found by IDWR (§42-237ag, Idaho Code).

- d. Do IDWR's water level decline maps accurately define the extent of ground water declines in the consolidated hearing study area from pumping in the CGWA?

SPF suggested that the ground water declines "extending west and southwest (i.e., outside) of the CGWA in the consolidated cases study area" are "software interpolations unsupported by actual ground water-level data" (Page 5, Item No. 4). SPF also questioned whether the observed ground water level declines in the southwestern portion of the CGWA are associated with all of the aquifer zones encountered within the open interval of the wells or with only individual aquifer zones (Page 5, Item No. 5).

Response: Relative to IDWR's estimate of ground water declines in the area west and southwest of the CGWA, ground water level data are not available from this area to support or refute the results of IDWR's water level analysis. The program used by IDWR to estimate the location of the contour lines is supportable unless ground water level decline data or technical information is available to show that faults or changes in aquifer properties skew the results.

SPF does not elaborate on how the open aquifer interval issue has significance relative to ground water levels and the ground water supply available in the area. The well SPF references as having an open interval of over 1000 feet is apparently misidentified. Without information to document that some of the aquifer zones encountered have separate water sources, this matter will not alter IDWR's finding that water supplies in the CGWA comparison area are over appropriated by existing water rights.

- e. Are ground water level changes in the consolidated hearing study area caused by regional or local conditions?

SPF notes that water levels have risen about 10 feet since 1993 in well 02S4E-09DDD2 (Page 5, Item No. 7). SPF further notes "It is unclear whether this rise reflects regional or local conditions."

Response: IDWR's hydrographs for other wells in the CGWA nearest to well 02S4E-09DDD2 exhibit declines in water level throughout the period of record indicating that the anomalous increase noted for well 02S4E-09DDD2 is related to "local" conditions such as pumping of a nearby well (note the greater yearly fluctuation in water level observed in IDWR's hydrograph for this well since the early 1980s).

Mountain Home Corridor Response

January 31, 2013

QUESTION NO. 3. How will development and use of ground water as proposed in the applications affect flows in Snake River?

SPF found that the depletion of flows to the Snake River will not exceed 9.8 cfs (i.e. IDWR's estimate of average annual natural recharge to the consolidated hearing study area although SPF argues for a higher estimate), that this depletion is insignificant in comparison to flows in this reach of Snake River and will not be realized for decades in the future (Page 3, Item No. 7 and Page 12, Item No. 28).

Response: SPF's estimate understates the likely amount of the depletion of Snake River flows. More importantly, comparing the amount of this depletion in flow to the normal flow in the reach or even to the established minimum flows has little if any relevance to IDWR's responsibility to prevent injury to senior priority water rights, including minimum stream flows, and to reallocate trust water. Said another way, an actual depletion of any amount, even if not measurable, reduces water availability to senior priority water rights whenever flows are not adequate to satisfy all rights calling for water. The following factors should be considered when evaluating whether and under what conditions further depletions to Snake River flows can be allowed:

- a. A year-round reduction in flow of 9.8 cfs (the reduction will likely be higher as discussed below) resulting from development of the projects as proposed in the pending applications is a significant share of the 600 cfs of trust water and of the 150 cfs increment of trust water reserved for DCMI purposes. When the Swan Falls Agreement was signed in 1984, these flow rates were expected to be available year-round to support future development in southern Idaho. Decisions on the pending applications must incorporate the criteria set out in Idaho law for appropriating water and for reallocating trust water.
- b. The affects of pumping will reach outside of the consolidated hearing study area to tap ground water supplies not included in the estimate (ERO November 14, 2012, Page 19) thereby ultimately further reducing inflow to Snake River. If the projects as applied for are approved and developed from ground water, SPF's estimated depletion of 14,200 afa will ultimately reduce the average rate of flow in Snake River by 19.6 cfs (SPF, November 15, 2012, Page 11, Item No. 25).
- c. Flow in the Snake River could be drawn into the aquifer if pumping levels fall below the level of the river. A substantial lowering of ground water levels will be required to induce flow from Snake River into the regional aquifer, but a municipality pressed for adequate water supplies may find that chasing ground water even to these levels is the most feasible way of obtaining water to sustain the community.
- d. Larger diversion rates could be sought from Snake River as an alternate source to save the communities created as a result of approval of all or some of the pending applications if ground water supplies are not adequate to complete or sustain the projects. The diversion rate sought from Snake River would likely approximate the

Mountain Home Corridor Response

January 31, 2013

diversion rates applied for in the applications (including those for irrigation) totaling nearly 85 cfs (ERO November 14, 2012, Table A). Other projects (such as those evidenced by withdrawn, rejected and voided applications and lapsed permits, most of which are associated with the individuals and entities that are applicants for the pending applications in the consolidated hearing) can be expected to join in a project to bring water into the area using a Snake River diversion. Potential projects already identified by inactive filings total another 57 cfs (ERO November 14, 2012 Table B) and additional projects could be identified if a pipeline from Snake River is seriously pursued.

Applications filed subsequent to those included in the consolidated hearing are another indication of continuing interest in diverting water for use in the consolidated study area. IDWR's electronic record lists two such applications: Application for Permit No. 61-12271 seeking 1.25 cfs for domestic and fire protection (voided October 1, 2012) and Application for Permit No. 61-12275 seeking 6 cfs to irrigate 320 acres.

- e. IDWR is obligated to fully protect the portion of IPCo's water rights not subordinated in the Swan Falls Agreement and the matching minimum stream flow rights held by the IWRB. At this time, nearly three decades after the Agreement, it is beginning to be realized that the minimum stream flow at Murphy Gage may constrain water diversions even for presently existing uses. Thus, the postulated increment of 600 cfs of "firm" trust water estimated at the time of the Agreement may never have been available, may have been reduced by changed conditions, such as droughts and conservation practices, in the Snake River watershed that have reduced base flows in the reach, and/or has been substantially depleted by the additional diversion and use of water developed since the Agreement (in part through permits issued for use of trust water).

ERO's analysis of Snake River flow (ERO November 14, 2012, Pages 22 to 26) shows that the average daily winter flow of 5600 cfs at Murphy Gage required by the agreement will not be met by 2025 if the rate of decline noted since 1981 continues. Similarly, if the rate of decline continues, the 3900 cfs summertime flow at Murphy Gage required by the agreement will not be met by average daily flow during low flow periods of the year by 2025 or sooner. The affect on water availability represented by the continuing decline in base flows must be considered as IDWR evaluates applications for new consumptive uses that will have the effect of further reducing these flows during the upcoming decades.

- f. While routine violations of the minimum stream flows at Murphy Gaging Station are in the near future, short-term violations during critical flow periods are already a concern. The preliminary order issued creating Water District No. 2 in the Milner to Murphy reach of Snake River found that "Snake River flows measured at Murphy Gaging Station have diminished over time and, in recent years, have approached the minimums established as part of the Swan Falls Agreement" (IDWR, May 1, 2012,

Mountain Home Corridor Response

January 31, 2013

Page 1, Finding 2). Responding to exceptions to the preliminary order, IDWR determined that although a water distribution crisis has not yet occurred in the Milner to Murphy reach of Snake River, the “potential for significant water administration is real” (IDWR, July 10, 2012). New consumptive uses depleting flows in this reach, including the projects under consideration in the consolidated hearing, will hasten administration by priority in Water District No. 2 causing curtailment of diversions under existing senior priority water rights that otherwise would have had water available.

- g. Permits and licenses issued by IDWR to use trust water are subject to a term condition such as: “This right is for the use of trust water and is subject to review 20 years after issuance of the permit to determine availability of water and to re-evaluate the public interest.” Some permits and the license subsequently issued have reached or are approaching the time for such review. IDWR has notified holders of such rights that reviews will be initiated.

A list prepared by IDWR dated March 28, 2011 identifies 680 permits and licenses that have been issued with a term condition (IDWR Staff Memorandum, March 28, 2011 accessed in IDWR’s electronic file for Permit No. 35-8359). The total diversion rate authorized under these permit and licenses is more than 1100 cfs. Of these, 486 have an irrigation component, totaling more than 800 cfs. About 90 percent of these filings have priority dates earlier than July 28, 2006, the earliest date of filing for the applications in the consolidated hearing. The continued availability of water will be a vital consideration as IDWR conducts the term review of these rights. Under the appropriation doctrine during times of scarcity, trust water flows are available for use by senior priority rights, including those subject to term review, in preference to junior priority rights.

In addition to the permits and licenses already issued for trust water, IDWR’s water right records list over 850 pending applications seeking, in total, nearly 2500 cfs of trust water (IDWR electronic data base query). About 90 percent of these filings were made prior to July 28, 2006, the earliest date of filing for the applications in the consolidated hearing. To the extent that these filings and the pending applications in the consolidated hearing seek trust water and/or water sources interconnected with trust water, the additional water depletion if any or all of these earlier applications are ultimately approved must be considered in determining water availability for the applications pending in the consolidated hearing.

LIST OF REFERENCES

ERO, November 14, 2012. Water Supply Evaluation for Proposed Projects Along the I-84 Corridor. David B. Shaw and Norman C. Young, ERO Resources Corp.

IDWR, September 1976. Geothermal Investigations in Idaho, Part 8, Heat Flow in the Snake River Plain Region, Southern Idaho. Charles Brott, David D. Blackwell (Southern Methodist University) and John C. Mitchell, Idaho Department of Water Resources.

IDWR, March 28, 2011. Memorandum in Response to Request for Staff Memorandum (Permit No. 35-8359). Shelley W. Keen, Idaho Department of Water Resources.

IDWR, January 24, 2012. Order Creating Contested Case and Consolidating Protested and Unprotested Applications. Gary Spackman, Interim Director, Idaho Department of Water Resources.

IDWR, May 1, 2012. Preliminary Order in the Matter of the Creation of Water District No. 2, Snake River from Milner Dam to the Murphy Gage Below Swan Falls Dam. Jeff Peppersack, Hearing Officer, Idaho Department of Water Resources.

IDWR, May 31, 2012. Sufficiency of Water Supply for Water Right Applications and Transfers along the I-84 Corridor. Craig Tesch, Hydrology Section, State Office, Idaho Department of Water Resources.

IDWR, July 10, 2012. Final Order in the Matter of the Creation of Water District No. 2, Snake River from Milner Dam to the Murphy Gage Below Swan Falls Dam. Gary Spackman, Interim Director, Idaho Department of Water Resources.

SPF, November 15, 2012. Response to IDWR Staff Memo regarding the sufficiency of water supply for water right applications and transfers along the I-84 corridor. Christian R. Petrich, Ph.D., P.E., P.G., SPF Water Engineering LLC.

Welhan, February 2012. Preliminary Hydrologic Analysis of the Mayfield Area, Ada and Elmore Counties, Idaho. John A. Welhan, Idaho Geological Survey.

IDAHO DEPARTMENT OF WATER RESOURCES

WELL DRILLER'S REPORT

Page 2 of 2 Pages

Office Use Only
Inspected by _____
Twp _____ Rge _____ Sec _____
1/4 _____ 1/4 _____ 1/4 _____
Lat _____ Long _____
_____ Air _____ Flowing Artesian

1. WELL TAG NO. D 0019724
DRILLING PERMIT NO. _____
Other IDWR No. _____

2. OWNER:
Name Kenneth W. Lange
Address 15888 E. Monroe Ave. — HC34
City Boise State ID Zip 83716

3. LOCATION OF WELL by legal description:

Sketch map location must agree with written location.

North or South
Rge. 4 E East or West
Sec. 29 SW 1/4 NW 1/4 SE 1/4
Gov'l Lot _____ County Elmore
Lat _____ Long _____

Address of Well Site 15888 E. Monroe Ave. — 1 mile SE of
Orchard Town Site (NE Side of RR tracks) City Orchard

Lt. _____ Blk. _____ Sub. Name _____

4. USE:

☒ Domestic ☐ Municipal ☐ Monitor ☐ Irrigation
☐ Thermal ☐ Injection ☐ Other _____

5. TYPE OF WORK check all that apply (Replacement etc.)
☒ New Well ☐ Modify ☐ Abandonment ☐ Other _____

6. DRILL METHOD

☐ Air Rotary ☒ Cable ☐ Mud Rotary ☐ Other _____

7. SEALING PROCEDURES

SEAL/FILTER PACK		AMOUNT		METHOD
Material	From	To	Sacks or Pounds	
Bentonite &	4	168.6	550 lb	Open hole maintained with slurry—overbore—Casing Run into full hole
Naive clays	4	168.6	2700 lb	

Was drive shoe used? ☒ Y ☐ N Shoe Depth(s) 168.6
Was drive shoe seal tested? ☒ Y ☐ N How? Slurry did not leak into well

8. CASING/LINER:

Diameter	From	To	Gauge	Material	Casing	Liner	Welded	Threaded
8 5/8	+ 1.4	168.6	0.250	Steel	☒			
6 5/8	+ 1.75	263.0	0.250	Steel	☒			
5 9/16	537.1	574.17	0.188	Steel top pipe		☒		
5 9/16	574.17	608.28	0.258	Steel		☒		

Length of Headpipe 71.18 ft Length of Tailpipe 0.97

9. PERFORATIONS/SCREENS

Perforations Method _____
Screens Screen Type Continuous Slot Wire Wound

From	To	Slot Size	Number	Diameter	Material	Casing	Liner	Assbly
608.28	618.53	0.025 inch		5 9/16	Stainless		☒	

10. STATIC WATER LEVEL OR ARTESIAN PRESSURE:

485.0 ft. below ground Artesian pressure _____ lb.
Depth flow encountered _____ ft. Describe access port or control devices: 6" I.D. of casing by removing well cap.

11. WELL TESTS:

☒ Pump ☐ Bailer

Yield gal./min.	Drawdown	Pumping Level	Time
13.0	1.2 ft	486.2	4.5 hours

Water Temp. _____ Excellent Bottom hole temp. _____

Water Quality test or comments: _____

Depth first Water Encounter 526

12. LITHOLOGIC LOG: (Describe repairs or abandonment)

Bore Dia	From	To	Remarks: Lithology, Water Quality & Temperature	Y	N
10	0	175 ft			N
8	175	426 ft			N
6	426	620 ft		Y	N
	336	357	Sands and Silts, Caving, Tan		N
	357	386	Basalt, Medium Hard, Grey		N
	386	401	Granitic Sand and Clay, Red Brown		N
	401	424	Basalt, Medium Hard, Grey		N
	424	523	Sandy Silts & Silty Sands, Brown-Tan		N
	523	526	Clay, Gravelly & Sandy, Brown		N
	526	532	Sand, Clayey, Brown	Y	
	532	534	Clay, Gravelly, Grey		N
	534	537	Clay, Gravelly, Brown		N
	537	547	Sand, Clayey, Brown	Y	
	547	562.3	Sandy Silts & Silty Sands, Brown	Y	N
	562.3	588	Basalt, Brown		N
	588	597	Cinders, Sand, then Clay, Brown	Y	
	597	609	Clay, Gravelly, Brown		N
	609	619	Sand, Coarse, Poorly Sorted	Y	
	619	619.5	Clay, Brown		N

RECEIVED

OCT 10 2002

WATER RESOURCES
WESTERN REGION

RECEIVED

OCT 18 2002

Department of Water Resources

Completed Depth 619.5 ft (Measurable)
Date: Started March 11, 2002 Completed Sept. 3, 2002

13. DRILLER'S CERTIFICATION

I/We certify that all minimum well construction standards were complied with at the time the rig was removed.

Company Name Artesian Co. Firm No. 318

Firm Official Hugh Harden Date 10/8/02

and Driller or Operator Hugh Harden Date October 8, 2002

IDAHO DEPARTMENT OF WATER RESOURCES
WELL DRILLER'S REPORTUse Typewriter
or
Ball Point Pen

56757

1. DRILLING PERMIT NO. 61 - 94 - W - 0027 - 000
Other IDWR No. _____

2. OWNER:

Name LEONARD EISEMANAddress 802 East Pennsylvania Ave.City Boise State ID Zip 83706

3. LOCATION OF WELL by legal description:

Sketch map location must agree with written location.

N	
W	E
S	

Twp. 1 North ☐ or South ☒
Rge. 4 East ☒ or West ☐
Sec. 15 1/4 NE 1/4 NE 1/4
Gov't Lot _____ County Elmore

Address of Well Site Simco Rd.City Mountain Home

(Give at least name of road + Distance to Road or Landmark)

Lt. _____ Blk. _____ Sub. Name _____

4. PROPOSED USE:

☒ Domestic ☐ Municipal ☐ Monitor ☐ Irrigation
☐ Thermal ☐ Injection ☐ Other _____

5. TYPE OF WORK

☒ New Well ☐ Modify or Repair ☐ Replacement ☐ Abandonment

6. DRILL METHOD

☐ Mud Rotary ☒ Air Rotary ☐ Cable ☐ Other _____

7. SEALING PROCEDURES

SEAL/FILTER PACK		AMOUNT		METHOD
Material	From	To	(Sacks or Pounds)	
Pentonite	0	250'	20	overbore

Was drive shoe used? ☒ N ☐ QWas drive shoe seal tested? ☒ N ☐ Q How? _____

8. CASING/LINER:

Diameter	From	To	Gauge	Material	Casing	Liner	Welded	Threaded
8.625	0	250'	.250	steel	☒	☒	☐	☐
6.625	2'	425'	.250	steel	☒	☒	☐	☐
5.57	436'	448'	.188	steel	☐	☒	☐	☐

Length of Headpipe 7' Length of Tailpipe 5'

9. PERFORATIONS/SCREENS

☐ Perforations

Method _____

☒ ScreensScreen Type V-wire

From	To	Slot Size	Number	Diameter	Material	Casing	Liner
453'	448'	.040		5.57	S.S.	☐	☒
436'	431'	.030		5.57	S.S.	☐	☒
						☐	☐

10. STATIC WATER LEVEL OR ARTESIAN PRESSURE:

335 ft. below ground Artesian pressure _____ lb.

Depth flow encountered _____ ft. Describe access port or control devices: _____

11. WELL TESTS:

☐ Pump ☐ Baller ☒ Air ☐ Flowing Artesian

Yield gal./min.	Drawdown	Pumping Level	Time
35			5hr.

Water Temp. _____ Bottom hole temp. _____

Water Quality test or comments: _____

12. LITHOLOGIC LOG: (Describe repairs or abandonment)

Bore Dia.	From	To	Remarks: Lithology, Water Quality & Temperature	Y	N
8"	0	2'	Topsoil		
"	2'	11'	Brown Clay		
"	11'	18'	Sand & Gravel		
"	18'	21'	Brown Clay		
"	21'	43'	Sand & Gravel		
"	43'	65'	Clay w/Sand		
"	65'	80'	Coarse Sand		
"	80'	84'	Sandy clay		
"	84'	108'	Sand w/gravel		
"	108'	140'	Sandy clay		
"	140'	150'	Coarse sand		
"	150'	155'	Sand w/gravel		
"	155'	161'	Sandy clay		
"	161'	190'	Coarse sand w/clay		
"	190'	203'	Cemented sand & gravel		
"	203'	228'	Clay w/sand & gravel		
"	228'	240'	Coarse Sand		
"	240'	330'	Sandstone		
"	330'	340'	Coarse sand		
"	340'	356'	Brown clay		
"	356'	365'	Coarse sand		
"	365'	375'	Brown clay		
"	375'	386'	Coarse sand		
"	386'	409'	Clay w/sand seams		
"	409'	415'	Brown clay		
"	415'	428'	Coarse sand		X
"	428'	430'	Brown clay		
6"	430'	439'	Coarse sand		X
"	439'	441'	Brown clay		
"	441'	458'	Sand & Gravel		X
"	458'	467'	Brown clay		

Completed Depth 458'

(Measurable)

Date: Started June 11, 1994 Completed June 26, '94

13. DRILLER'S CERTIFICATION

We certify that all minimum well construction standards were complied with at the time the rig was removed.

Firm Name Hiddleston & Son, Inc. Firm No. 35Firm Official M. Hiddleston Date 7/19/94

and _____

Supervisor or Operator _____ Date _____

(Sign once if Firm Official & Operator)

FORWARD WHITE COPY TO WATER RESOURCES

61

Form 238-7
6/07

Pg 1 of 2

IDAHO DEPARTMENT OF WATER RESOURCES
WELL DRILLER'S REPORT

903350-850338

1. WELL TAG NO. D 0052631

Drilling Permit No. 903350-850338

Water right or Injection well # 63-33036

2. OWNER

Name Pacific West Land, LLC Test Well #1

Address 911 Hildebrand Lane NE #203

City Bainbridge Island State WA Zip 98110

3. WELL LOCATION:

Twp. 1 North ☐ or South ☒ Rge. 4 East ☒ or West ☐

Sec. 8 NW 1/4 SW 1/4 NE 1/4

Gov't Lot _____ County Ada

Lat. N43° 21.237" (Deg. and Decimal minutes)

Long. W116° 0.243" (Deg. and Decimal minutes)

Address of Well Site 2.3 mi. S of I84 on S. Orchard Access Rd. &

200 ft. E. of Orchard City Boise

(Plot, at least 1/4 mile, of road & direction to road on landmark)

Lot. _____ Blk. _____ Sub. Name _____

4. USE:

☐ Domestic ☐ Municipal ☒ Monitor ☐ Irrigation ☐ Thermal ☐ Injection☒ Other Piezometer Nest

5. TYPE OF WORK check all that apply (Replacement etc.)

☒ New Well ☐ Replacement well ☐ Modify existing well☐ Abandonment ☐ Other Well Design by Hydro Logic, Inc.

6. DRILL METHOD:

☐ Air Rotary ☒ Mud Rotary ☐ Cable ☐ Other AR 110' to 310'

7. SEALING PROCEDURES

Seal material	From (ft)	To (ft)	Quantity (lbs or ft ³)	Placement method/procedure
3/4" Baroid Chips	0'	19'	11.9 ft.	Poured

8. CASING/LINER:

Diameter (nominal)	From (ft)	To (ft)	Gauge/Schedule	Material	Casing	Liner	Threaded	Welded
16"	0'	19'	.250	Steel	☒	☐	☐	☒
12"	0'	110'	.375	Steel	☒	☐	☐	☒
10"	+2'	295'	.250	Steel	☒	☐	☐	☒

Was drive shoe used? ☐ Y ☒ N Shoe Depth(s) _____

9. PERFORATIONS/SCREENS:

Perforations ☐ Y ☒ N Method _____Manufactured screen ☒ Y ☐ N Type 2" PVC Sch80 Slotted

Method of installation _____

From (ft)	To (ft)	Slot size	Number/ft	Diameter (nominal)	Material	Gauge or Schedule
932'	1052'	.020	Zone1	2"	PVC	Sch80
732'	822'	.020	Zone2	2"	PVC	Sch80
575'	645'	.020	Zone3	2"	PVC	Sch80

Length of Headpipe None Length of Tailpipe None

Packer ☐ Y ☒ N Type _____

10. FILTER PACK:

Filter Material	From (ft)	To (ft)	Quantity (lbs or ft ³)	Placement method
See Table Pg. 2				

11. FLOWING ARTESIAN:

Flowing Artesian? ☐ Y ☒ N Artesian Pressure (PSIG) See Pg. 2

Describe control device Locked Steel Enclosure

12. STATIC WATER LEVEL and WELL TESTS:

Depth first water encountered (ft) 516' Static water level (ft) See Pg. 2

Water temp. (°F) See Pg. 2 Bottom hole temp. (°F) 78.59°F

Describe access port 3 - 2" Tube Wells inside Locked Well Head

Well test:

Test method:

Drawdown (feet)	Discharge or yield (gpm)	Test duration (minutes)	Pump	Bailer	Air	Flowing artesian
No Pump	Testing	Other	☐	☒	☒	☐
Than	Air-Lifting	and				
Pump	Samples					

Water Quality test or comments: See Table Pg. 2

13. LITHOLOGIC LOG and/or repairs or abandonment:

Bore Dia. (in)	From (ft)	To (ft)	Remarks, lithology or description of repairs or abandonment, water temp.	Water Y N
20	0	19	Tan & Brown Sand	X
16	19	26	Tan & Brown Sand	X
16	26	47	Tan Coarse Sand	X
16	47	68	Tan Coarse Sand & Clay	X
16	68	73	Tan Coarse Sand	X
16	73	86	Gravel with Some Sand	X
16	86	105	Sticky Tan Clay	X
16	105	107	Basalt	X
16	107	110	Tan Clay & Dark Brown Cinders	X
12	110	119	Black Basalt & Hard Cinders	X
12	119	154	Black Fractured Basalt	X
12	154	176	Red Basalt Cinders	X
12	176	200	Basalt	X
12	200	208	Sand, Gravel, & Basalt	X
12	208	220	Brwn Clay, Sand & Reddish-Brwn Cinders	X
12	220	300	Coarse Sand & Gravel	X
10	300	338	Coarse Sand & Gravel	X
10	338	396	Tan Clay	X
10	396	432	Coarse Sand & Tan Clay	X
10	432	451	Coarse Sand	X
10	451	527	Dark Tan Clay	X
10	527	568	Small & Coarse Sand	X
10	568	616	Clayey Tan Sand	X
10	616	652	White Sand with Tan Clay Beds	X
10	652	697	Large White Coarse Sand	X
10	697	708	Small Sand	X
10	708	732	Gray & Clayey Tan Sand	X
10	732	748	Medium Gray Sand	X
10	748	772	Sticky Grayish Sandy Blue Clay	X
10	772	824	Small Gray Sand	X
10	824	927	Grayish Sandy Blue Clay	X
10	824	992	Medium Dark Gray Sand	X
Completed Depth (Measurable)				1082'
Date: Started		1/7/2008	Completed	
		3/21/2008		

14. DRILLER'S CERTIFICATION

I/We certify that all minimum well construction standards were complied with at the time the rig was removed.

Company Name Treasure Valley Drilling Co. No. 560

*Principal Driller _____ Date 4/2/2008

*Driller _____ Date 4/2/2008

*Operator II _____ Date _____

Operator I _____ Date _____

* Signature of Principal Driller and rig operator are required.

IDAHO DEPARTMENT OF WATER RESOURCES

WELL DRILLER'S REPORT

1. WELL TAG NO. D 0052631Drilling Permit No. 903350-850338Water right or injection well # 63-33036**2. OWNER**Name Pacific West Land, LLC Test Well #1Address 911 Hildebrand Lane NE #203City Bainbridge Island State WA Zip 98110**3. WELL LOCATION:**Twp. 1 North ☐ or South ☒ Rge. 4 East ☒ or West ☐Sec. 8 NW 1/4 SW 1/4 NE 1/4
10 acres 40 acres 160 acresGov't Lot _____ County AdaLat. N 43° 21.237" (Deg. and Decimal minutes)Long. W 116° 0.243" (Deg. and Decimal minutes)Address of Well Site 2.3 mi. S of I84 on S. Orchard Access Rd. &200 ft. E. of Orchard City Boise

Name of land owner of road - Distance to Road or Landmark

Lot. _____ Blk. _____ Sub. Name _____

4. USE:☐ Domestic ☐ Municipal ☒ Monitor ☐ Irrigation ☐ Thermal ☐ Injection
☒ Other Piezometer Nest**5. TYPE OF WORK** check all that apply (Replacement etc.)☒ New Well ☐ Replacement well ☐ Modify existing well
☐ Abandonment ☐ Other Well Design by Hydo Logic, Inc.**6. DRILL METHOD:**☐ Air Rotary ☒ Mud Rotary ☐ Cable ☐ Other AR 110' to 310'**7. SEALING PROCEDURES**

Seal material	From (ft)	To (ft)	Quantity (lbs or ft³)	Placement method/procedure
3/4" Baroid Chips	0'	19'	11.9 ft.	Poured

8. CASING/LINER:

Diameter (nominal)	From (ft)	To (ft)	Gauge/Schedule	Material	Casing	Liner	Threaded	Welded
2"	+2'	932	Sch80	PVC	☒	☐	☒	☐
2"	+2'	732	Sch80	PVC	☒	☐	☒	☐
2"	+2'	575	Sch80	PVC	☒	☐	☒	☐

Was drive shoe used? ☐ Y ☒ N Shoe Depth(s) _____**9. PERFORATIONS/SCREENS:**Perforations ☐ Y ☒ N Method _____Manufactured screen ☒ Y ☐ N Type PVC Sch80 SlottedMethod of installation Lowered & Tagged into Place

From (ft)	To (ft)	Slot size	Number/ft	Diameter (nominal)	Material	Gauge or Schedule
932'	1052'	.020	Zone1	2"	PVC	Sch80
732'	822'	.020	Zone2	2"	PVC	Sch80
575'	645'	.020	Zone3	2"	PVC	Sch80

Length of Headpipe None Length of Tailpipe NonePacker ☐ Y ☒ N Type _____**10. FILTER PACK:**

Filter Material	From (ft)	To (ft)	Quantity (lbs or ft³)	Placement method
			See Table	

11. FLOWING ARTESIAN:Flowing Artesian? ☐ Y ☒ N Artesian Pressure (PSIG) See TableDescribe control device Locked Steel Enclosure**12. STATIC WATER LEVEL and WELL TESTS:**Depth first water encountered (ft) 516' Static water level (ft) See BelowWater temp. (°F) See Below Bottom hole temp. (°F) 78.59°FDescribe access port 3 - 2" Tube Wells inside Locked Well Head**Well test:****Test method:**

Drawdown (feet)	Discharge or yield (gpm)	Test duration (minutes)	Pump	Bailer	Air	Flowing Artesian
No Pump	Testing	Other	☐	☒	☒	☐
Than	Air-Lifting	and				
Pump	Samples					

Water Quality test or comments: See Table Below**13. LITHOLOGIC LOG and/or repairs or abandonment:**

Bore Dia. (in)	From (ft)	To (ft)	Remarks, lithology or description of repairs or abandonment, water temp.	Water Y N
10	992	1027	Medium Sand with Some Blue Clay	X
10	1027	1063	Medium Gray Sand	X
10	1063	1087	Sticky Blue Clay	X
SEALING PROCEDURES:				
0	19	11.9 Ft	3/4" Bentonite Chips	Poured
105	110	1.9 Ft	3/4" Bentonite Chips	Poured
0	105	4.0 CY	Cement Grout	Pumped
0	300	3.2 CY	Cement Grout	Pumped
895	877	8.3 Ft	30% Bentonite Grout	Pumped
877	862	6.7 Ft	Cement Grout	Pumped
862	828	9.9 Ft	30% Bentonite Grout	Pumped
709	689	8.2 Ft	30% Bentonite Grout	Pumped
689	672	6.7 Ft	Cement Grout	Pumped
672	645	9.5 Ft	30% Bentonite Grout	Pumped
532	493	9.9 Ft	30% Bentonite Grout	Pumped
0	493	7.2 CY	Cement Grout	Pumped

FILTER PACK:

1082	895	"Birdseed" #8-#16
828	729	"Birdseed" #8-#16
645	532	"Birdseed" #8-#16

WATER LEVEL, TEMPERATURE, CHEMISTRY

Z-1	1052	932	SWL=523.8, 70.0F, pH=8.53; 275µS
Z-2	822	732	SWL=522.6; 65.0F; pH=8.50; 259µS
Z-3	645	575	SWL=516.21; not meas.; not meas;

ARTESIAN PRESSURES:

Z-1	371	Ft. or 161 psig
Z-2	186	Ft. or 81 psig
Z-3	16	Ft. or 7 psig

Completed Depth (Measurable) 1082'Date: Started 1/7/2008 Completed 3/21/2008**14. DRILLER'S CERTIFICATION**

I/We certify that all minimum well construction standards were complied with at the time the rig was removed.

Company Name Treasure Valley Drilling Co. No. 560Principal Driller _____ Date 4/2/2008Driller _____ Date 4/2/2008

Operator II _____ Date _____

Operator I _____ Date _____

* Signature of Principal Driller and rig operator are required.

IDAHO DEPARTMENT OF WATER RESOURCES

WELL DRILLER'S REPORT

Office Use Only		
Inspected by _____		
Twp _____	Rge _____	Sec _____
_____ 1/4	_____ 1/4	_____ 1/4
Lat. : :	Long: : :	

1. DRILLING PERMIT NO. _____
Other IDWR No. D0019379

2. OWNER:

Name **JIM PHAGAN**
Address **4200 PASADENA DR. #30**
City **BOISE** State ID Zip **83705**

3. LOCATION OF WELL by legal description:

Sketch map location must agree with written location

W  E

Twp. 1 North ☒ or South ☐
 Rge. 4 East ☒ or West ☐
 Sec. 33 $\frac{1}{4}$ NE 1/4 NW 1/4
 10 acres 40 acres 160 acres

S Gov't lot _____ County ADA

Lat: _____ : _____ : _____ Long: _____ : _____ : _____
Address of Well Site 23735 DESERT WIND

City BC
(Give at least name of road + Distance to Road or Landmark)

Lt. _____ Blk. _____ Sub. Name REGINA HEIGHTS

4. USE:

☒ Domestic ☐ Municipal ☐ Monitor ☐ Irrigation
☐ Thermal ☐ Injection ☐ Other

5. TYPE OF WORK check all that apply (Replacement etc.)

☒ New Well ☐ Modify ☐ Abandonment ☐ Other _____

6. DRILL METHOD

☒ Air Rotary ☐ Cable ☐ Mud Rotary ☐ Other

7. SEALING PROCEDURES

SEAL/FILTER PACK			AMOUNT	METHOD
Material	From	To	Sacks or Pounds	
BENTONITE	0	18	9 SACKS	OVERBORE

Was drive shoe used? ☒ Y ☐ N Shoe Depth(s) _____

Was drive shoe seal tested? ☐ Y ☒ N How?

8. CASING/LINER:

Diameter	From	To	Gauge	Material	Casing	Liner	Welded	Threaded
6	+2	560	250	ST	☒	☐	☒	☐
					☐	☐	☐	☐
					☐	☐	☐	☐

Length of Headpipe 10'8" Length of Tailpipe

9. PERFORATIONS/SCREENS

☐ Perforations Method _____
☒ Screens Screen Type telescoping

From	To	Slot Size	Number	Diameter	Material	Casing	Liner
559	569	20		5"	ST ST	☐	☐
						☐	☐
						☐	☐

10. STATIC WATER LEVEL OR ARTESIAN PRESSURE:

481 ft. below ground Artesian Pressure _____ lb
Depth flow encountered _____ ft. Describe access port or control devices:

11. WELL TESTS:

☐ Pump ☐ Bailer ☒ Air ☐ Flowing Artesian

Yield gal/min.	Drawdown	Pumping Level	Time
17		560	2 HRS

Water Temp. _____ Bottom hole temp. _____

Water Quality test or comments:

Depth first Water Encountered 487

12. LITHOLOGIC LOG: (Describe repairs or abandonment)

Water			Remarks: Lithology, Water Quality & Temp.	Y	N
Bore Dia	From	To			
10	0	3	BROWN TOPSOIL		X
10	3	14	BROWN SANDY CLAY		X
10	14	18	TAN SANDY CLAY		X
8	18	29	TAN SANDY CLAY		X
8	29	57	BROWN CLAY, SAND & SMALL GRAVEL		X
8	57	81	BLACK LAVA		X
8	81	212	TAN CLAY W/SAND		X
8	212	244	STICKY TAN CLAY		X
8	244	309	STICKY TAN CLAY W/STRIPS BROWN SAND		X
8	309	376	BROWN SAND W/SMALL STRIPS TAN CLAY		X
8	376	421	CEMENTED BROWN SAND		X
8	421	480	STRIPS BROWN SAND & TAN CLAY		X
6	480	487	STRIPS BROWN SAND & TAN CLAY		X
6	487	511	FINE BROWN & CLEAR QUARTZ SAND	X	
6	511	539	STICKY TAN CLAY		X
6	539	541	VERY FINE BROWN & MICA SAND	X	
6	541	545	DIRTY BROWN SAND & SOFT TAN CLAY		X
6	545	562	MEDIUM STICKY TAN CLAY		X
6	562	572	COARSE CLEAR QUARTZ SAND & PEA GRAVEL		X
			RECEIVED		
			JAN 03 2002		
			WATER RESOURCES WESTERN REGION		
Completed Depth: 569			(Measurable)		
Date: Started 11/12/01			Completed 11/17/01		

13. DRILLER'S CERTIFICATION

I/We certify that all minimum well construction standards were complied with at the time the rig was removed.

Firm Name SOS Welldrilling & Pump Co Firm No. 212

Firm Official Frank Skinner Date 12-5-01

Supervisor or Operator [Signature] Date 12-28-01
(Sign once if Firm Official & Operator)

Date: 12/5/01 Time: 12:12 PM

1. WELL OWNER

Name Neil HelnickAddress HC 34 Mayfield, Boise, ID 83706Drilling Permit No. 61-92-W-044

Water Right Permit No. _____

2. NATURE OF WORK

- ☒ New well ☐ Deepened ☐ Replacement
☐ Well diameter increase ☐ Modification
☐ Abandoned (describe abandonment or modification procedures such as liners, screen, materials, plug depths, etc. in lithologic log, section 9.)

3. PROPOSED USE

- ☒ Domestic ☐ Irrigation ☐ Monitor
☐ Industrial ☐ Stock ☐ Waste Disposal or Injection
☐ Other _____ (specify type)

4. METHOD DRILLED

- ☒ Rotary ☒ Air ☐ Auger ☐ Reverse rotary
☐ Cable ☐ Mud ☐ Other _____ (backhoe, hydraulic, etc.)

5. WELL CONSTRUCTION

Casing schedule: ☒ Steel ☐ Concrete ☒ Other PVC

Thickness	Diameter	From	To
<u>.250</u> inches	<u>6 5/8</u> inches	<u>3</u> feet	<u>404</u> feet
<u>Sch 40</u> inches	<u>4</u> inches	<u>240</u> feet	<u>500</u> feet
_____ inches	_____ inches	_____ feet	_____ feet

Was casing drive shoe used? ☒ Yes ☐ No
 Was a packer or seal used? ☐ Yes ☒ No
 Perforated? ☐ Yes ☒ No

How perforated? ☐ Factory ☐ Knife ☐ Torch ☐ Gun

Size of perforation? _____ inches by _____ inches

Number	From	To
_____ perforations	_____ feet	_____ feet
_____ perforations	_____ feet	_____ feet
_____ perforations	_____ feet	_____ feet

Well screen installed? ☒ Yes ☐ No
 Manufacturer Johnson Type PVC
 Top Packer or Headpipe 240
 Bottom of Tailpipe 510

Diameter 4" Slot size .010 Set from 410 feet to 440 feet
 Diameter 4" Slot size .020 Set from 440 feet to 510 feet

Gravel packed? ☐ Yes ☐ No ☐ Size of gravel _____
 Placed from _____ feet to _____ feet

Surface seal depth 38 Material used in seal: ☐ Cement grout
☒ Bentonite ☐ Pudding clay ☐ _____


Sealing procedure used: ☐ Slurry pit
☐ Temp. surface casing ☒ Overbore to seal depth

Method of joining casing: PVC ☒ Threaded ☒ Welded
☐ Solvent Weld ☐ Cemented between strata

Describe access port Top of 6"

6. LOCATION OF WELL

Sketch map location must agree with written location:



Subdivision Name _____

Lot No. _____ Block No. _____

County Blaine

MICROFILMED

DEC 03 1992

7. WATER LEVEL

Static water level 340 feet below land surface.Flowing? ☐ Yes ☒ No G.P.M. flow _____

Artesian closed-in pressure _____ p.s.i.

Controlled by: ☐ Valve ☐ Cap ☐ Plug

Temperature _____ °F. Quality _____
 Describe artesian or temperature zones below.

8. WELL TEST DATA

☐ Pump ☐ Bailor ☒ Air ☐ Other _____

Discharge G.P.M.	Pumping Level	Hours Pumped
20		5HR

9. LITHOLOGIC LOG

082452

Bore Diam.	Depth		Material	Water	
	From	To		Yes	No
8	0	2	Top Soil		
"	2	10	Brown Clay		
"	10	11	Coarse Sand		
8-6	11	40	Brown Clay		
8	40	105	Clay & Sand Seams		
"	105	120	Sand & 1/4 Gravel		
"	120	143	Cement and Sand		
"	143	162	Clay Tan		
"	162	190	Sand & Gravel		
"	190	200	Tan Clay		
"	200	260	Tan Sand & Gravel		
"	260	268	Tan Clay		
"	268	298	Tan Sand		
"	298	305	Clay		
"	305	336	Tan Sand		
"	336	375	Tan Clay		
"	375	420	Tan Coarse Sand	X	
"	420	510	Clay - Sand Seam	X	

RECEIVED

AUG 17 1992

Department of Water Resources
 Western Regional Office

Department of Water Resources

10.

Work started 7-29-92 finished 8-7-92

11. DRILLER'S CERTIFICATION

I/We certify that all minimum well construction standards were complied with at the time the rig was removed.

Firm Name Hickelston & Son, INC. Firm No. 35

Address Rt 3, Box 610-D Date 8-10-92

Use Typewriter
or
Ball Point Pen

**WATER RESOURCES
WESTERN REGION**

PAGE 1 OF 3 PAGES 95406

1. DRILLING PERMIT NO. 61-98-W-0075-000
Other IDWR No. D000 7483

10. WELL TESTS:

☒ Pump ☐ Baller ☐ Air ☐ Flowing Artesian

Yield gal/min.	Drawdown	Pumping Depth	Time
9.7	< 1 FT	500.8	12 HRS

Temperature of water 66°F Was a water analysis done? Yes ☐ No ☒
By whom? _____

Water Quality (odor, etc.) EXCELLENT

Bottom Hole Temperature 66°F

11. STATIC WATER LEVEL:

500 ft. below surface Depth artesian flow found _____
Artesian pressure _____ lb. Describe access port 8" CASING
BY REMOVING WELL CAP

12. LITHOLOGIC LOG: (Describe repairs or abandonment)

WATER

Bore Dia.	From	To	Remarks: Lithology, Water Quality & Temperature	DATE	BY
8	0	55			
6	55	63			
	0	2	SOIL		
	2	6	SOIL, SUBSOIL, CLAYEY HARDPAN		
	6	8	SANDY CLAY		
	8	16	CLAY		
	16	18	SAND		
	18	34.5	SANDY CLAY		
	34.5	35	ROCK		
	35	63	CLAYEY SAND		
	63	64	GRAVEL		
	64	69	CLAYEY SAND		
	69	70	GRAVEL		
	70	96	CLAYEY SAND		
	96	107	GRAVEL		
	107	116	CLAY		
	116	122	GRAVEL		
	122	194	BASALT		
	194	197	RUBBLE & CINDERS		
	197	216	BASALT		
	216	217	BASALT, CREVCKED, RED IN SEAMS		
	217	255	BASALT		
	255	257	BOULDERS, HARD, RED MATRIX		
	257	272	BASALT, RED IN SEAMS		
	272	273	RUBBLE & CINDERS		
	273	311	BASALT		
	311	312	RUBBLE & CINDERS		

RECEIVED JUN 14 1999

Department of Water Resources

Date: Started Nov 30, 1998 Completed SEE PAGE 3

Date: Started Nov 30, 1998 Completed SEE PAGE 3

13. DRILLER'S CERTIFICATION

I/We certify that all minimum well construction standards were complied with at the time the rig was removed.

Firm Name ARTESIAN CO Firm No. W18

Firm Official HUGH HARDEN Date 7 June 1999

Supervisor or Operator Hugh Gordon Date 7 June 1999
(Sign once if Firm Official & Operator)

(Sign once if Firm Official & Operator)

FORWARD WHITE COPY TO WATER RESOURCES

RECEIVED IDAHO DEPARTMENT OF WATER RESOURCES

RECEIVED Use Typewriter
or
Ball Point Pen

JUN 08 1999

WELL DRILLER'S REPORT

JUN 14 1999

PAGE 2 OF 3 PAGES

95107

Department of Water Resources

1. DRILLING PERMIT REGION

Other IDWR No. D 000 7483

2. OWNER:

Name FRANK [REDACTED] BONESSA

Address _____

City _____ State _____ Zip _____

3. LOCATION OF WELL by legal description:

Sketch map location must agree with written location.

OFFICE USE ONLY	
Registered by	T. _____
Page	63E Sec 13
Gov't Lot	County
SE 1/4 NE 1/4 NE 1/4	

Address of Well Site _____

(Give at least Direction + Distance to Road or Landmark)

Lot No. _____ Block No. _____ Subd. Name _____

4. PROPOSED USE:

- ☐ Domestic ☐ Municipal ☐ Monitor ☐ Irrigation
☐ Thermal ☐ Injection ☐ Other _____

5. TYPE OF WORK

- ☐ New Well ☐ Modify or Repair ☐ Replacement ☐ Abandonment

6. DRILL METHOD

- ☐ Mud Rotary ☐ Air Rotary ☐ Cable ☐ Other _____

7. SEALING PROCEDURES

SEAL/FILTER PACK			AMOUNT		METHOD
Material	From	To	Sacks or Pounds		

Was drive shoe seal tested? YES NO How? _____

8. CASING/LINER:

Diameter	From	To	Gauge	Casting	Liner	Steel	Plastic	Welded	Threaded
						☐	☐	☐	☐
						☐	☐	☐	☐
						☐	☐	☐	☐
						☐	☐	☐	☐

Final location of shoes 6" PVC COUPLING @ 551 FT

Top Packer or Headpipe _____ Bottom Tailpipe _____

9. PERFORATIONS/SCREENS

- ☐ Perforations Method _____
☐ Screens Type _____ Material _____

From	To	Slot Size	Number	Diameter	Tele/Pipe Size	Casting	Liner
						☐	☐
						☐	☐
						☐	☐
						☐	☐

MICROFILMED

AUG 25 1999

FORWARD WHITE COPY TO WATER RESOURCES

10. WELL TESTS:

- ☐ Pump ☐ Bailor ☐ Air ☐ Flowing Artesian

Yield gal/min.	Drawdown	Pumping Depth	Time

Temperature of water _____ Was a water analysis done? Yes ☐ No ☐

By whom? _____

Water Quality (odor, etc.) _____

Bottom Hole Temperature _____

11. STATIC WATER LEVEL:

_____ ft. below surface Depth artesian flow found _____

Artesian pressure _____ lb. Describe access port _____

Describe Controlling Devices: _____

12. LITHOLOGIC LOG: (Describe repairs or abandonment)

Bore Dia.	From	To	Remarks: Lithology, Water Quality & Temperature	Yield	Temp
	312	317	BASALT SOFTER, BROWN	✓	
	317	320	BASALT HARD, GREY	✓	
	320	327	BASALT SOFTER, BROWN	✓	
	327	330.5	BASALT MED. HARD, GREY	✓	
	330.5	334	RUBBLE & CINDERS, BROWN	✓	
	334	336	CLAY, BROWN	✓	
	336	342	BASALT, HARD, BROWN	✓	
	342	379	SANDSTONE, TAN	✓	
	379	383	CLAY, TAN	✓	
	383	401	SAND, TAN	✓	
	401	403	CLAY, TAN	✓	
	403	434	CLAYEY SAND, TAN	✓	
	434	435	CLAY, TAN	✓	
	435	438	SANDY CLAY, TAN	✓	
	438	451	CONGLOMERATE, TAN	✓	
	451	471	CLAYEY SAND, TAN	✓	
	471	472	CONGLOMERATE TAN	✓	
	472	479	CLAYEY SAND, TAN	✓	
	479	482	CLAY, TAN	✓	
	482	484	SAND, TAN	✓	
	484	487	CLAYEY SAND, TAN	✓	
	487	487.2	SAND TAN	✓	
	487.2	500	CLAYEY SAND TAN	✓	
	500	500.2	SAND TAN	✓	
	500.2	514	CLAYEY SAND & CLAY	✓	
	514	517	SAND TAN	✓	
	517	517	CLAYEY SAND TAN	✓	

Date: Started PAGE 1 Completed PAGE 3

13. DRILLER'S CERTIFICATION

I/We certify that all minimum well construction standards were complied with at the time the rig was removed.

Firm Name ARTESIAN CO Firm No. 318Firm Official Hugh Haddon Date 7 June 1999

Supervisor or Operator _____ Date _____

(Sign once if Firm Official & Operator)

RECEIVED

JUN 08 1999

IDAHO DEPARTMENT OF WATER RESOURCES

WELL DRILLER'S REPORT

Use Typewriter
or
Ball Point PenWATER RESOURCES
WESTERN REGION

61-98-W-0075-000

(PAGE 3) OF 3 PAGES 95108

1. DRILLING PERMIT NO.

Other IDWR No. D 0000 7423

2. OWNER:

Name FRANK BONESSAAddress 1979 BORCHERS DRIVECity SAN JOSE State CA Zip 95124

3. LOCATION OF WELL by legal description:

Sketch map location must agree with written location.

OFFICE USE ONLY

Twp. <u>21 S</u>		Rge. <u>03 E</u>		Sec. <u>13</u>	
N		E		S	
W		E		S	
SE 1/4		NE 1/4		SW 1/4	
10 acres		40 acres		160 acres	

County _____

Address of Well Site _____

(Give at least Direction + Distance to Road or Landmark)

Lot No. _____ Block No. _____ Subd. Name _____

4. PROPOSED USE:

- ☐ Domestic ☐ Municipal ☐ Monitor ☐ Irrigation
☐ Thermal ☐ Injection ☐ Other _____

5. TYPE OF WORK

- ☐ New Well ☐ Modify or Repair ☐ Replacement ☐ Abandonment

6. DRILL METHOD

- ☐ Mud Rotary ☐ Air Rotary ☐ Cable ☐ Other _____

7. SEALING PROCEDURES

SEAL/FILTER PACK			AMOUNT		METHOD
Material	From	To	Sacks or Pounds		

Was drive shoe seal tested? ☐ Yes ☐ No How? _____8. 4 1/2" OD LINER: HANGER 5" COUPLING CUT OFF

Diameter	From	To	Gauge	Casting	Liner	Steel	Plastic	Welded	Threaded

Final location of shoes - 4" LINER - NO SHOE

Top Packer or Headpipe _____ Bottom Tailpipe _____

9. PERFORATIONS/SCREENS PIPE AXIS, CHAMFERED

- ☐ Perforations ☐ Method INTERIALLY & GROUND
☐ Screens ☐ Type _____ Material _____

From	To	Slot Size	Number	Diameter	Tele/Pipe Size

Casting _____ Liner _____

MICROFILMED
AUG 25 1999

10. WELL TESTS:

- ☐ Pump ☐ Baller ☐ Air ☐ Flowing Artesian

Yield gal./min.	Drawdown	Pumping Depth	Time

Temperature of water _____ Was a water analysis done? Yes ☐ No ☐

By whom? _____

Water Quality (odor, etc.) _____

Bottom Hole Temperature _____

11. STATIC WATER LEVEL:

_____ ft. below surface Depth artesian flow found _____

Artesian pressure _____ lb. Describe access port _____

Describe Controlling Devices: _____

12. LITHOLOGIC LOG: (Describe repairs or abandonment)

Bore Dia.	From	To	Remarks: Lithology, Water Quality & Temperature	Y	N
	517	518	SAND TAN	✓	
	518	524	CLAYEY SAND, TAN		✓
	524	525	SAND, TAN	✓	
	525	526	CLAYEY SAND, TAN		✓
	526	527	SAND, TAN	✓	
	527	528	CLAYEY SAND, TAN		✓
	528	529	CLAYEY SAND, TAN		✓
	529	530	CLAYEY SAND, TAN		✓
	530	531	CLAYEY SAND, TAN		✓
	531	532	CLAYEY SAND, TAN		✓
	532	533	CLAYEY SAND, TAN		✓
	533	534	CLAYEY SAND, TAN		✓
	534	535	CLAYEY SAND, TAN		✓
	535	536	CLAYEY SAND, TAN		✓
	536	537	CLAYEY SAND, TAN		✓
	537	538	CLAYEY SAND, TAN		✓
	538	539	CLAYEY SAND, TAN		✓
	539	540	CLAYEY SAND, TAN		✓
	540	541	CLAYEY SAND, TAN		✓
	541	542	CLAYEY SAND, TAN		✓
	542	543	CLAYEY SAND, TAN		✓
	543	544	CLAYEY SAND, TAN		✓
	544	545	CLAYEY SAND, TAN		✓
	545	546	CLAYEY SAND, TAN		✓
	546	547	CLAYEY SAND, TAN		✓
	547	548	CLAYEY SAND, TAN		✓
	548	549	CLAYEY SAND, TAN		✓
	549	550	CLAYEY SAND, TAN		✓
	550	551	CLAYEY SAND, TAN		✓
	551	552	CLAYEY SAND, TAN		✓
	552	553	CLAYEY SAND, TAN		✓
	553	554	CLAYEY SAND, TAN		✓
	554	555	CLAYEY SAND, TAN		✓
	555	556	CLAYEY SAND, TAN		✓
	556	557	CLAYEY SAND, TAN		✓
	557	558	CLAYEY SAND, TAN		✓
	558	559	CLAYEY SAND, TAN		✓
	559	560	CLAYEY SAND, TAN		✓
	560	561	CLAYEY SAND, TAN		✓
	561	562	CLAYEY SAND, TAN		✓
	562	563	CLAYEY SAND, TAN		✓
	563	564	CLAYEY SAND, TAN		✓
	564	565	CLAYEY SAND, TAN		✓
	565	566	CLAYEY SAND, TAN		✓
	566	567	CLAYEY SAND, TAN		✓
	567	568	CLAYEY SAND, TAN		✓
	568	569	CLAYEY SAND, TAN		✓
	569	570	CLAYEY SAND, TAN		✓
	570	571	CLAYEY SAND, TAN		✓
	571	572	CLAYEY SAND, TAN		✓
	572	573	CLAYEY SAND, TAN		✓
	573	574	CLAYEY SAND, TAN		✓
	574	575	CLAYEY SAND, TAN		✓
	575	576	CLAYEY SAND, TAN		✓
	576	577	CLAYEY SAND, TAN		✓
	577	578	CLAYEY SAND, TAN		✓
	578	579	CLAYEY SAND, TAN		✓
	579	580	CLAYEY SAND, TAN		✓
	580	581	CLAYEY SAND, TAN		✓
	581	582	CLAYEY SAND, TAN		✓
	582	583	CLAYEY SAND, TAN		✓
	583	584	CLAYEY SAND, TAN		✓
	584	585	CLAYEY SAND, TAN		✓
	585	586	CLAYEY SAND, TAN		✓
	586	587	CLAYEY SAND, TAN		✓
	587	588	CLAYEY SAND, TAN		✓
	588	589	CLAYEY SAND, TAN		✓
	589	590	CLAYEY SAND, TAN		✓
	590	591	CLAYEY SAND, TAN		✓
	591	592	CLAYEY SAND, TAN		✓
	592	593	CLAYEY SAND, TAN		✓
	593	594	CLAYEY SAND, TAN		✓
	594	595	CLAYEY SAND, TAN		✓
	595	596	CLAYEY SAND, TAN		✓
	596	597	CLAYEY SAND, TAN		✓
	597	598	CLAYEY SAND, TAN		✓
	598	599	CLAYEY SAND, TAN		✓
	599	600	CLAYEY SAND, TAN		✓
	600	601	CLAYEY SAND, TAN		✓
	601	602	CLAYEY SAND, TAN		✓
	602	603	CLAYEY SAND, TAN		✓
	603	604	CLAYEY SAND, TAN		✓
	604	605	CLAYEY SAND, TAN		✓
	605	606	CLAYEY SAND, TAN		✓
	606	607	CLAYEY SAND, TAN		✓
	607	608	CLAYEY SAND, TAN		✓
	608	609	CLAYEY SAND, TAN		✓
	609	610	CLAYEY SAND, TAN		✓
	610	611	CLAYEY SAND, TAN		✓
	611	612	CLAYEY SAND, TAN		✓
	612	613	CLAYEY SAND, TAN		✓
	613	614	CLAYEY SAND, TAN		✓
	614	615	CLAYEY SAND, TAN		✓
	615	616	CLAYEY SAND, TAN		✓
	616	617	CLAYEY SAND, TAN		✓
	617	618	CLAYEY SAND, TAN		✓
	618	619	CLAYEY SAND, TAN		✓
	619	620	CLAYEY SAND, TAN		✓
	620	621	CLAYEY SAND, TAN		✓
	621	622	CLAYEY SAND, TAN		✓
	622	623	CLAYEY SAND, TAN		✓
	623	624	CLAYEY SAND, TAN		✓
	624	625	CLAYEY SAND, TAN		✓
	625	626	CLAYEY SAND, TAN		✓
	626	627	CLAYEY SAND, TAN		✓
	627	628	CLAYEY SAND, TAN		✓
	628	629	CLAYEY SAND, TAN		✓
	629	630	CLAYEY SAND, TAN		✓
	630	631	CLAYEY SAND, TAN		✓
	631	632	CLAYEY SAND, TAN		✓
	632	633	CLAYEY SAND, TAN		✓
	633	634	CLAYEY SAND, TAN		✓
	634	635	CLAYEY SAND, TAN		✓
	635	636	CLAYEY SAND, TAN		✓
	636	637	CLAYEY SAND, TAN		✓
	637	638	CLAYEY SAND, TAN		✓
	638	639	CLAYEY SAND, TAN		✓
	639	640	CLAYEY SAND, TAN		✓
	640	641	CLAYEY SAND, TAN		✓
	641	642	CLAYEY SAND, TAN		✓
	642	643	CLAYEY SAND, TAN		✓
	643	644	CLAYEY SAND, TAN		✓
	644	645	CLAYEY SAND, TAN		✓
	645	646	CLAYEY SAND, TAN		✓
	646	647	CLAYEY SAND, TAN		✓
	647	648	CLAYEY SAND, TAN		✓
	648	649	CLAYEY SAND, TAN		✓
	649	650	CLAYEY SAND, TAN		✓
	650	651	CLAYEY SAND, TAN		✓
	651	652	CLAYEY SAND, TAN		✓
	652	653	CLAYEY SAND, TAN		✓
	653	654	CLAYEY SAND, TAN		✓
	654	655	CLAYEY SAND, TAN		✓
	655	656	CLAYEY SAND, TAN		✓
	656	657	CLAYEY SAND, TAN		✓
	657	658	CLAYEY SAND, TAN		✓
	658	659	CLAYEY SAND, TAN		✓
	659	660	CLAYEY SAND, TAN		✓
	660	661	CLAYEY SAND, TAN		✓
	661	662	CLAYEY SAND, TAN		✓
	662	663	CLAYEY SAND, TAN		✓
	663	664	CLAYEY SAND, TAN		✓
	664	665	CLAYEY SAND, TAN		✓
	665	666	CLAYEY SAND, TAN		✓
	666	667	CLAYEY SAND, TAN		✓
	667	668	CLAYEY SAND, TAN		✓
	668	669	CLAYEY SAND, TAN		✓
	669	670	CLAYEY SAND, TAN		✓
	670	671	CLAYEY SAND, TAN		✓
	671	672	CLAYEY SAND, TAN		✓
	672	673	CLAYEY SAND, TAN		✓
	673	674	CLAYEY SAND, TAN		✓
	674	675	CLAYEY SAND, TAN		✓
	675	676	CLAYEY SAND, TAN		✓
	676	677	CLAYEY SAND, TAN		✓
	677	678	CLAYEY SAND, TAN		✓
	678	679	CLAYEY SAND, TAN		✓
	679	680	CLAYEY SAND, TAN		✓
	680	681	CLAYEY SAND, TAN		✓
	681	682	CLAYEY SAND, TAN		✓
	682	683	CLAYEY SAND, TAN		✓
	683	684	CLAYEY SAND, TAN		✓
	684	685	CLAYEY SAND, TAN		✓
	685	686	CLAYEY SAND, TAN		✓
	686	687	CLAYEY SAND, TAN		✓
	687	688	CLAYEY SAND, TAN		✓
	688	689	CLAYEY SAND, TAN		✓
	689	690	CLAYEY SAND, TAN		✓
	690	691	CLAYEY SAND, TAN		✓
	691	692	CLAYEY SAND, TAN		✓
	692	693	CLAYEY SAND, TAN		✓
	693	694	CLAYEY SAND, TAN		✓
	694	695	CLAYEY SAND, TAN		✓
	695	696	CLAYEY SAND, TAN		✓
	696	697	CLAYEY SAND, TAN		✓
	697	698	CLAYEY SAND, TAN		✓
	698	699	CLAYEY SAND, TAN		✓
	699	700	CLAYEY SAND, TAN		✓

RECEIVED

JUN 14 1999

870655-775948
IDAHO DEPARTMENT OF WATER RESOURCES
WELL DRILLER'S REPORT

Office Use Only			
Inspected by			
Twp	Rge	Sec	
1/4	1/4	1/4	
Lat:		Long:	

1. DRILLING PERMIT NO. - - - -
Other IDWR No. D0019537
2. OWNER:
Name Bob Wickham
Address 730 S. Prairie Grass Dr.
City Boise State ID Zip 83716
3. LOCATION OF WELL by legal description:
Sketch map location must agree with written location

W	X	E	Twp. <u>1</u> North ☐ or South ☒
			Rgc. <u>4</u> East ☒ or West ☐
			Sec. <u>1</u> 1/4 SW 1/4 NW 1/4
			10 acres 40 acres 160 acres

Gov't lot _____ County Elmore
Lat: : : Long: : :
Address of Well Site 730 S. Prairie Dr.

City Mtn Home

(Give at least name of road + Distance in Road or Landmark)

Lt. _____ Blk. _____ Sub. Name _____

4. USE:

☒ Domestic ☐ Municipal ☐ Monitor ☐ Irrigation
☐ Thermal ☐ Injection ☐ Other

5. TYPE OF WORK check all that apply (Replacement etc.)

X New Well ☐ Modify ☐ Abandonment ☐ Other

6. DRILL METHOD

X Air Rotary ☐ Cable ☐ Mud Rotary ☐ Other

7. SEALING PROCEDURES

SEAL/FILTER PACK		AMOUNT		METHOD
Material	From	To	Sacks or Pounds	
Bentonite	0	20	700 lbs.	Overbore

Was drive shoe used? X Y ☐ N Shoe Depth(s) _____

Was drive shoe seal tested? ☐ Y X N How? _____

8. CASING/LINER:

Diameter	From	To	Gauge	Material	Casing	Liner	Welded	Threaded
6.625	+1	444	.250	Steel	X	☐	X	☐
					☐	☐	☐	☐
					☐	☐	☐	☐

Length of Headpipe 6' Length of Tailpipe 3'

9. PERFORATIONS/SCREENS

☐ Perforations Method _____

X Screens Screen Type Johnson

From	To	Slot Size	Number	Diameter	Material	Casing	Liner
445	450	.030		5"	SS	☐	☐
						☐	☐
						☐	☐

10. STATIC WATER LEVEL OR ARTESIAN PRESSURE:

337 ft. below ground

Depth flow encountered _____ ft.

devices: _____

Artesian Pressure _____ lb

Describe access port or control

11. WELL TESTS:

☐ Pump ☐ Bailor ☒ Air ☐ Flowing Artesian

Yield gal/min.	Drawdown	Pumping Level	Time
20			1 hr

Water Temp. 68 Bottom hole temp. _____

Water Quality test or comments: _____

Depth first Water Encountered 415'

12. LITHOLOGIC LOG: (Describe repair or abandonment)

Water

Bore Dia.	From	To	Remarks: Lithology, Water Quality & Temp.	Y	N
10"	0	2	Top Soil		X
10"	2	7	Cleache		X
10"	7	18	Sand & Gravel		X
6"	18	30	Sand & Gravel		X
6"	30	34	Brown Clay		X
6"	34	225	Sand & Gravel w/ Clay Seams		X
6"	225	236	Brown Clay		X
6"	236	250	Tan Sand Stone		X
6"	260	415	Sand & Gravel w/ Clay Seams		X
6"	415	428	Coarse Sand	X	
6"	428	441	Brown Clay		X
6"	441	455	Coarse Sand	X	
6"	455	460	Brown Clay		X

RECEIVED

APR 26 2002

WATER RESOURCES
WESTERN REGION

Completed Depth: 455'

(Measurable)

Date: Started 1-04-02

Completed 1-11-02

13. DRILLER'S CERTIFICATION

I/We certify that all minimum well construction standards were complied with at the time the rig was removed.

Firm Name Hiddleston & Son, Inc.

Firm No. 35

Firm Official Kenneth Hiddleston

Date 04-22-02

Supervisor or Operator Mark Hiddleston

Date 4-17-02
(Sign once if Firm Official & Operator)

IDAHO DEPARTMENT OF WATER RESOURCES WELL DRILLER'S REPORT

1. WELL TAG NO. D 0060330
Drilling Permit No. 913940-862568

Water right or injection well # _____
2. OWNER: Lord Ranch LLP
Name Jeff Lord
Address 1171 Mayfield Road
City Boise State ID. Zip 83716

3. WELL LOCATION:
Twp. 1 North ☒ or South ☐ Rge. 5 East ☒ or West ☐
Sec. 30 1/4 SW 1/4 SE 1/4

Gov't Lot _____ County Elmore
Lat. 43 23.35 (Deg. and Decimal minutes)
Long. -115 54.15 (Deg. and Decimal minutes)
Address of Well Site 1.6 miles NE. off Base Line Road
City Mayfield

(Give at least name of road + distance to road or landmark)
Lot _____ Blk. _____ Sub. Name _____

4. USE:
☒ Domestic ☐ Municipal ☐ Monitor ☐ Irrigation ☐ Thermal ☐ Injection
☐ Other _____

5. TYPE OF WORK:
☒ New well ☐ Replacement well ☐ Modify existing well
☐ Abandonment ☐ Other _____

6. DRILL METHOD:
☒ Air Rotary ☐ Mud Rotary ☐ Cable ☐ Other _____

Seal material	From (ft)	To (ft)	Quantity (lbs or ft')	Placement method/procedure
Bentonite #5	0	40'	1350 lbs	Overbore Pour

Diameter (nominal)	From (ft)	To (ft)	Gauge/Schedule	Material	Casing	Liner	Threaded	Welded
6 5/8"	+2'	298'	.250	Steel	☒	☐	☐	☒

Was drive shoe used? ☒ Y ☐ N Shoe Depth(s) 298 feet

9. PERFORATIONS/SCREENS:
Perforations ☐ Y ☒ N Method _____
Manufactured screen ☐ Y ☒ N Type _____
Method of Installation _____

From (ft)	To (ft)	Slot size	Number/ft	Diameter (nominal)	Material	Gauge or Schedule
-----------	---------	-----------	-----------	--------------------	----------	-------------------

Length of Headpipe _____ Length of Tailpipe _____
Packer ☐ Y ☒ N Type _____

Filter Material	From (ft)	To (ft)	Quantity (lbs or ft')	Placement method
-----------------	-----------	---------	-----------------------	------------------

11. FLOWING ARTESIAN:
Flowing Artesian? ☐ Y ☒ N Artesian Pressure (PSIG) _____
Describe control device _____

12. STATIC WATER LEVEL and WELL TESTS:

Depth first water encountered (ft) 300 Static water level (ft) 243
Water temp. (°F) 58 Bottom hole temp. (°F) _____
Describe access port Through top of well seal

Well test:	Test method:
Drawdown (feet)	Pump ☐ Baller ☐ Air ☒ Flowing artesian ☐
Discharge or yield (gpm)	
Test duration (minutes)	

Water quality test or comments: _____

13. LITHOLOGIC LOG and/or repairs or abandonment:

Bore Dia. (in)	From (ft)	To (ft)	Remarks, lithology or description of repairs or abandonment, water temp.	Water	
				Y	N
10"	0	2'	Topsoil		X
10"	2'	5'	Caleche		X
10"	5'	35'	Sand and gravel		X
10"	35'	40'	Brown clay		X
6"	40'	43'	Brown clay		X
6"	43'	136'	Sand and gravel tan		X
6"	136'	138'	Tan clay		X
6"	138'	296'	Sand and gravel		X
6"	296'	299'	Brown clay		X
6"	299'	307'	Tan sand with pea gravel	X	

RECEIVED

JAN 26 2012

WATER RESOURCES
WEST TERN REGION

Completed Depth (Measurable): 303 Feet
Date Started: 11/17/2011 Date Completed: Dec 30, 2011

14. DRILLER'S CERTIFICATION:

I/We certify that all minimum well construction standards were complied with at the time the rig was removed.

Company Name Hiddleston Drilling Co. No. 35
*Principal Driller [Signature] Date 1/11/12
*Driller [Signature] Date 1/16/12
*Operator [Signature] Date 1/16/12
Operator I / Date _____

* Signature of Principal Driller and rig operator are required.