

PART 1

6. General Information:

- a. Description of diversion system Pump and pipeline from Hiawatha Canal will deliver water to infiltration system for recharge.
- b. Are the lands from which you propose to transfer the water right subject to any liens, deeds of trust, mortgages, or contracts?
☐ Yes ☒ No. If yes, provide a notarized statement from the holder of the lien, deed of trust, mortgage or contract agreeing to the proposed changes.
- c. Describe the effect on the land now irrigated if the place of use is changed pursuant to this transfer:
Sixty acres at the present place of use will no longer be irrigated.
- d. Remarks:
See attached narrative describing transfer and accompanying permit.

ACTION OF THE DIRECTOR, DEPARTMENT OF WATER RESOURCES

This is to certify that I have examined Application for Transfer of Water Rights No. _____

And said application is hereby _____, subject to the following limitations and conditions:

Witness my hand this _____ day of _____, 20_____.

Page _____ of _____

STATE OF IDAHO
DEPARTMENT OF WATER RESOURCESRECEIVED
MAY 06 2008
APPLICATION FOR TRANSFER OF WATER RIGHT
PART 1DEPT. OF WATER RESOURCES
SOUTHERN REGION

Dry Lot LLC

Phone 208-578-2116

Post Office address 116 Valley Club Dr. Hailey, ID 83333

A. PURPOSE OF TRANSFER

1. ☐ Change point of diversion ☐ Add diversion point ☒ Change place of use
☒ Change nature of use ☐ Change period of use ☐ Other _____
2. Describe the reason for the proposed changes Provide mitigation for additional ground water irrigation for the Valley Club Subdivision.

B. DESCRIPTION OF RIGHT(S) OR PORTION THEREOF, AFTER THE REQUESTED CHANGE

1. Right Number Priority Amount (cfs/ac-ft) Nature of Use Period of Use
- | | | | | |
|--------------|-----------|-------|----------------|----------------|
| 37-21130 | 3/24/1883 | 0.37/ | Recharge | 04/15 to 10/31 |
| 37-21137 | 3/24/1883 | 2.91/ | Recharge | 04/15 to 10/31 |
| 37-21139 | 3/24/1883 | 0.36/ | Recharge | 04/15 to 10/31 |
| All 3 rights | 3/24/1883 | 2.0 | Rec/aesthetics | 04/15 to 10/31 |
2. Total amount of water being transferred 3.64 cubic feet per second and/or _____ acre-feet per annum.
3. Source of water Big Wood River tributary to Malad River
4. Point(s) of Diversion:

Lot	1/4	1/4	1/4	Sec.	Twp.	Rge	County	Local name for diversion
		SW	NW	20	03N	18E	BLAINE	HIAWATHA CANAL

5. Lands irrigated or place of use: *R_e = Recharge R/J = Recreation and aesthetics

Twp.	Rge.	Sec.	NE 1/4				NW 1/4				SW 1/4				SE 1/4				Totals
			NE 1/4	NW 1/4	SW 1/4	SE 1/4	NE 1/4	NW 1/4	SW 1/4	SE 1/4	NE 1/4	NW 1/4	SW 1/4	SE 1/4	NE 1/4	NW 1/4	SW 1/4	SE 1/4	
03N	18E	20		R _e	R/J					R/J					R/J	R _e R/J		R/J	
03N	18E	21											R/J						
03N	18E	28						R/J	R/J			R/J							
03N	18E	29	R/J			R/J									R/J				

Page _____ of _____

Transfer No. _____

STATE OF IDAHO
DEPARTMENT OF WATER RESOURCES
APPLICATION FOR TRANSFER OF WATER RIGHT
PART 2

(Attach one copy for each right)

A. DESCRIPTION OF RIGHT AS RECORDED

1. Right evidenced by:

- a. Decree No. _____ Decreed to _____
 in case of _____ vs. _____
 dated _____ in _____ county of _____
- b. License No. _____ issued by the Idaho Department of Water Resources.
- c. Claim No. 37-21130 on file with the Idaho Department of Water Resources.
- d. Transfer No. _____ which produced this right.

2. Attach a copy of last year's tax notice for the property to which the water right is appurtenant or other documents which show ownership. Label document as attachment A. check appropriate box below.

☐ Tax notice☒ Warranty Deed☐ Other _____3. Source of water Big Wood River tributary to Malad River4. Date of priority 3/24/1883

5. Water is used for the following purpose:

Amount 0.41 for Irrigation purposes from 04/15 to 10/31
 (cfs/ac-ft)
 Amount _____ for _____ purposes from _____ to _____
 (cfs/ac-ft)
 Amount _____ for _____ purposes from _____ to _____
 (cfs/ac-ft)

6. Total amount of water under right 0.41 cubic feet per second and/or _____ acre-feet per annum.

7. Point(s) of Diversion:

Lot	1/4	1/4	1/4	Sec.	Twp.	Rge	County	Local name for diversion
		SW	NW	20	03N	18E	BLAINE	HIAWATHA CANAL

8. Lands irrigated or place of use:

Twp.	Rge.	Sec.	NE 1/4				NW 1/4				SW 1/4				SE 1/4				Totals
			NE 1/4	NW 1/4	SW 1/4	SE 1/4	NE 1/4	NW 1/4	SW 1/4	SE 1/4	NE 1/4	NW 1/4	SW 1/4	SE 1/4	NE 1/4	NW 1/4	SW 1/4	SE 1/4	
02N	18E	3											20						20
02N	18E	4													21	3		22	46

Total acres 669. Describe any other water rights used for the same purpose as described above 37-21137, 37-21139

Page _____ of _____

PART 2

Transfer No. _____

10. To your knowledge, has any portion of this water right undergone a period of five or more consecutive years of non-use?

No _____ If yes, describe _____

B. DESCRIPTION OF PORTION OF RIGHT BEING TRANSFERRED

(if the entire right is to be changed by the applicant, omit part B and C)

1. Amount 0.37 for Irrigation purposes from 04/15 to 10/31
 (cfs/ac-ft)
 Amount _____ for _____ purposes from _____ to _____
 (cfs/ac-ft)
 Amount _____ for _____ purposes from _____ to _____
 (cfs/ac-ft)

2. Point(s) of Diversion:

Lot	1/4	1/4	1/4	Sec.	Twp.	Rge	County	Local name for diversion
		SW	NW	20	03N	18E	BLAINE	HIAWATHA CANAL

3. Lands irrigated or place of use:

Twp.	Rge.	Sec.	NE 1/4				NW 1/4				SW 1/4				SE 1/4				Totals
			NE 1/4	NW 1/4	SW 1/4	SE 1/4	NE 1/4	NW 1/4	SW 1/4	SE 1/4	NE 1/4	NW 1/4	SW 1/4	SE 1/4	NE 1/4	NW 1/4	SW 1/4	SE 1/4	
02N	18E	3											20						20
02N	18E	4													21	3		22	46

* 60 acres of the authorized 66 acres will be transferred.

Total acres 66***C. DESCRIPTION OF UNCHANGED PORTION OF RIGHT** (omit if there is no change)

1. Amount 0.04 for Irrigation purposes from 04/15 to 10/31
 (cfs/ac-ft)
 Amount _____ for _____ purposes from _____ to _____
 (cfs/ac-ft)
 Amount _____ for _____ purposes from _____ to _____
 (cfs/ac-ft)

2. Point(s) of Diversion:

Lot	1/4	1/4	1/4	Sec.	Twp.	Rge	County	Local name for diversion
		SW	NW	20	03N	18E	BLAINE	HIAWATHA CANAL

3. Lands irrigated or place of use:

Twp.	Rge.	Sec.	NE 1/4				NW 1/4				SW 1/4				SE 1/4				Totals
			NE 1/4	NW 1/4	SW 1/4	SE 1/4	NE 1/4	NW 1/4	SW 1/4	SE 1/4	NE 1/4	NW 1/4	SW 1/4	SE 1/4	NE 1/4	NW 1/4	SW 1/4	SE 1/4	
02N	18E	3											20						20
02N	18E	4													21	3		22	46

* Irrigation within 66 acre PPU will be reduced to 6 acres.

Total acres 66*

STATE OF IDAHO
DEPARTMENT OF WATER RESOURCES
APPLICATION FOR TRANSFER OF WATER RIGHT
PART 2

(Attach one copy for each right)

A. DESCRIPTION OF RIGHT AS RECORDED

1. Right evidenced by:

- a. Decree No. _____ Decreed to _____
in case of _____ vs. _____
dated _____ in _____ county of _____
- b. License No. _____ issued by the Idaho Department of Water Resources.
- c. Claim No. 37-21137 on file with the Idaho Department of Water Resources.
- d. Transfer No. _____ which produced this right.

2. Attach a copy of last year's tax notice for the property to which the water right is appurtenant or other documents which show ownership. Label document as attachment A. check appropriate box below.

☐ Tax notice ☒ Warranty Deed ☐ Other _____

3. Source of water Big Wood River tributary to Malad River

4. Date of priority 3/24/1883

5. Water is used for the following purpose:

Amount 3.2 for Irrigation purposes from 04/15 to 10/31
(cfs/ac-ft)
Amount _____ for _____ purposes from _____ to _____
(cfs/ac-ft)
Amount _____ for _____ purposes from _____ to _____
(cfs/ac-ft)

6. Total amount of water under right 3.2 cubic feet per second and/or _____ acre-feet per annum.

7. Point(s) of Diversion:

Lot	1/4	1/4	1/4	Sec.	Twp.	Rge	County	Local name for diversion
		SW	NW	20	03N	18E	BLAINE	HIAWATHA CANAL

8. Lands irrigated or place of use:

Twp.	Rge.	Sec.	NE 1/4				NW 1/4				SW 1/4				SE 1/4				Totals
			NE 1/4	NW 1/4	SW 1/4	SE 1/4	NE 1/4	NW 1/4	SW 1/4	SE 1/4	NE 1/4	NW 1/4	SW 1/4	SE 1/4	NE 1/4	NW 1/4	SW 1/4	SE 1/4	
02N	18E	3											20						20
02N	18E	4													21	3		22	46

Total acres 66

9. Describe any other water rights used for the same purpose as described above 37-21130, 37-21139

Page _____ of _____

PART 2

Transfer No. _____

10. To your knowledge, has any portion of this water right undergone a period of five or more consecutive years of non-use?

No _____ If yes, describe _____

B. DESCRIPTION OF PORTION OF RIGHT BEING TRANSFERRED*(if the entire right is to be changed by the applicant, omit part B and C)*

1. Amount 2.91 for Irrigation purposes from 04/15 to 10/31
 (cfs/ac-ft)
 Amount _____ for _____ purposes from _____ to _____
 (cfs/ac-ft)
 Amount _____ for _____ purposes from _____ to _____
 (cfs/ac-ft)

2. Point(s) of Diversion:

Lot	1/4	1/4	1/4	Sec.	Twp.	Rge	County	Local name for diversion
		SW	NW	20	03N	18E	BLAINE	HIAWATHA CANAL

3. Lands irrigated or place of use:

Twp.	Rge.	Sec.	NE 1/4				NW 1/4				SW 1/4				SE 1/4				Totals
			NE 1/4	NW 1/4	SW 1/4	SE 1/4	NE 1/4	NW 1/4	SW 1/4	SE 1/4	NE 1/4	NW 1/4	SW 1/4	SE 1/4	NE 1/4	NW 1/4	SW 1/4	SE 1/4	
02N	18E	3											20						20
02N	18E	4													21	3		22	46

* 60 acres of the authorized 66 acres will be transferred.

Total acres 66***C. DESCRIPTION OF UNCHANGED PORTION OF RIGHT** *(omit if there is no change)*

1. Amount 0.29 for Irrigation purposes from 04/15 to 10/31
 (cfs/ac-ft)
 Amount _____ for _____ purposes from _____ to _____
 (cfs/ac-ft)
 Amount _____ for _____ purposes from _____ to _____
 (cfs/ac-ft)

2. Point(s) of Diversion:

Lot	1/4	1/4	1/4	Sec.	Twp.	Rge	County	Local name for diversion
		SW	NW	20	03N	18E	BLAINE	HIAWATHA CANAL

3. Lands irrigated or place of use:

Twp.	Rge.	Sec.	NE 1/4				NW 1/4				SW 1/4				SE 1/4				Totals
			NE 1/4	NW 1/4	SW 1/4	SE 1/4	NE 1/4	NW 1/4	SW 1/4	SE 1/4	NE 1/4	NW 1/4	SW 1/4	SE 1/4	NE 1/4	NW 1/4	SW 1/4	SE 1/4	
02N	18E	3											20						20
02N	18E	4													21	3		22	46

* Irrigation within 66 acre PPU will be reduced to 6 acres.

Total acres 66*

STATE OF IDAHO
DEPARTMENT OF WATER RESOURCES
APPLICATION FOR TRANSFER OF WATER RIGHT
PART 2

(Attach one copy for each right)

A. DESCRIPTION OF RIGHT AS RECORDED

1. Right evidenced by:

- a. Decree No. _____ Decreed to _____
in case of _____ vs. _____
dated _____ in _____ county of _____
- b. License No. _____ issued by the Idaho Department of Water Resources.
- c. Claim No. 37-21139 on file with the Idaho Department of Water Resources.
- d. Transfer No. _____ which produced this right.

2. Attach a copy of last year's tax notice for the property to which the water right is appurtenant or other documents which show ownership. Label document as attachment A. check appropriate box below.

☐ Tax notice☒ Warranty Deed☐ Other _____3. Source of water Big Wood River tributary to Malad River4. Date of priority 3/24/1883

5. Water is used for the following purpose:

Amount 0.39 for Irrigation purposes from 04/15 to 10/31
(cfs/ac-ft)
Amount _____ for _____ purposes from _____ to _____
(cfs/ac-ft)
Amount _____ for _____ purposes from _____ to _____
(cfs/ac-ft)

6. Total amount of water under right 0.39 cubic feet per second and/or _____ acre-feet per annum.

7. Point(s) of Diversion:

Lot	1/4	1/4	1/4	Sec.	Twp.	Rge	County	Local name for diversion
		SW	NW	20	03N	18E	BLAINE	HIAWATHA CANAL

8. Lands irrigated or place of use:

Twp.	Rge.	Sec.	NE 1/4				NW 1/4				SW 1/4				SE 1/4				Totals
			NE 1/4	NW 1/4	SW 1/4	SE 1/4	NE 1/4	NW 1/4	SW 1/4	SE 1/4	NE 1/4	NW 1/4	SW 1/4	SE 1/4	NE 1/4	NW 1/4	SW 1/4	SE 1/4	
02N	18E	3											20						20
02N	18E	4													21	3		22	46

Total acres 669. Describe any other water rights used for the same purpose as described above 37-21130, 37-21137

10. To your knowledge, has any portion of this water right undergone a period of five or more consecutive years of non-use?

No _____ If yes, describe _____

B. DESCRIPTION OF PORTION OF RIGHT BEING TRANSFERRED

(if the entire right is to be changed by the applicant, omit part B and C)

1. Amount 0.36 for Irrigation purposes from 04/15 to 10/31
 (cfs/ac-ft)
 Amount _____ for _____ purposes from _____ to _____
 (cfs/ac-ft)
 Amount _____ for _____ purposes from _____ to _____
 (cfs/ac-ft)

2. Point(s) of Diversion:

Lot	1/4	1/4	1/4	Sec.	Twp.	Rge	County	Local name for diversion
		SW	NW	20	03N	18E	BLAINE	HIAWATHA CANAL

3. Lands irrigated or place of use:

Twp.	Rge.	Sec.	NE 1/4				NW 1/4				SW 1/4				SE 1/4				Totals
			NE 1/4	NW 1/4	SW 1/4	SE 1/4	NE 1/4	NW 1/4	SW 1/4	SE 1/4	NE 1/4	NW 1/4	SW 1/4	SE 1/4	NE 1/4	NW 1/4	SW 1/4	SE 1/4	
02N	18E	3											20						20
02N	18E	4													21	3		22	46

* 60 acres of the authorized 66 acres will be transferred.

Total acres 66*

C. DESCRIPTION OF UNCHANGED PORTION OF RIGHT (omit if there is no change)

1. Amount 0.03 for Irrigation purposes from 04/15 to 10/31
 (cfs/ac-ft)
 Amount _____ for _____ purposes from _____ to _____
 (cfs/ac-ft)
 Amount _____ for _____ purposes from _____ to _____
 (cfs/ac-ft)

2. Point(s) of Diversion:

Lot	1/4	1/4	1/4	Sec.	Twp.	Rge	County	Local name for diversion
		SW	NW	20	03N	18E	BLAINE	HIAWATHA CANAL

3. Lands irrigated or place of use:

Twp.	Rge.	Sec.	NE 1/4				NW 1/4				SW 1/4				SE 1/4				Totals
			NE 1/4	NW 1/4	SW 1/4	SE 1/4	NE 1/4	NW 1/4	SW 1/4	SE 1/4	NE 1/4	NW 1/4	SW 1/4	SE 1/4	NE 1/4	NW 1/4	SW 1/4	SE 1/4	
02N	18E	3											20						20
02N	18E	4													21	3		22	46

* Irrigation within 66 acre PPU will be reduced to 6 acres.

Total acres 66*



0 200 400 800 Feet

BROCKWAY ENGINEERING, PLLC
ALR (ZL) - 3/21/08

F:\Projects\Valley Club H.O.A\ARCV IEW 9\Cutter Split Map.mxd

VALLEY CLUB PROPERTY OWNERS ASSOCIATION **CUTTERS AREA TO BE DRIED UP** **WATER RIGHTS 37-21130, 37-21137, 37-21139** **2006 NAIP AERIAL**

Legend

- IDWR REC. POU 37-21130, 21137, 21139
- Cutter Split**
- Acres_to**
- Cutters Retain 6 ac.
- Valley Club HOA 60 ac. or Dry Up Area
- Ponds
- Lot_Lines
- Street_Centerlines
- Water
- t02n18e



**VALLEY CLUB HOME OWNERS ASSOCIATION-
PROPOSED PLACE OF USE
T.03N R.18E. BLAINE COUNTY, ID
2006 AERIAL PHOTOGRAPHS**

1 inch = 700 FT
0 350 700 1,400 Feet
BROCKWAY ENGINEERING, PLLC.
ZL - 3/21/08

Legend
Valley Club H.O.A. PPU QQ = 221.7
Section_Lines
t03n18e




PART 3**B. CHANGES IN NATURE OF USE**

1.

<u>New Nature of Use</u>	<u>Amount</u> (cfs/ac-ft)	<u>Hours/days/year</u>	<u>Period of Use</u>
Recharge	3.63/		04/15 to 10/31
			to
2. Quantity and quality of return flows and location of discharge:
N/A.
3. Describe the effects on other water uses resulting from the proposed change:
None.

I hereby assert that no one will be injured by such change and that the change does not constitute an enlargement in use of the original right. The information contained in this application is true to the best of my knowledge.

I understand that any willful misrepresentations made in this application may result in voiding its approval.



Subscribed and sworn to before me this

6

day of

(Signature of Applicant)

MAY

, 20 08.

(Notary Public)

My commission expires

9-28-10

FOR DEPARTMENT USE ONLY

Transfer contains _____ pages and _____ attachments

Received by _____ Date _____ Protest filed by _____

Prelim. check by _____ Fee _____

Receipted by _____ Date _____

Published in _____ Copies of protest forwarded by _____

Pub. dates _____ Hearing held by _____ Date _____

Watermaster recommendation requested on _____ Recommended for ☐ Approval ☐ Denial

_____ rec'd. _____ by _____

Copy of transfer sent to lien holder _____

Project No. 938-01-2006

Narrative in Support of Water Right Transfer and Mitigation Plan for Irrigation

Prepared for:

Valley Club Home Owners Association, Inc.
Hailey, ID

March 21, 2008

For information concerning this report, contact
Charles E. Brockway, Ph.D., P.E.



CHARLES E. BROCKWAY, PH.D., P.E.
CHARLES G. BROCKWAY, PH.D., P.E.

2016 NORTH WASHINGTON, SUITE 4
TWIN FALLS, IDAHO 83301

Narrative in Support of Water Right Permit Transfer and Mitigation Plan for Irrigation

Valley Club Home Owners Association Inc.
Hailey, Idaho

Charles E. Brockway, P.E.
Brockway Engineering, PLLC.

Revised
March 21, 2007

The Valley Club Home Owners Association represents owners of the 99 lots in the Valley Club Subdivision in Blaine County Idaho. The subdivision was established in early 1990's and currently has residences on 40 lots (Figure 1). The Association holds two ground water right permits 37-8613A and 37- 8810 which provide in-house, irrigation, and fire protection water to all lots. The permit components are shown on Table 1.

Table 1 Water Right Permits-The Valley Club Home Owners Association Inc.

Right No.	Priority Date	Proof Date	Use	Diversion Rate cfs	Irrig Acres	Diversion
37-8613A	4/4/1990	5/2/1996	Irrigation & Domestic	0.98 Irrig. 0.50 Domestic	49.5 acres-limit 0.5acres/residence	2 wells
37-8810	5/3/1993	8/18/1998	Domestic & Fire Protection	0.4 Domestic 3.4 Fire Protection	Domestic is for 99 units, clubhouse/restaurant and recreation center	2 wells

The two wells are located at the north end of the subdivision in the SWNWNW Sec 28 T3N R18E and pump into a looped distribution system (Figure 1). Drillers' logs for both wells are shown in Appendix A. Combined capacities of the two wells are adequate to provide the additional irrigation requirements contemplated under this plan. Based on the two existing water right permits, the allowable irrigated acreage from the system is 49.5 acres with each residential lot limited to 0.5 acres irrigated. The Owners Association proposes to provide

irrigation water wherever possible to each lot owner up to an average of 0.9 acres or a total irrigated acreage associated with the residential lots of 89.1 acres. Since the current permits allow irrigation of 49.5 acres, the Association is desirous of securing water rights to allow an additional 40 acres or more of irrigation within the place of use of the domestic system but not limited to any certain acreage per lot.

The Association has acquired additional water rights from the Big Wood River. These water rights are recommended in the Snake River Basin Adjudication and are conveyed from the Big Wood River through the Hiawatha Canal. The Hiawatha Canal conveys some 30 cfs of Big Wood River water rights to users adjacent too and south of the Valley Club property. A pumping plant located on the Hiawatha Canal, is owned and operated by the Valley Club and used to divert Big Wood River water rights to the Valley Club Golf Course and amenities. It is proposed to utilize this pumping plant and pipeline to divert newly acquired Big Wood River water rights, currently conveyed in the Hiawatha Canal, to infiltration areas near the north end of the Valley Club Subdivision to mitigate for additional ground water extraction for irrigation of the additional 40 acres. All irrigation of the lots on the Valley Club Subdivision will be served from the two existing wells owned by the Valley Club Owners Association. Locations of the Hiawatha Canal, pump diversion, pipeline and proposed infiltration basins are shown on the aerial photograph, Figure 1.

Members of the Valley Club Home Owners Assoc. dba DRY LOT LLC have purchased 60 acres of water rights 37-21130, 37-21137, and 37-21139 in the Big Wood River all with priority dates of 3/24/1883 and a permissible place of use of 60 acres. Analyses of records of the Watermaster District 37 indicate that this priority right has been cut 16 times in the period 1948 through 2004 or 28 percent of years with the right in priority on average until September 14, average of about 153 days. The earliest it has been cut is July 1, as seen in Appendix B.

Irrigation water requirements for the proposed additional 40 acres were determined based on estimated Pdef (consumptive irrigation requirement) for turf published by the University of Idaho (Allen, 2007). Peak monthly use was determined from potential evapotranspiration at the 80% probability level as published by Allen. This analysis indicates an estimated maximum monthly day ET of 5.75 mm/day (0.23 inches/day) or an average daily consumptive discharge of 0.47 cfs on 40 acres. Irrigation season Pot ET for turf (lawns) at this site is 685mm (2.27 acre feet/acre) so the total annual ET for 40 acres is estimated at 90.8 acre feet and the net irrigation water requirement is estimated to be 77.3 acre feet as shown in Appendix C.

Driller's logs for the two Valley Club Home Owners Association wells indicate sand gravel and clay media to a depth of 140 feet with static water levels of 64 to 71 feet below ground surface. Pumping tests indicate pumping levels of 79 to 84 feet for a discharge of 507 to 657 gpm. An irrigation well owned by the Valley

Club Inc (golf course) adjacent to the two municipal wells is 180 feet deep with sand, gravel and clay throughout the profile. The discharge for this well (locally called the Mizer well) was reported by the driller to be 1800 gpm with a pumping level of 88 feet, as seen in Appendix A.

Based on an application of the Theis equation for pumping of an additional 0.63 cfs from a single well to accommodate the additional peak irrigation requirement of 0.47 cfs, the additional drawdown is estimated less than 1.0 feet at a distance of 1000 feet from the well after continuous pumping for 40 days. This analysis is shown in Appendix A.

Alternative infiltration basin locations are proposed for the project. Dual infiltration basins near the north end of the project and near the middle of the project as shown on Figure 1 are proposed with water supplied from the pumping plant on the Hiawatha Canal through the pipeline to the northernmost pond on the Valley Club golf course (Figure 1). Water would be pumped from the pipeline or the northern Valley Club pond to two or four infiltration basins. The sustainable infiltration rate for the infiltration basins is estimated at a minimum of 1.5 ft/day through a substrate of at least 18 inches of select filter sand. Based on an annual calculated infiltration requirement of 138 acre feet, pond evaporation of 1.22 acre feet and an infiltration period of 153 days, the average infiltration of the basins would be 0.91 acre feet per day or an average discharge of 0.46 cfs (206 gpm). With an infiltration rate of 1.5 ft/day, the basin wetted area required would be 0.6 acres or 26,140 square feet. The two sets of two proposed basins would be approximately 75 x 175 feet each in size and located at least 500 feet from any existing wells.

A pump from the Valley Club upper pond to the northern infiltration basins would be designed for a discharge of 400 gpm and the lower set of basins would be served directly from the Valley Club pipeline. A totalizing flow meter is required on the Valley Club Inc. pumping system from the Hiawatha Canal and a meter with instantaneous readout and totalizer would be installed on the pipeline to the infiltration basins with monthly reporting to ascertain the volume infiltrated. Flow meters are currently installed on the two domestic wells and total volumes pumped are documented to assure compliance with water right.

The goal of the water right acquisition is to assure that an additional 40 acres can be irrigated anywhere on the subdivision and that each lot owner has the opportunity to irrigate, if he or she desires, a total of 0.9 acres. Each lot owner may irrigate up to 0.5 acres from the original two water rights. The additional 40 acres of irrigation allowed by the proposed permit and transfer can be allocated by the Owners Association any place within the authorized place of use which includes all lots and common area in the subdivision. In addition, the Association would like to assure that the full additional 40 acres could be irrigated for the full irrigation season even though the 3/24/1883 priority water right is not available for the full irrigation season. This mitigation plan proposes to assure that an

adequate volume of water is replaced in the aquifer from the 3/24/1883 water right to mitigate the additional use on the 40 acres after the cutoff date to the end of the irrigation season. This plan is based on the seasonal consumptive irrigation requirement on the new acres for the latter part of the irrigation season with no expansion of the water right discharge or volume.

At total buildout of the subdivision, there will be 99 residences with a maximum irrigated turf area within the place of use of an average of 0.9 acres per lot or 89.1 acres. Current ground water rights allow the irrigation of 99x 0.5 or 49.5 acres. The additional irrigated acreage is therefore 39.6 acres at full buildout. The additional water right purchased by Valley Club Owners Assoc. is the 3/24/1883 irrigation right which allows 60 acres of irrigation with the established irrigation diversion of 3.5 af/acre for a full irrigation season or 210 acre feet for the 60 purchased acres. On average, this right has been on 153 days or through September 15. As shown in Appendix C, the consumptive irrigation requirement for the 153 days is estimated at 2.56 acre feet per acre or 168.8 acre feet on the 60 historically irrigated acres assuming a frequently cut alfalfa crop.

The seasonal consumptive irrigation requirement for the 39.6 additional irrigated acres on the Valley Club Subdivision is estimated at 39.6×1.95 ac ft/acre or 77.3 acre feet for the full 183 day season. Since the average length of time the 3/24/1883 right is in priority is 153 days out of the 183 days in the established irrigation season, the additional consumptive irrigation requirement to extend the season from 153 days to 183 days is 0.164 ac ft/acre or $0.164 \times 39.6 = 6.5$ acre feet (Table 1). By operating the infiltration system for 153 days, from April 15 through September 15, approximately 138 acre feet will be added to the aquifer which will more than mitigate for the irrigation season consumptive irrigation requirement of 77.3 acre feet. The 77.3 acre feet of seasonal consumptive irrigation requirement for the additional Valley Club Owners acreage is $77.3/168.8 = 46\%$ of the seasonal consumptive irrigation requirement under the purchased water right. Therefore, at full buildout, approximately 54% of the seasonal consumptive irrigation requirement on the 60 acres of the 3/24/1883 water right will not be required for mitigation. Additionally, the average groundwater diversion for the full irrigation season of 138.1 acre feet is matched by the infiltration volume of 138.3 acre feet so there is no net temporal impact on the aquifer. The infiltration volume exceeds the diversion requirement throughout the irrigation season until the surface water right is out of priority (see seasonal graph of infiltration). Since the ground water diversion points and infiltration basins for the north set of basins are approximately 700 feet apart the local effect on the aquifer will be minimal. Recharge using the lower set of basins will not likely impact the late season aquifer levels significantly since the volume expected for late season extension of 6.5 acre feet. Pumping of the extended season of volume of 6.5 acre feet is not expected to significantly impact any local ground water diversions. The proposed place of use for the recently purchased water rights 37-21130, 37-21137, and 37-21139 will consist of the entire subdivision as shown in Appendix D. This place of use consists of 221.7 acres

and the total allowed irrigation including existing and new water rights is 89.1 acres.

The mitigation project will be phased to match the buildout rate of the residences within the subdivision and a mitigation schedule for each year of the planned phases would be prepared and submitted to IDWR as required. It is proposed that any portion of the water right not required for mitigation will be diverted as a non-consumptive use into the Valley Club golf course recreation and aesthetic ponds and ultimately back in to the Hiawatha Canal to mitigate seepage losses in the Hiawatha which impact existing down canal water users. Alternately, the remainder of the Big Wood River rights would be offered to the Idaho State Water Bank.

A maintenance program for the infiltration basin will be developed and followed to assure that infiltration rates are maintained. This program will consist of scarifying the bottom of the basin and/or removal of fine grained sediments as necessary.

The place of use of the water right purchased for ground water mitigation is located approximately three (3) miles south of the new proposed place of use on the Valley Club Subdivision, Figure 2. Cessation of irrigation with Big Wood River water on the historical place of use will reduce deep percolation to the Big Wood River Valley aquifer. However, the infiltration of water in excess of the additional net depletion at the proposed new site will more than mitigate for the increased groundwater pumped at the new site and assist in mitigation for the decreased deep percolation at the historical site.

The water rights purchased by the Dry Lot LLC for mitigation of aquifer pumping requires moving the diversion upstream in the Hiawatha Canal approximately 3.4 miles. The historical loss in this reach of the Hiawatha has been shared by water right holders with deliveries throughout the length of the canal. Recently (2006) a 4350 foot length of the Hiawatha Canal was rehabilitated by the Valley Club Inc. and lined with a membrane to reduce seepage. An analysis of seepage losses in the Hiawatha was performed by the IDWR Twin Falls Regional Office in conjunction with a previous transfer. This analysis shows that, with the recent lining of part of the canal, moving the diversion of 4.0 cfs of the purchased water rights upstream to the Valley Club Inc diversion will require 0.50 cfs to remain in the canal to make up the additional impact to down-canal water users. Therefore, the remaining 3.55 cfs is available for diversion at the Valley Club Inc. diversion. The spreadsheets showing the IDWR analysis are included in Appendix D.

BEFORE THE IDAHO DEPARTMENT OF WATER RESOURCES

IN THE MATTER OF WATER USE
ON THE PROPERTY NOW KNOWN AS THE OLD
CUTTERS, HAILEY, ID AND WATER
RIGHTS 37-21130, 37-21137, 37-21139

) COMMENTS AND
) EVIDENCE OF
) CHARLIE CORD
)
)

COMES NOW, CHARLIE CORD, and provides the following comments and evidence in this matter:


1. I owned the Old Cutters property in Blaine County ID, from the late 1980's through 2003. The Old Cutters property is located in Township 02N, Range 18E, Sec.3 SW $\frac{1}{4}$ SW $\frac{1}{4}$ and Sec.4 NE $\frac{1}{4}$ SE $\frac{1}{4}$, SE $\frac{1}{4}$ SE $\frac{1}{4}$, SW $\frac{1}{4}$ SE $\frac{1}{4}$ and NW $\frac{1}{4}$ SE $\frac{1}{4}$.
2. The Old Cutters property used gravity methods to irrigate the farm from the time I purchased the property, until the time I sold the property. Sixty six (66.0) acres or more of the Old Cutters property was planted in alfalfa hay and/or pasture during most of the years that I owned the property. The alfalfa hay and/or pasture was used as feed for horses and cows.

DATED this 11 day of Jan, 2008.

Charlie Cord

Charlie Cord


SUBSCRIBED and SWORN to before me this 11th day of January, 2008



Deborah Erickson
NOTARY PUBLIC

Residing at : Hailey, ID

My Commission Expires: 10/09/10



**VALLEY CLUB HOME OWNERS INC.
PROPOSED INFILTRATION BASIN LOCATIONS
2006 AERIAL PHOTOGRAPH**

1 inch = 600ft

0 310 620 1,240 Feet



BROCKWAY ENGINEERING, PLLC.
ZL - 3/13/08

Appendix A

Well Drillers Logs and Well Interface


56087

1. DRILLING PERMIT NO. 37. 94. S. 0089 . 000
Other IDWR No. 37-08810

2. OWNER: Valley Ranch Partners
Name
Address 7 EHM Engineers 621 N College
City Twin Falls State ID Zip 83301

3. LOCATION OF WELL by legal description:

Sketch map location must agree with written location.



Twp. 3 North ☒ or South ☐
 Rge. 18 East ☒ or West ☐
 Sec. 20 SW 1/4 NE 1/4 1/4
 Gov't Lot _____ County Blaine

Address of Well Site **Valley Club Drive**

(Give at least name of road + Distance to Road or Landmark)

Lt. _____ Blk. _____ Sub. Name The Valley Club
Parcel B

4. PROPOSED USE:

☒ Domestic ☐ Municipal ☐ Monitor ☐ Irrigation
☐ Thermal ☐ Injection ☐ Other

5. TYPE OF WORK

☒ New Well ☐ Modify or Repair ☐ Replacement ☐ Abandonment

6. DRILL METHOD

☐ Mud Rotary ☒ Air Rotary ☐ Cable ☐ Other_____

7. SEALING PROCEDURES

SEAL/FILTER PACK			AMOUNT	METHOD
Material	From	To	Sacks or Pounds	
Cement grout	0	20	60 sk	Overbore

Was drive shoe used? Y ☒ N ☐

Was drive shoe seal tested? Y ☐ N ☒ How?

8. CASING/LINER:

Diameter	From	To	Gauge	Material	Casing	Liner	Welded	Threaded
10.75	+3	140	365	Steel	☒	☐	☐	☒
					☐	☐	☐	☒
					☐	☐	☐	☐

Length of Headpipe_____ Length of Tailpipe_____

9. PERFORATIONS/SCREENS

☒ Perforations Method Knife

☐ Screens Screen Type _____

From	To	Slot Size	Number	Diameter	Material	Casing	Live
64	136	1/8 x 1/8	± 750			☒	☐
						☐	☐
						☐	☐

10. STATIC WATER LEVEL OR ARTESIAN PRESSURE:

64 ft. below ground Artesian pressure _____ lb.
Depth flow encountered _____ ft. Describe access port or
control devices:

11. WELL TESTS:

☒ Pump ☐ Bailer ☐ Air ☐ Flowing Artesian

Yield gal./min.	Drawdown	Pumping Level	Time
657	31 ft.	79 feet	7½ hr.

Water Temp. 48 Bottom hole temp.

Water Quality test or comments:

12. LITHOLOGIC LOG: (Describe repairs or abandonment)

Bore Dia.	From	To	Remarks: Lithology, Water Quality & Temperature	Y	N
16	0	3	Surface soil & gravel		
	3	8	Boulders & gravel		
	8	14	Clay & boulders		
	14	16	Gravel		
	16	20	Clay & gravel (stays open)		
10	20	42	Clay & gravel		
	42	47	Coarse gravel, sand & clay		
	47	50	Clay & gravel	T	
	50	57	Coarse gravel		
	57	64	Clay & gravel		
	64	77	Gravel & sand	X	
	77	84	Clay, gravel & sand	?	
	84	97	Gravel & sand	X	
	97	105	Coarse gravel & clay	?	
	105	109	Clay & gravel		X
	109	140	Gravel, sand & clay	X	

RECEIVED

AUG 12 1953

AUG 02 1994

Department of Water Resource
Southern Region Office

Completed Depth : 140 feet (Measurable)
Date: Started 7/13/94 Completed 7/20/94

T3-DRILLER'S CERTIFICATION

I/We certify that all minimum well construction standards were complied with at the time the rig was removed.

Firm Name **Walker Water Systems, Inc.** 624 Pierce Street Firm No. 15

Twin Falls, Idaho 83301

Firm Official _____ Date 11/28/94
and _____
Supervisor or Operator Paul Walk Date _____

(Sign once if Firm Official & Operator)

IDAHO DEPARTMENT OF WATER RESOURCES

WELL DRILLER'S REPORT

**Use Typewriter
or
Ball Point Pen**

1. DRILLING PERMIT NO. 37. 94. S. 0078 . 000
Other IDWR No. _____

2. OWNER:
Name Valley Ranch Partners
Address % EHM Engineers 621 N College Suite 100
City Twin Falls State ID Zip 83301

3. LOCATION OF WELL by legal description:

Sketch map location must agree with written location.

N
 W E S
 Twp. 3 North ☒ or South ☐
 Rge. 18 East ☒ or West ☐
 Sec. 20 SW 1/4 NE 1/4 1/4
 Gov't Lot _____ County Blaine 10 acres 160 acres
 S

Address of Well Site Valley Club Drive
City _____

Lt. _____ Blk. _____ Sub. Name The Valley Club
Parcel A

4. PROPOSED USE:

☒ Domestic ☐ Municipal ☐ Monitor ☐ Irrigation
☐ Thermal ☐ Injection ☐ Other

5. TYPE OF WORK

☒ New Well ☐ Modify or Repair ☐ Replacement ☐ Abandonment

6. DRILL METHOD

☐ Mud Rotary ☒ Air Rotary ☐ Cable ☐ Other _____

7. SEALING PROCEDURES

SEAL/FILTER PACK			AMOUNT	METHOD
Material	From	To	Sacks or Pounds	
Cement	0	20	40 Sk	Overbore

Was drive shoe used? Y ☒ N ☐
Was drive shoe seal tested? Y ☐ N ☒ How?

8. CASING/LINER:

Diameter	From	To	Gauge	Material	Casing	Liner	Welded	Thread
12.75	+3	140	375	Steel	☒	☐	☒	☐
					☐	☐	☐	☐
					☐	☐	☐	☐

Length of Headpipe _____ Length of Tailpipe _____

9. PERFORATIONS/SCREENS

☒ Perforations Method Knife
☐ Screens Screen Type _____

From	To	Slot Size	Number	Diameter	Material	Casing	Line
70	136	1/4 x 1/8	±1020			☒	☐
						☐	☐
						☐	☐

10. STATIC WATER LEVEL OR ARTESIAN PRESSURE:

71 ft. below ground Artesian pressure _____ lb.
Depth flow encountered _____ ft. Describe access port or
control devices:

11. WELL TESTS:

☒ Pump ☐ Bailer ☐ Air ☐ Flowing Artesian

Yield gal./min.	Drawdown	Pumping Level	Time
507	36 ft.	84'	7½ hr.

Water Temp. _____ Bottom hole temp. _____

Water Quality test or comments:_____

12. LITHOLOGIC LOG: (Describe repairs or abandonment)

Water

Bore Dia.	From	To	Remarks: Lithology, Water Quality & Temperature	Y	N
18	0	2	Surface		
	2	6	Gravel		
	6	17	Boulders & gravel		
	17	20	Coarse gravel & clay		
12	20	30	Coarse gravel & clay		
	30	45	Gravel & clay		
	45	47	Coarse gravel		
	47	51	Clay & gravel		
	51	71	Coarse gravel & sand	T	
	71	80	Coarse gravel & sand	X	
	80	84	Clay & gravel		
	84	95	Gravel & sand	X	
	95	108	Clay & gravel & sand	X	
	108	130	Coarse gravel & sand	X	
	130	140	Gravel & clay	X	

~~REF ID: A66484~~

~~AUG 12 1964~~

Department of the Army

|| 5 5 | 5 ||

~~AUG 02 1994~~

Department of Water Resource
Southern Region Office

Completed Depth	140 feet	(Measurable)
Date: Started	6/22/94	Completed 7/8/94

13. DRILLER'S CERTIFICATION

I/We certify that all minimum well construction standards were complied with at the time the rig was removed.

Walker Water Systems, Inc.
Firm Name 624 Pierce Street Firm No. 15
Twin Falls, Idaho 83301

Firm Official _____ Date 7/25/94
and
Supervisor or Operator J. I. Welch Date _____

(Sign once if Firm Official & Operator)

FORWARD WHITE COPY TO WATER RESOURCES

RECEIVED
OCT 28 1959
Department of Agriculture

**WELL LOG AND REPORT OF THE
STATE RECLAMATION ENGINEER OF IDAHO**

034429

Permit No. _____ Well No. _____ County Belt
Owner Morgan Bros
Address Hailey Idaho
Driller Eugene H. Walker
Address Twin Falls
Well location SE 1/4 NW 1/4 Sec 20 T. 2 N. R. 18 E. NW
Size of drilled hole 20 in

Locate well in section

NW 1/4	NE 1/4
SW 1/4	SE 1/4

Total depth of well 180
Give depth to standing water from the ground 41 1/2" Water temp. 46 °Fahr.

On "Pumping Test" delivery was 1800 g.p.m. or _____ c.f.s. Drawdown was 88 feet.

Size of pump and motor used to make test 12 in Boral 300 HP Diesel

Length of time of test 5 hours _____ minutes.

If flowing well, give flow _____ c.f.s. or _____ g.p.m. and of shut off pressure _____

If flowing well, described control works _____

(TYPE AND SIZE OF VALVE, ETC.)

Water will be used for Irrigation Weight of casing per lineal foot 65 lb

Thickness of casing 5/16 Casing material Steel
(STEEL, CONCRETE, WOOD, ETC.)

Diameter, length and location of casing 20" 174 Surface to 174
(CASING 12" IN DIAMETER OR LESS, GIVE INSIDE DIAMETER;
CASING OVER 12" IN DIAMETER, GIVE OUTSIDE DIAMETER)

CASING RECORD

Diam. Casing	From Feet	To Feet	Length	Remarks—seals, grouting, etc.
<u>20</u>	<u>0</u>	<u>174</u>	<u>174</u>	

Number and size of perforations 2285 located 41 feet to 170 feet from ground

Mills Knife 1/2" x 3"

Date of commencement of well 24 July Date of completion of well 3 Sep

SE NW 5.20 3N18E

WELL LOG

From Foot	To Foot	Type of Material	Water-bearing Formation Abn. Yes or No	Casing Perforated Abn. Yes or No
0	3	Surface	No	No
3	45	Coarse gravel, sand & Boulders	No	No
45	55	Gravel, thin layers of clay	Yes	Yes
55	70	Gravel & clay	No	Yes
70	81	Gravel	Yes	Yes
81	92	Gravel & clay	Yes	Yes
92	105	Cemented gravel & clay with large Boulders	No	Yes
105	112	Boulders, gravel & clay	No	Yes
112	130	Gravel, some clay	Yes	Yes
130	143	Gravel Pink clay	?	Yes
143	145	Pink clay	No	Yes
145	161	Gravel - Pink clay	?	Yes
161	163	Pink clay	No	Yes
163	170	Red shale, gravel & Pink clay	?	Yes
170	180	1 1	?	No
If more space is required use Sheet No. 2				

WELL DRILLER'S STATEMENT

This well was drilled under my supervision and the above information is true and correct to the best of my knowledge and belief.

Signed Eugene W. Walker
By _____

Dated 1 Oct 1959

License No. 15

IDAHO DEPARTMENT OF WATER RESOURCES
WELL DRILLER'S REPORT

Official Use Only			
Inspected by _____			
Twp _____	Rge _____	Sec _____	
_____ 1/4	_____ 1/4	_____ 1/4	
Lat: _____	Long: _____		

1. WELL TAG NO. D - 0037012

DRILLING PERMIT NO. 836697

Other IDWR No. 37-21435

2. OWNER

Name SEA BOARD PROPERTIES INC.

Address P.O. BOX 3510

City Ketchum State ID Zip 83340

3. LOCATION OF WELL by legal description:

Sketch map location must agree with written location

N		Twp. 3		☒ North or ☐ South	
W		Rge. 18		☒ East or ☐ West	
E		Sec. 20		SW 1/4 NE 1/4 NE 1/4	
S		Gov't Lot _____		County BLAINE	
		Lat: _____		Long: _____	

Address of Well Site 3/4 E IF HWY 75 ON OHIO GULCH ROAD City HAILEY

(Give at least name of road + Distance to Road or Landmark)

Lt. _____ Blk. _____ Sub. Name BLUE GROUSE

Well Lot #A

4. USE:

☐ Domestic ☒ Municipal ☐ Monitor ☐ Irrigation☐ Thermal ☐ Injection ☐ Other

5. TYPE OF WORK check all that apply (replacement ect.)

☒ New Well ☐ Modify ☐ Abandonment ☐ Other

6. DRILL METHOD

☒ Air Rotary ☐ Cable ☐ Mud Rotary ☐ Other

7. SEALING PROCEDURES

Seal/Filter Pack			Amount	Method
Material	From	To	Sacks or Pounds	
BENT	0	60	6350 LBS	OVERBORE

Was drive shoe used? ☒ Y ☐ N Shoe depth(s) _____Was drive shoe seal tested? ☐ Y ☒ N How? _____

8. CASING/LINER

Dia.	From	To	Gauge	Material	Casing	Liner	Welded	Threaded
8	± 3	120	322	STEEL	☒	☐	☒	☐
					☐	☐	☐	☐
					☐	☐	☐	☐

Length of Headpipe _____

Length of Tailpipe _____

9. PERFORATIONS/SCREENS

Perforations Methods AIR KNIFE

Screens Screen Type _____

From	To	Slot Size	Number	Diameter	Material	Casing	Liner
70	100	1/4	± 400	8	STEEL	☒	☐
						☐	☐
						☐	☐

10. STATIC WATER LEVEL OR ARTESIAN PRESSURE:

59 ft below ground

Artesian pressure _____

depth flow encountered _____ ft.

Describe access port _____

or control devices WELL CAP

11. WELL TESTS:

☐ Pump	☐ Bailer	☒ Air	☐ Flowing Artesian
Yield gpm	Drawdown	Pumping Level	Time
± 200			

Water Temp. 48°

Bottom hole temp. _____

Water Quality test or comments: _____

Depth first water encounter _____

12. LITHOLOGIC LOG: (Describe repairs or abandonment)

Dia.	From	To	Remarks: Lithology, Water Quality & Temperature	Water	Y	N
12	0	6	SOIL & GRAVEL			
	6	35	HARD CLAY BROWN			
	35	40	GRAVEL/ COARSE CLAY			
	40	45	GRAVEL/ SAND /CLAY			
	45	56	BOULDERS & GRAVEL			
	56	60	COARSE GRAVEL			
8	60	63	GRAVEL & CLAY			
	63	65	CLAY & GRAVEL			
	65	68	CLAY SILT & GRAVEL		X	
	68	72	COARSE GRAVEL & SAND		T	
	72	77	SMALL GRAVEL		X	
	77	82	MEDIUM GRAVEL & CLAY			
	82	87	COARSE GRAVEL		X	
	87	88	COARSE GRAVEL			
	88	92	COARSE GRAVEL			
	92	97	COARSE GRAVEL W/ LOTS OF FINES		X	
	97	101	SMALLER GRAVEL & FINES LITTLE CLAY		X	
	101	107	MED GRAVEL & LOTS OF CLAY & SILT			
	107	109	FINE GRAVEL & LOTS OF CLAY & SILT		X	
	109	120	STICKY CLAY & SILT			

RECEIVED

DEC 09 2005

Department of Water Resources
Southern Region

Completed depth 120 ft. (measurable)

Date: Started November 13, 2005

Completed November 21, 2005

13. DRILLERS CERTIFICATION

I/We certify that all minimum well construction standards were complied with at the time the rig was removed.

Company Name WALKER WATER SYSTEMS Firm No. 15

624 PIERCE ST. TWIN FALLS, ID 83301

Firm Official

Date 11/28/05

and

Driller or Operator

Date 11/28/05

(Sign once in Firm Official & Operator)

WELL DRILLER'S REPORT

State law requires that this report be filed with the Director, Department of Water Resources within 30 days after the completion or abandonment of the well.

1. WELL OWNER
Name Bob Brennan
Address 1411 Marsh St. Suite 207
San Luis Abispo, Cal. 93401
Owner's Permit No. 37-90-S-048 OL

2. NATURE OF WORK
☒ New well ☐ Deepened ☐ Replacement
☐ Well diameter increase
☐ Abandoned (describe abandonment procedures such as materials, plug depths, etc. in lithologic log)

3. PROPOSED USE
☒ Domestic ☐ Irrigation ☐ Test ☐ Municipal
☐ Industrial ☐ Stock ☐ Waste Disposal or Injection
☐ Other _____ (specify type)

4. METHOD DRILLED
☒ Rotary ☐ Air ☐ Hydraulic ☐ Reverse rotary
☐ Cable ☐ Dug ☐ Other _____

5. WELL CONSTRUCTION
Casing schedule: ☒ Steel ☐ Concrete ☐ Other _____
Thickness .250 inches Diameter 6 inches From 1 1/2 feet To 58 1/2 feet
_____ inches _____ inches _____ feet _____ feet
_____ inches _____ inches _____ feet _____ feet
_____ inches _____ inches _____ feet _____ feet
Was casing drive shoe used? ☒ Yes ☐ No
Was a packer or seal used? ☐ Yes ☒ No
Perforated? ☐ Yes ☒ No
How perforated? ☐ Factory ☐ Knife ☐ Torch ☐ Gun
Size of perforation _____ inches by _____ inches
Number _____ From _____ To _____
_____ perforations _____ feet _____ feet
_____ perforations _____ feet _____ feet
_____ perforations _____ feet _____ feet
Well screen installed? ☐ Yes ☒ No
Manufacturer's name _____
Type _____ Model No. _____
Diameter _____ Slot size _____ Set from _____ feet to _____ feet
Diameter _____ Slot size _____ Set from _____ feet to _____ feet
Gravel packed? ☐ Yes ☒ No ☐ Size of gravel _____
Placed from _____ feet to _____ feet
Surface seal depth 20 Material used in seal: ☐ Cement grout
☒ Bentonite ☐ Puddling clay ☐ _____
Sealing procedure used: ☐ Slurry pit ☒ Temp. surface casing
☒ Overbore to seal depth
Method of joining casing: ☐ Threaded ☒ Welded ☐ Solvent Weld
☐ Cemented between strings
Describe access port _____

6. LOCATION OF WELL
Sketch map location must agree with written location.
N
W X E
S
County BLAINE
Subdivision Name STAR
WEATHER PLAT 1
Lot No. 60B Block No. 1
SW 1/4 NW 1/4 Sec. 20 T. 3 S. R. 18 W.

7. WATER LEVEL
Static water level 9 feet below land surface.
Flowing? ☐ Yes ☒ No G.P.M. flow _____
Artesian closed-in pressure _____ p.s.i.
Controlled by: ☐ Valve ☐ Cap ☐ Plug
Temperature _____ of. Quality good
Describe artesian or temperature zones below.

8. WELL TEST DATA
☐ Pump ☐ Bailer ☒ Air ☐ Other _____
Discharge G.P.M. Pumping Level Hours Pumped
100 35 1

9. LITHOLOGIC LOG

Bore Diam.	Depth		Material	Water	
	From	To		Yes	No
8	0	2	Topsoil		
8	2	5	Boulders		X
8	5	12	Gravel	X	
8	12	17	Sand	X	
8	17	34	Gravel	X	
6	34	37	Gravel and clay	X	
6	37	60	Gravel	X	

10.
Work started 5-10-90 finished 5-14-90

11. DRILLERS CERTIFICATION
I/We certify that all minimum well construction standards were complied with at the time the rig was removed.
WOOD RIVER DRILLING AND PUMP Firm No. 265
BOX 1165 788-3163
Address HAILEY, IDAHO 83333 Date 5-29-90
Signed by (Firm Official) Ron Smith
and
(Operator) BOB McLaughlin

USE ADDITIONAL SHEETS IF NECESSARY - FORWARD THE WHITE COPY TO THE DEPARTMENT

RECEIVED

REPORT OF WELL DRILLER
State of Idaho

MAY 29 1969

State law requires that this report shall be filed with the State Reclamation Engineer within 30 days after completion or abandonment of the well.

WELL OWNER:

Name RALPH THORNTON

Address KETCHUM, IDAHO (GIMLET)

Owner's Permit No. _____

NATURE OF WORK (check): Replacement well ☐

New well ☒ Deepened ☐ Abandoned ☐

Water is to be used for: DOMESTIC

METHOD OF CONSTRUCTION: Rotary ☐ Cable ☒

Dug ☐ Other _____

(explain)

CASING SCHEDULE: Threaded _____ Welded ☒

6 "Diam. from 0 ft. to 63 ft.

"Diam. from _____ ft. to _____ ft.

"Diam. from _____ ft. to _____ ft.

"Diam. from _____ ft. to _____ ft.

Thickness of casing: .250 Material:

Steel ☒ concrete ☐ wood ☐ other ☐

(explain)

PERFORATED? Yes ☐ No ☒ Type of perforator used: _____

Size of perforations: _____ " by _____ "
perforations from _____ ft. to _____ ft.
perforations from _____ ft. to _____ ft.
perforations from _____ ft. to _____ ft.
perforations from _____ ft. to _____ ft.

WAS SCREEN INSTALLED? Yes ☐ No ☒

Manufacturer's name _____

Type _____ Model No. _____

Diam. _____ Slot size _____ Set from _____ ft. to _____ ft.

Diam. _____ Slot size _____ Set from _____ ft. to _____ ft.

CONSTRUCTION: Well gravel packed? Yes ☐

No. ☒ size of gravel _____ Gravel

placed from _____ ft. to _____ ft. Surface seal

provided? Yes ☒ No ☐ To what depth?

_____ ft. Material used in seal: CLAY GROUTED

WHILE PUTTING CASING DOWN

Did any strata contain unusable water? Yes ☐

No. ☒ Type of water: _____


Depth of strata _____ ft. Method of sealing

strata off: _____

Surface casing used? Yes ☐ No ☐

Cemented in place? Yes ☐ No ☐

Locate well in section



LOCATION OF WELL: County BLAINE

SE * NW * Sec. 20 T. 3N R. 18E E/0

Use other side for additional remarks

Size of drilled hole: 6" Total
depth of well: 63ft Standing water
level below ground: 38ft Temp. _____
Fahr. _____ ° Test delivery: OVER 25 gpm
or _____ cfs Pump? ☒ Bail ☒
Size of pump and motor used to make test: _____

Length of time of test: _____ Hrs. _____ Min.
Drawdown: _____ ft. Artesian pressure: _____ ft.
above land surface _____ Give flow _____ cfs
or _____ gpm. Shutoff pressure: _____
Controlled by: Valve ☐ Cap ☐ Plug ☐
No control ☐ Does well leak around casing?
Yes ☐ No ☒

DEPTH MATERIAL 39883 WATER
FROM TO YES OR NO

FET	FEET		
0	12	GRAVEL & BOULDERS SOME CLAY	NO
12	43	GRAVEL SET IN CLAY	NO
43	58	SAND WITH SMALL PEA GRAVEL	YES
58	63	COURSE GRAVEL WITH WATER	YES

Work started: 30 APRIL 1969

Work finished: 5 MAY 1969

Well Driller's Statement: This well was drilled under my supervision and this report is true to the best of my knowledge.

Name: CLAUDE NICHOLSON

Address: BOX 322 SHOSHONE, IDAHO

Signed by: Claude Nicholson

License No. 159 Date: 27 MAY 1969

USGS

UNCORRECTED COPY

Form 238-7
11/97

IDAHO DEPARTMENT OF WATER RESOURCES
WELL DRILLER'S REPORT

RECEIVED

1. WELL TAG NO. D 0030113

DRILLING PERMIT NO. _____

Other IDWR No. _____

JAN 21 2004

2. OWNER:

Name Seaboard Corporation

Department of Water Resources
Southern Region


Address P.O. BOX 3510

City Ketchum

State ID Zip 83340

3. LOCATION OF WELL by legal description:

Sketch map location must agree with written location.



Twp. 03 North ☒ or South ☐
Rge. 18 East ☒ or West ☐
Sec. 20 1/4 NW 1/4 NE 1/4
Gov't Lot _____ County Blaine
Lat: _____ Long: _____

Address of Well Site Old Dump Site

Between Hailey & Ketchum City Hailey

Li. _____ Blk. _____ Sub. Name Blue Grouse

4. USE:

☐ Domestic ☐ Municipal ☒ Monitor ☐ Irrigation
☐ Thermal ☐ Injection ☐ Other _____

5. TYPE OF WORK check all that apply (Replacement etc.)

☒ New Well ☐ Modify ☐ Abandonment ☐ Other _____

6. DRILL METHOD

☒ Air Rotary ☐ Cable ☐ Mud Rotary ☐ Other _____

7. SEALING PROCEDURES

SEAL/FILTER PACK			AMOUNT		METHOD
Material	From	To	Sacks or Pounds		
Bentonite	0	20	18Sks		Overbore
Bentonite	103	143	13Sks		Backfill

Was drive shoe used? ☒ Y ☐ N Shoe Depth(s) 143'

Was drive shoe seal tested? ☐ Y ☒ N How? _____

8. CASING/LINER:

Diameter	From	To	Gauge	Material	Casing	Liner	Welded	Threaded
6"	+1 1/2	143	250	Steel	☒	☐	☒	☐
					☐	☐	☐	☐
					☐	☐	☐	☐

Length of Headpipe _____ Length of Tailpipe _____

9. PERFORATIONS/SCREENS

Perforations Method Torch

Screens Screen Type _____

From	To	Slot Size	Number	Diameter	Material	Casing	Liner
70'	100'	1/8	110	6"	Steel	☒	☐
						☐	☐
						☐	☐

10. STATIC WATER LEVEL OR ARTESIAN PRESSURE:

74 ft. below ground Artesian pressure _____ lb.

Depth flow encountered _____ ft. Describe access port or control devices: _____

11. WELL TESTS:

☐ Pump ☐ Bailer ☐ Air ☐ Flowing Artesian

Yield gal./min.	Drawdown	Pumping Level	Time
1/4			1 Hour

Water Temp. _____

Bottom hole temp. _____

Water Quality test or comments: _____

Depth first Water Encounter _____

12. LITHOLOGIC LOG: (Describe repairs or abandonment)

Bore Dia.	From	To	Remarks: Lithology, Water Quality & Temperature	Y	H
10	0	20	Sand-Gravel-Clay		X
6	20	40	Sand		X
6	40	51	Gravel & Boulders		X
6	51	57	Sand		X
6	57	59	Boulders		X
6	59	80	Sand & Clay	X	
6	80	83	Sand & Clay		X
6	83	94	Clay		X
6	94	108	Sand & Boulders	X	
6	103	148	Clay		X

SCANNED

JAN 22 2004

Completed Depth 143' (Measurable)

Date: Started 12-30-03 Completed 12-31-03

13. DRILLER'S CERTIFICATION

We certify that all minimum well construction standards were complied with at the time the rig was removed.

Company Name Wood River Drilling Firm No. 265

& Pump, Inc.

Firm Official Ken Smith Date 01-12-04

and

Driller or Operator Boonchay Date _____

(Sign once if Firm Official & Operator)

FORWARD WHITE COPY TO WATER RESOURCES

SEP 1963

State law requires that this report be filed with the Director, Department of Water Resources within 30 days after the completion or abandonment of the well.

1. WELL OWNER Name <u>Stephen D. Pruitt</u> Address <u>P. O. Box 479 Sun Valley, ID 83353</u> Owner's Permit No. _____	7. WATER LEVEL Static water level _____ feet below land surface. Flowing? ☐ Yes ☒ No G.P.M. flow _____ Artesian closed-in pressure _____ p.s.i. Controlled by: ☐ Valve ☐ Cap ☐ Plug Temperature <u>48</u> °F. Quality _____ Describe artesian or temperature zones below.																																																					
2. NATURE OF WORK ☒ New well ☐ Deepened ☐ Replacement ☐ Abandoned (describe abandonment procedures such as materials, plug depths, etc. in lithologic log)	8. WELL TEST DATA ☐ Pump ☐ Bailer ☒ Air ☐ Other _____ <table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th>Discharge G.P.M.</th> <th>Pumping Level</th> <th>Hours Pumped</th> </tr> </thead> <tbody> <tr> <td align="center"><u>30</u></td> <td></td> <td align="center"><u>1</u></td> </tr> <tr><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td></tr> </tbody> </table>	Discharge G.P.M.	Pumping Level	Hours Pumped	<u>30</u>		<u>1</u>																																															
Discharge G.P.M.	Pumping Level	Hours Pumped																																																				
<u>30</u>		<u>1</u>																																																				
3. PROPOSED USE ☒ Domestic ☐ Irrigation ☐ Test ☐ Municipal ☐ Industrial ☐ Stock ☐ Waste Disposal or Injection ☐ Other _____ (specify type)	9. LITHOLOGIC LOG 83139 <table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th>Bore Diam.</th> <th colspan="2">Depth</th> <th rowspan="2">Material</th> <th colspan="2">Water</th> </tr> <tr> <th></th> <th>From</th> <th>To</th> <th>Yes</th> <th>No</th> </tr> </thead> <tbody> <tr> <td align="center"><u>6</u></td> <td align="center"><u>0</u></td> <td align="center"><u>3</u></td> <td>Surface dirt</td> <td></td> <td></td> </tr> <tr> <td></td> <td align="center"><u>3</u></td> <td align="center"><u>14</u></td> <td>Gravel & sand & clay</td> <td align="center"><u>T</u></td> <td></td> </tr> <tr> <td></td> <td align="center"><u>14</u></td> <td align="center"><u>18</u></td> <td>Boulders</td> <td></td> <td></td> </tr> <tr> <td></td> <td align="center"><u>18</u></td> <td align="center"><u>24</u></td> <td>Gravel & sand & clay</td> <td></td> <td></td> </tr> <tr> <td></td> <td align="center"><u>24</u></td> <td align="center"><u>26</u></td> <td>Gravel</td> <td></td> <td align="center"><u>X</u></td> </tr> <tr> <td></td> <td align="center"><u>26</u></td> <td align="center"><u>39</u></td> <td>Gravel & clay</td> <td></td> <td></td> </tr> <tr> <td></td> <td align="center"><u>39</u></td> <td align="center"><u>45</u></td> <td>Gravel</td> <td></td> <td align="center"><u>X</u></td> </tr> <!-- Empty rows omitted for brevity --> </tbody> </table>	Bore Diam.	Depth		Material	Water			From	To	Yes	No	<u>6</u>	<u>0</u>	<u>3</u>	Surface dirt				<u>3</u>	<u>14</u>	Gravel & sand & clay	<u>T</u>			<u>14</u>	<u>18</u>	Boulders				<u>18</u>	<u>24</u>	Gravel & sand & clay				<u>24</u>	<u>26</u>	Gravel		<u>X</u>		<u>26</u>	<u>39</u>	Gravel & clay				<u>39</u>	<u>45</u>	Gravel		<u>X</u>
Bore Diam.	Depth		Material	Water																																																		
	From	To		Yes	No																																																	
<u>6</u>	<u>0</u>	<u>3</u>	Surface dirt																																																			
	<u>3</u>	<u>14</u>	Gravel & sand & clay	<u>T</u>																																																		
	<u>14</u>	<u>18</u>	Boulders																																																			
	<u>18</u>	<u>24</u>	Gravel & sand & clay																																																			
	<u>24</u>	<u>26</u>	Gravel		<u>X</u>																																																	
	<u>26</u>	<u>39</u>	Gravel & clay																																																			
	<u>39</u>	<u>45</u>	Gravel		<u>X</u>																																																	
4. METHOD DRILLED ☒ Rotary ☒ Air ☐ Hydraulic ☐ Reverse rotary ☐ Cable ☐ Dug ☐ Other _____																																																						
5. WELL CONSTRUCTION Casing schedule: ☒ Steel ☐ Concrete ☐ Other _____ <table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th>Thickness</th> <th>Diameter</th> <th>From</th> <th>To</th> </tr> </thead> <tbody> <tr> <td><u>.250</u> inches</td> <td><u>6 5/8</u> inches + <u>3</u> feet</td> <td><u>45</u> feet</td> <td></td> </tr> <tr><td>_____ inches</td><td>_____ inches</td><td>_____ feet</td><td>_____ feet</td></tr> <tr><td>_____ inches</td><td>_____ inches</td><td>_____ feet</td><td>_____ feet</td></tr> <tr><td>_____ inches</td><td>_____ inches</td><td>_____ feet</td><td>_____ feet</td></tr> </tbody> </table> Was casing drive shoe used? ☒ Yes ☐ No Was a packer or seal used? ☐ Yes ☒ No Perforated? ☐ Yes ☒ No How perforated? ☐ Factory ☐ Knife ☐ Torch Size of perforation _____ inches by _____ inches <table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th>Number</th> <th>From</th> <th>To</th> </tr> </thead> <tbody> <tr> <td>_____ perforations</td> <td>_____ feet</td> <td>_____ feet</td> </tr> <tr> <td>_____ perforations</td> <td>_____ feet</td> <td>_____ feet</td> </tr> <tr> <td>_____ perforations</td> <td>_____ feet</td> <td>_____ feet</td> </tr> </tbody> </table> Well screen installed? ☐ Yes ☒ No Manufacturer's name _____ Type _____ Model No. _____ Diameter _____ Slot size _____ Set from _____ feet to _____ feet Diameter _____ Slot size _____ Set from _____ feet to _____ feet Gravel packed? ☐ Yes ☒ No Size of gravel _____ Placed from _____ feet to _____ feet Surface seal depth <u>18</u> Material used in seal: ☐ Cement grout ☒ Bentonite ☐ Puddling clay ☐ Sealing procedure used: ☐ Slurry pit ☐ Temp. surface casing ☒ Overbore to seal depth Method of joining casing: ☐ Threaded ☒ Welded ☐ Solvent Weld ☐ Cemented between strata Describe access port <u>well cap</u>	Thickness	Diameter	From	To	<u>.250</u> inches	<u>6 5/8</u> inches + <u>3</u> feet	<u>45</u> feet		_____ inches	_____ inches	_____ feet	_____ feet	_____ inches	_____ inches	_____ feet	_____ feet	_____ inches	_____ inches	_____ feet	_____ feet	Number	From	To	_____ perforations	_____ feet	_____ feet	_____ perforations	_____ feet	_____ feet	_____ perforations	_____ feet	_____ feet																						
Thickness	Diameter	From	To																																																			
<u>.250</u> inches	<u>6 5/8</u> inches + <u>3</u> feet	<u>45</u> feet																																																				
_____ inches	_____ inches	_____ feet	_____ feet																																																			
_____ inches	_____ inches	_____ feet	_____ feet																																																			
_____ inches	_____ inches	_____ feet	_____ feet																																																			
Number	From	To																																																				
_____ perforations	_____ feet	_____ feet																																																				
_____ perforations	_____ feet	_____ feet																																																				
_____ perforations	_____ feet	_____ feet																																																				
6. LOCATION OF WELL Sketch map location must agree with written location. Subdivision Name <u>Zinc Spur</u> IMPROVED Lot No. <u>Block</u> County <u>Blaine</u> <u>NW</u> % <u>NE</u> % Sec. <u>20</u> , T. <u>3</u> N/R. <u>18</u> E/W.	10. Work started <u>7/11/83</u> finished <u>7/11/83</u> 11. DRILLERS CERTIFICATION <u>da</u> I/We certify that all minimum well construction standards were complied with at the time the rig was removed. Firm Name <u>Walker Water Systems, Inc.</u> Firm No. <u>15</u> <u>624 Pierce Street</u> Address <u>Twin Falls, Idaho 83301</u> Date <u>7/18/83</u> Signed by (Firm Official) <u>Leland B. Walk</u> and (OPerator) <u>Leland B. Walk</u>																																																					

Appendix B
Water Rights Purchased

Valley Club Owners Assoc.
 Cutter Water Right Seasonal CIR
 Water Right Numbers 37-21130 37-21137 37-21139
 Period of Active Priority Based on WD 37 Records Acres 66
 Exceedance 80% Number of Days on 122 or until August 15
 Estimated Irrigation Efficiency-flood irrigation 0.5

Alfalfa (frequent cuttings) Pdef					Net irrigation water requirement (CIR)					
Month	Apr	May	Jun	Jul	Aug 1-15	Aug 16-31	Sep	Oct	Season	
Days	15	31	30	31	15	16	30	15	183	
Days Active 80% ex	15	31	30	31	15	0	0	0	122	
Accum days	15	46	76	107	122					
Supplied										
mm/day	0.55	2.37	4.97	5.52	4.53	4.53	3.16	0.66		
in/day	0.02	0.09	0.20	0.22	0.18	0.18	0.13	0.03	0.00	
Pdef in/period	0.33	2.93	5.94	6.82	2.71	0.00	0.00	0.00	18.72	
Pdef ft/period	0.03	0.24	0.50	0.57	0.23	0.00	0.00	0.00	1.56	
Pdef ac-ft	1.81	16.10	32.67	37.50	14.89	0.00	0.00	0.00	102.96	
Applic Effic %	0.61	0.61	0.61	0.61	0.61	0.61	0.61	0.61	0.61	
Div. Req't	2.96	26.39	53.56	61.47	24.41	0.00	0.00	0.00	168.79	2.56 af/ac
Full Season										
mm/day	0.55	2.37	4.97	5.52	4.53		3.16	0.66		
in/day	0.02	0.09	0.20	0.22	0.18		0.13	0.03	0.00	
Pdef in/period	0.33	2.93	5.94	6.82	5.59		3.78	0.39	25.78	
Pdef ft/period	0.03	0.24	0.50	0.57	0.47		0.31	0.03	2.15	
Pdef ac-ft	1.81	16.10	32.67	37.50	30.77		20.77	2.17	141.79	
Applic Effic %	0.61	0.61	0.61	0.61	0.61	0.61	0.61	0.61	0.61	
Div. Req't	2.96	26.39	53.56	61.47	50.45		34.05	3.56	232.44	3.52 af/ac

Difference in seasonal CIR and CIR provided under water rights

Number of days active= 122

or

38.82 af

27.4% %


Difference in seasonal diversion req't and diversion requirement provided under water rights

or

63.65 af

27.4% %

Water Right Cutoff Dates Big Wood River
Water Right Priority 3/24/1883



Big Wood River Water Right 3/24/1883

Days in Priority

<i>Point</i>	<i>Row1</i>	<i>Rank</i>	<i>Percent</i>			
1	182	1	28.50%	0.715		
3	182	1	28.50%	0.715		
4	182	1	28.50%	0.715		
5	182	1	28.50%	0.715		
6	182	1	28.50%	0.715		
7	182	1	28.50%	0.715		
8	182	1	28.50%	0.715		
9	182	1	28.50%	0.715		
10	182	1	28.50%	0.715		
11	182	1	28.50%	0.715		
12	182	1	28.50%	0.715		
15	182	1	28.50%	0.715		
16	182	1	28.50%	0.715		
17	182	1	28.50%	0.715		
18	182	1	28.50%	0.715		
20	182	1	28.50%	0.715		
21	182	1	28.50%	0.715		
22	182	1	28.50%	0.715		
23	182	1	28.50%	0.715		
24	182	1	28.50%	0.715		
25	182	1	28.50%	0.715		
27	182	1	28.50%	0.715		
28	182	1	28.50%	0.715		
29	182	1	28.50%	0.715		
30	182	1	28.50%	0.715		
31	182	1	28.50%	0.715		
33	182	1	28.50%	0.715		
34	182	1	28.50%	0.715		
35	182	1	28.50%	0.715		
36	182	1	28.50%	0.715		
37	182	1	28.50%	0.715		
38	182	1	28.50%	0.715		
39	182	1	28.50%	0.715		
42	182	1	28.50%	0.715		
43	182	1	28.50%	0.715		
46	182	1	28.50%	0.715		
48	182	1	28.50%	0.715		
49	182	1	28.50%	0.715		
50	182	1	28.50%	0.715		
51	182	1	28.50%	0.715		
52	182	1	28.50%	0.715		
40	149	42	26.70%	0.733		
19	147	43	25.00%	0.75		
2	143	44	21.40%	0.786		
26	143	44	21.40%	0.786		
55	136	46	19.60%	0.804	136 days=20%	
56	135	47	17.80%	0.822	or 80% of years	
57	134	48	16.00%	0.84	water is on 136 days	15-Aug
44	133	49	14.20%	0.858		
13	130	50	12.50%	0.875		
32	129	51	10.70%	0.893	128 days =10%	
41	123	52	7.10%	0.929	or 90% of years	
53	123	52	7.10%	0.929	water is on 128 days	8-Aug
54	120	54	5.30%	0.947	120 days =5%	
14	115	55	3.50%	0.965	or 95% of years	
45	104	56	1.70%	0.983	water is on 120 days	30-Jul
47	91	57	0.00%	1		
mean	166.965					

Big Wood River above Magic Reservoir Water Rights Cutoff Data										WRPRIOR2(REVISED2004).XLS																									
SUPPLIED BY WATERMASTER DISTRICT 37																																			
PREPARED BY C.E. BROCKWAY P.E.																																			
MO	DAY	YR	1948	1949	1950	1951	1952	1953	1954	1955	1956	1957	1958	1959	1960	1961	1962	1963	1964	1965	1966	1967	1968	1969	1970	1971	1972	1973	1974	1975	1976	1977	1978	1979	1980

ET Idaho --- Evapotranspiration and Consumptive Irrigation Water Requirements for Idaho

Hailey Ranger Stn (NWS NOAA--103942)

Statistics based on 30 years between 1947 to 1981

Open water - shallow systems (ponds, streams)

Potential Evapotranspiration

	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Growing Season ^a	Annual
Mean	mm/day												mm	
Monthly ^b	0.41	0.72	1.2	2.32	3.28	3.77	4.28	3.8	2.78	1.71	0.85	0.33	779	770
15-Day Moving Average ^c	0.4	0.71	1.18	2.35	3.27	3.75	4.25	3.81	2.75	1.7	0.82	0.33		
7-Day Moving Average ^d	0.41	0.72	1.2	2.32	3.28	3.75	4.28	3.8	2.77	1.71	0.83	0.33		
3-Day Moving Average ^e	0.41	0.72	1.2	2.32	3.28	3.76	4.27	3.8	2.76	1.71	0.84	0.33		
Standard Deviation	mm/day												mm	
Monthly	0.1	0.07	0.16	0.28	0.47	0.32	0.28	0.28	0.23	0.3	0.11	0.06	26	26
15-Day Moving Average	0.08	0.08	0.16	0.36	0.45	0.45	0.23	0.31	0.34	0.28	0.15	0.07		
7-Day Moving Average	0.11	0.13	0.22	0.48	0.61	0.58	0.28	0.36	0.45	0.4	0.2	0.08		
3-Day Moving Average	0.14	0.17	0.28	0.59	0.74	0.71	0.4	0.48	0.54	0.5	0.24	0.11		
20% Exceedance	mm/day												mm	
Monthly	0.44	0.78	1.23	2.5	3.48	3.98	4.41	3.95	2.96	1.86	0.73	0.38	798	798
15-Day Moving Average	0.53	0.86	1.45	2.96	3.95	4.3	4.58	4.21	3.21	2.15	0.82	0.41		
7-Day Moving Average	0.65	1	1.64	3.18	4.23	4.64	4.75	4.38	3.58	2.51	1.08	0.52		
3-Day Moving Average	0.76	1.13	2.03	3.6	4.64	4.98	4.98	4.55	3.74	2.7	1.18	0.58		
80% Exceedance	mm/day												mm	
Monthly	0.38	0.68	1.12	2.15	2.98	3.48	4.07	3.88	2.95	1.51	0.55	0.28	744	744
15-Day Moving Average	0.27	0.58	0.95	1.78	2.58	2.98	3.83	3.24	2.05	1.14	0.42	0.24		
7-Day Moving Average	0.22	0.48	0.81	1.55	2.04	2.53	3.81	2.88	1.74	0.91	0.35	0.18		
3-Day Moving Average	0.11	0.37	0.62	1.28	1.87	2.28	3.22	2.5	1.57	0.78	0.24	0.08		
Ave Highest ET	mm/day												--	
15-Day Moving Average ^f	0.47	0.8	1.38	2.62	3.83	4.11	4.44	4.08	3.08	2.01	0.78	0.38		
7-Day Moving Average ^g	0.56	0.91	1.54	2.92	4.02	4.44	4.81	4.27	3.38	2.27	0.92	0.44		
3-Day Moving Average ^h	0.67	1.01	1.78	3.23	4.33	4.78	4.85	4.47	3.62	2.51	1.08	0.51		
Ave Lowest ET	mm/day												--	
15-Day Moving Average ⁱ	0.34	0.64	1.03	2.05	2.88	3.38	4.13	3.52	2.46	1.41	0.51	0.28		
7-Day Moving Average ^j	0.28	0.55	0.91	1.74	2.43	2.98	3.8	3.24	2.25	1.18	0.44	0.23		
3-Day Moving Average ^k	0.18	0.44	0.75	1.44	2.05	2.8	3.51	2.88	1.91	0.95	0.33	0.15		
Special normal distribution parameters for monthly, seasonal, and annual intervals														
Skew	0.04	-0.23	0.35	-0.48	0.04	0.78	-0.07	-0.45	-0.57	0.07	0.21	0.18	-0.15	-0.15
Kurtosis	0.81	2.71	0.85	3.81	0.84	3.95	0.81	1.28	3.17	0.88	2.88	0.88	2.34	2.34

^a Growing Season: This is usually the time from green up or planting in the spring to a killing frost or harvest in the fall. It is not applicable for entries without a growing season and will be blank.

^b Mean of the average daily value for month

^c Mean of the fourteen 15-day period averages contained in the month

^d Mean of the twenty three 7-day period averages contained in the month

^e Mean of the twenty seven 3-day period averages contained in the month

^f Mean of the highest/lowest 15-day period average in month

^g Mean of the highest/lowest 7-day period average in month

^h Mean of the highest/lowest 3-day period average in month

Appendix C

Water Requirements and Aquifer Water Balance

Valley Club Homeowners Association

Seasonal Aquifer Mitigation

Weather Station	Hailey	Data from	ET Idaho	Allen 2007
Number of lots	99			Infiltration System
Acres/lot irrigated	0.4 acres			No of ponds
Total irrigated acres	39.6 acres			Pond size I L
				W
				Area
				Total area

Infiltration rate 1.50 ft/day


	Turf(lawns)				Pot Et	Potential Evapotranspiration									
Month	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Growing	Annual	
mm/day	0.22	0.38	0.59	1.07	3.06	5.11	5.75	5	3.24	1.15	0.32	0.19	685	813	
in/day	0.01	0.02	0.02	0.04	0.12	0.20	0.23	0.20	0.13	0.05	0.01	0.01	27.29	32.39	
Pot ET in/mo	0.27	0.42	0.73	1.28	3.78	6.11	7.10	6.18	3.87	1.42	0.38	0.23	27.29	32.39	
Pot ET ft/mo	0.02	0.04	0.06	0.11	0.31	0.51	0.59	0.51	0.32	0.12	0.03	0.02	2.27	2.70	
Pot ET ac-ft	0.90	1.40	2.40	4.22	12.47	20.15	23.44	20.38	12.78	4.69	1.26	0.77	90.06	106.89	

	Turf(lawns)				Pdef	Net Irrigation water requirement (CIR)										
Month	Jan	Feb	Mar	Apr	May	Jun	Jul	Aug	Sep	Oct	Nov	Dec	Growing	Annual		
mm/day	0.02	0.13	0.21	0.47	2.02	4.04	5.42	4.49	2.69	0.6	-0.26	-0.05	574	620		
in/day	0.00	0.01	0.01	0.02	0.08	0.16	0.22	0.18	0.11	0.02	-0.01	0.00	22.87	24.70		
Pdef in/mo	0.02	0.15	0.26	0.56	2.49	4.83	6.69	5.55	3.22	0.74	-0.31	-0.06	22.87	24.70		
Pdef ft/mo	0.00	0.01	0.02	0.05	0.21	0.40	0.56	0.46	0.27	0.06	-0.03	-0.01	1.91	2.06		
Pdef ac-ft	0.08	0.48	0.86	1.85	8.23	15.93	22.09	18.30	10.61	2.45	-1.03	-0.20	75.47	81.51		


Average year

Month	Apr	May	Jun	Jul	Aug	Sep	Oct	Season	
Days	15	31	30	31	31	30	15	183	Full season
Aquifer Pumping									
Pdef (CIR)ac ft/period	0.9	8.2	15.9	22.1	18.3	10.6	1.2	77.3 af	
Irrig. Efficiency	0.56	0.56	0.56	0.56	0.56	0.56	0.56	0.56	
Req'd Div ac ft	1.7	14.7	28.5	39.4	32.7	18.9	2.2	138.1 af or	3.5 af/acre diversion
Accum. Diversion	1.7	16.4	44.8	84.3	116.9	135.9	138.1	af	
Avg daily cfs	0.06	0.24	0.48	0.64	0.53	0.32	0.07	0.38 cfs or	
Infiltration									
Volume infiltrated*	13.56	28.02	27.12	28.02	28.02	13.56		138.3 af*	* Water right in priority until Sept 15=153 days
Daily avg cfs	0.457	0.457	0.457	0.457	0.457	0.228			
Accumulated infilt.	13.6	41.6	68.7	96.7	124.7	138.3	138.3		
Pond Evap									
Pond Evap mm/day	2.32	3.28	3.77	4.26	3.8	2.78	1.71		
Pond Evap in/day	0.092	0.131	0.150	0.170	0.151	0.111	0.068		Open water evap- Allen 2007
Pond Evap ac ft/period	0.07	0.20	0.23	0.26	0.24	0.17	0.05	1.22 ac ft	
Pond Evap cfs	0.002	0.003	0.004	0.004	0.004	0.003	0.002		
								139.5 ac ft	Total infiltration +pond evap
Infiltration +Pond Evap									
Avg total daily cfs	0.46	0.46	0.46	0.46	0.46	0.23	0.00	0.46 cfs or	206.7 gpm
Volume total af	13.63	28.23	27.34	28.29	28.26	13.73	0.05	139.52	
Accumulated vol	13.63	41.85	69.20	97.48	125.74	139.47	139.52		
Excess(infil-div)	11.90	13.32	-1.34	-11.43	-4.66	-5.39	-2.18	0.23 af	
Excess accumulated	11.90	25.22	23.89	12.46	7.80	2.42	0.23		

Valley Club Homeowners Mitigation Plan Additional Irrigation and Extended Season Full Buildout



Valley Club Homeowners Aquifer Balance



Appendix D
Hiawatha Canal Data

CONVEYANCE LOSS - WORSTELL

NAME OF DITCH: Hiawatha Ditch BY: adm DATE: 02/05/01

REACH	LENGTH (FT)	AVE WIDTH (FT)	SEEPAGE (FT/DAY)	WORSTELL LOSS (CFS)	DELIVERY (CFS)	DELIVERY LEFT (CFS)	LOSS FACTOR	DELIVERY LOSS (CFS)	FLOW (CFS)	DELIVERY LOSS MINUS HIAWATHA RIGHTS FOR LOSS
Decree	900	24.0	10.00	2.73	0.00	29.99	0.0910	0.00	37.54	0.00
1	1910	18.0	3.00	1.30	6.88	29.99	0.0434	0.92	34.81	0.42
2	450	18.0	3.00	0.31	0.04	23.11	0.0133	0.01	26.63	0.00
3	480	18.0	3.00	0.33	0.02	23.07	0.0142	0.00	26.28	0.00
4	430	18.0	3.00	0.29	0.02	23.05	0.0127	0.00	25.94	0.00
5	1770	15.0	0.00	0.00	2.02	23.03	0.0000	0.35	25.62	0.16
6	730	15.0	0.00	0.00	1.45	21.01	0.0000	0.25	23.60	0.11
7	490	15.0	0.00	0.00	0.05	19.56	0.0000	0.01	22.15	0.00
8	1820	15.0	0.00	0.00	0.00	19.51	0.0000	0.00	22.10	0.00
9	1470	15.0	1.50	0.42	0.62	19.51	0.0214	0.12	22.10	0.05
10	4500	14.0	1.28	1.02	0.24	18.90	0.0539	0.06	21.07	0.03
11	680	12.0	1.00	0.10	2.17	18.66	0.0055	0.55	19.81	0.25
12	970	12.0	1.00	0.15	0.04	16.49	0.0089	0.01	17.54	0.00
13	350	12.0	1.00	0.05	0.13	16.45	0.0032	0.04	17.35	0.02
14	440	12.0	1.00	0.07	0.66	16.31	0.0041	0.18	17.16	0.08
15	1860	12.0	1.00	0.28	1.44	15.65	0.0180	0.42	16.43	0.19
16	530	12.0	1.00	0.08	0.82	14.21	0.0057	0.24	14.71	0.11
17	490	12.0	1.00	0.07	0.68	13.39	0.0055	0.20	13.81	0.09
18	460	12.0	1.00	0.07	0.00	12.71	0.0055	0.00	13.06	0.00
19	820	10.0	1.00	0.10	1.10	12.71	0.0082	0.35	12.99	0.16
20	650	7.0	0.66	0.04	1.55	11.61	0.0033	0.49	11.78	0.22
21	1260	4.0	0.66	0.04	0.20	10.06	0.0042	0.06	10.20	0.03
22	2900	4.0	0.66	0.10	2.86	9.86	0.0098	0.95	9.95	0.43
23	1	4.0	0.66	0.00	7.00	7.00	0.0000	2.32	7.00	1.05
TOTALS	26361			7.55	29.99		0.2409	7.55		3.41

loss after move of
4.0 from #18 to #1

Net contribution after move:
 $0.42 - 0.17 = 0.25$

0.5 cfs required to mitigate
removal of rights.

$\Rightarrow 0.25$ required to remain
in canal to make up
deficit

or

REACH = SECTION OF CHANNEL
LENGTH = LENGTH OF REACH, THE CHANNEL CAN BE DIVIDED INTO EQUAL LENGTH REACHES
OR ACTUAL LENGTHS BETWEEN DELIVERY POINTS
AVE WIDTH = AVERAGE TOP WIDTH OF WATER SURFACE IN REACH
SEEPAGE = SOIL SEEPAGE RATE OF REACH
WORSTELL LOSS = CONVEYANCE LOSS IN REACH BASED ON WORSTELL METHOD
DELIVERY = TOTAL DELIVERIES IN REACH
DELIVERY LEFT = SUM(DELIVERIES OF CURRENT AND REMAINING REACHES)
LOSS FACTOR = WORSTELL LOSS/DELIVERY LEFT
DELIVERY LOSS = SUM(LOSS FACTORS OF CURRENT AND PREVIOUS REACHES) X DELIVERY;
REPRESENTS THE LOSSES ASSIGNED TO THE DELIVERIES IN THE REACH;
IF MULTIPLE RIGHTS WITHIN REACH, DELIVERY LOSSES SHOULD BE
PRORATED BASED ON SIZE OF DELIVERY FOR EACH RIGHT WITHIN REACH
FLOW = TOTAL FLOW AT BEGINNING OF EACH REACH

AS per
Calculations
on
1991 Hiawatha
Transfer

Before move share of loss:

$$\frac{4.00}{4.00} \times 0.498 = 0.498 \text{ cfs}$$

After move share of loss:

$$\frac{4.00}{6.88} \times 0.42 = 0.244 \text{ cfs}$$

$$\Rightarrow \text{Impact due to change} = 0.498 - 0.244 = 0.254 \text{ cfs}$$

CONVEYANCE LOSS - WORSTELL

NAME OF DITCH: Hiawatha Ditch BY: adm DATE: 02/05/01

REACH	LENGTH (FT)	AVE WIDTH (FT)	SEEPAGE (FT/DAY)	WORSTELL LOSS (CFS)	DELIVERY (CFS)	DELIVERY LEFT (CFS)	LOSS FACTOR	DELIVERY LOSS (CFS)	FLOW (CFS)	DELIVERY LOSS MINUS HIAWATHA RIGHTS FOR LOSS
Decree	900	24.0	10.00	2.73	0.00	29.99	0.0910	0.00	39.16	0.00
1	1910	18.0	3.00	1.30	6.88	29.99	0.0434	0.92	36.43	0.51
2	450	18.0	3.00	0.31	0.04	23.11	0.0133	0.01	28.25	0.00
3	480	18.0	3.00	0.33	0.02	23.07	0.0142	0.00	27.90	0.00
4	430	18.0	3.00	0.29	0.02	23.05	0.0127	0.00	27.56	0.00
5	1770	15.0	2.25	0.75	2.02	23.03	0.0328	0.42	27.24	0.23
6	730	15.0	1.50	0.21	1.45	21.01	0.0099	0.32	24.47	0.17
7	490	15.0	1.50	0.14	0.05	19.56	0.0071	0.01	22.81	0.01
8	1820	15.0	1.50	0.52	0.00	19.51	0.0265	0.00	22.62	0.00
9	1470	15.0	1.50	0.42	0.62	19.51	0.0214	0.17	22.10	0.09
10	4500	14.0	1.28	1.02	0.24	18.90	0.0539	0.08	21.07	0.04
11	680	12.0	1.00	0.10	2.17	18.66	0.0055	0.72	19.81	0.39
12	970	12.0	1.00	0.15	0.04	16.49	0.0089	0.01	17.54	0.01
13	350	12.0	1.00	0.05	0.13	16.45	0.0032	0.05	17.35	0.03
14	440	12.0	1.00	0.07	0.66	16.31	0.0041	0.23	17.16	0.13
15	1860	12.0	1.00	0.28	1.44	15.65	0.0180	0.53	16.43	0.29
16	530	12.0	1.00	0.08	0.82	14.21	0.0057	0.30	14.71	0.17
17	490	12.0	1.00	0.07	0.68	13.39	0.0055	0.26	13.81	0.14
18	460	12.0	1.00	0.07	0.00	12.71	0.0055	0.00	13.06	0.00
19	820	10.0	1.00	0.10	1.10	12.71	0.0082	0.43	12.99	0.24
20	650	7.0	0.66	0.04	1.55	11.61	0.0033	0.61	11.78	0.33
21	1260	4.0	0.66	0.04	0.20	10.06	0.0042	0.08	10.20	0.04
22	2900	4.0	0.66	0.10	2.86	9.86	0.0098	1.17	9.95	0.64
23	1	4.0	0.66	0.00	7.00	7.00	0.0000	2.86	7.00	1.57
TOTALS	26361			9.17	29.99		0.3171	9.17		5.03

loss after moving 4.0
from #18 to #1
Net contribution after move =
 $0.51 - 0.21 = 0.30$
0.75 cfs req'd to mitigate
removal
 $\Rightarrow$ 0.45 cfs req'd to
remain in canal to
make up deficit

REACH = SECTION OF CHANNEL
LENGTH = LENGTH OF REACH, THE CHANNEL CAN BE DIVIDED INTO EQUAL LENGTH REACHES
OR ACTUAL LENGTHS BETWEEN DELIVERY POINTS
AVE WIDTH = AVERAGE TOP WIDTH OF WATER SURFACE IN REACH
SEEPAGE = SOIL SEEPAGE RATE OF REACH
WORSTELL LOSS = CONVEYANCE LOSS IN REACH BASED ON WORSTELL METHOD
DELIVERY = TOTAL DELIVERIES IN REACH
DELIVERY LEFT = SUM(DELIVERIES OF CURRENT AND REMAINING REACHES)
LOSS FACTOR = WORSTELL LOSS/DELIVERY LEFT
DELIVERY LOSS = SUM(LOSS FACTORS OF CURRENT AND PREVIOUS REACHES) X DELIVERY;
REPRESENTS THE LOSSES ASSIGNED TO THE DELIVERIES IN THE REACH;
IF MULTIPLE RIGHTS WITHIN REACH, DELIVERY LOSSES SHOULD BE
PRORATED BASED ON SIZE OF DELIVERY FOR EACH RIGHT WITHIN REACH
FLOW = TOTAL FLOW AT BEGINNING OF EACH REACH

CONVEYANCE LOSS - WORSTELL

02/05/01

DATE:

adm

BY:

Hiawatha Ditch

NAME OF DITCH:

REACH	LENGTH (FT)	AVE WIDTH (FT)	SEEPAGE (FT/DAY)	WORSTELL LOSS (CFS)	DELIVERY (CFS)	DELIVERY LEFT (CFS)	LOSS FACTOR	DELIVERY LOSS (CFS)	FLOW (CFS)	DELIVERY LOSS MINUS HIAWATHA RIGHTS FOR LOSS
Decree	900	24.0	10.00	2.73	0.00	29.99	0.0910	0.00	37.54	0.00
1	1910	18.0	3.00	1.30	2.88	29.99	0.0434	0.39	34.81	0.17
2	450	18.0	3.00	0.31	0.04	27.11	0.0113	0.01	30.63	0.00
3	480	18.0	3.00	0.33	0.02	27.07	0.0121	0.00	30.28	0.00
4	430	18.0	3.00	0.29	0.02	27.05	0.0108	0.00	29.94	0.00
5	1770	15.0	0.00	0.00	2.02	27.03	0.0000	0.34	29.62	0.15
6	730	15.0	0.00	0.00	1.45	25.01	0.0000	0.24	27.60	0.11
7	490	15.0	0.00	0.00	0.05	23.56	0.0000	0.00	26.15	0.00
8	1820	15.0	0.00	0.00	0.00	23.51	0.0000	0.00	26.10	0.00
9	1470	15.0	1.50	0.42	0.62	23.51	0.0178	0.11	26.10	0.05
10	4500	14.0	1.28	1.02	0.24	22.90	0.0445	0.06	25.07	0.03
11	680	12.0	1.00	0.10	2.17	22.66	0.0046	0.51	23.81	0.23
12	970	12.0	1.00	0.15	0.04	20.49	0.0072	0.01	21.54	0.00
13	350	12.0	1.00	0.05	0.13	20.45	0.0026	0.03	21.35	0.01
14	440	12.0	1.00	0.07	0.66	20.31	0.0033	0.16	21.16	0.07
15	1860	12.0	1.00	0.28	1.44	19.65	0.0144	0.38	20.43	0.17
16	530	12.0	1.00	0.08	0.82	18.21	0.0044	0.18	18.71	0.10
17	490	12.0	1.00	0.07	0.68	17.39	0.0043	0.22	17.81	0.08
18	460	12.0	1.00	0.07	4.00	16.71	0.0042	1.10	17.06	0.50
19	820	10.0	1.00	0.10	1.19	12.71	0.0082	0.31	12.99	0.14
20	650	7.0	0.66	0.04	1.55	11.61	0.0033	0.45	11.78	0.20
21	1260	4.0	0.66	0.04	0.20	10.06	0.0042	0.06	10.20	0.03
22	2900	4.0	0.66	0.10	2.86	9.86	0.0098	0.86	9.95	0.39
23	1	4.0	0.66	0.00	7.00	7.00	0.0000	2.11	7.00	0.95
TOTALS	26361			7.55	29.99		0.2102	7.55		3.41

Contribution before move

loss needed to remain in this section to mitigate removal of rights from reach

Reflects loss loss due to lining #5-#8

REACH = SECTION OF CHANNEL

LENGTH = LENGTH OF REACH, THE CHANNEL CAN BE DIVIDED INTO EQUAL LENGTH REACHES OR ACTUAL LENGTHS BETWEEN DELIVERY POINTS

AVE WIDTH = AVERAGE TOP WIDTH OF WATER SURFACE IN REACH

SEEPAGE = SOIL SEEPAGE RATE OF REACH

WORSTELL LOSS = CONVEYANCE LOSS IN REACH BASED ON WORSTELL METHOD

DELIVERY = TOTAL DELIVERIES IN REACH

DELIVERY LEFT = SUM(DELIVERIES OF CURRENT AND REMAINING REACHES)

LOSS FACTOR = WORSTELL LOSS/DELIVERY LEFT

DELIVERY LOSS = SUM(LOSS FACTORS OF CURRENT AND PREVIOUS REACHES) X DELIVERY;

REPRESENTS THE LOSSES ASSIGNED TO THE DELIVERIES IN THE REACH;

IF MULTIPLE RIGHTS WITHIN REACH, DELIVERY LOSSES SHOULD BE

PRORATED BASED ON SIZE OF DELIVERY FOR EACH RIGHT WITHIN REACH

FLOW = TOTAL FLOW AT BEGINNING OF EACH REACH

Prior to installation of membrane lining

CONVEYANCE LOSS - WORSTELL

NAME OF DITCH: Hiawatha Ditch BY: adm DATE: 02/05/01

REACH	LENGTH (FT)	AVE WIDTH (FT)	SEEPAGE (FT/DAY)	WORSTELL LOSS (CFS)	DELIVERY (CFS)	DELIVERY LEFT (CFS)	LOSS FACTOR	DELIVERY LOSS (CFS)	FLOW (CFS)	DELIVERY LOSS MINUS HIAWATHA RIGHTS FOR LOSS
Decree	900	24.0	10.00	2.73	0.00	29.99	0.0910	0.00	39.16	0.00
1	1910	18.0	3.00	1.30	2.86	29.99	0.0434	0.39	36.43	0.21
2	450	18.0	3.00	0.31	0.04	27.11	0.0113	0.01	32.25	0.00
3	480	18.0	3.00	0.33	0.02	27.07	0.0121	0.00	31.90	0.00
4	430	18.0	3.00	0.29	0.02	27.05	0.0108	0.00	31.56	0.00
5	1770	15.0	2.25	0.75	2.02	27.03	0.0279	0.40	31.24	0.22
6	730	15.0	1.50	0.21	1.45	25.01	0.0083	0.30	28.47	0.16
7	490	15.0	1.50	0.14	0.05	23.56	0.0059	0.01	26.81	0.01
8	1820	15.0	1.50	0.52	0.00	23.51	0.0220	0.00	26.62	0.00
9	1470	15.0	1.50	0.42	0.62	23.51	0.0178	0.15	26.10	0.08
10	4500	14.0	1.28	1.02	0.24	22.90	0.0445	0.07	25.07	0.04
11	680	12.0	1.00	0.10	2.17	22.66	0.0046	0.65	23.81	0.36
12	970	12.0	1.00	0.15	0.04	20.49	0.0072	0.01	21.54	0.01
13	350	12.0	1.00	0.05	0.13	20.45	0.0026	0.04	21.35	0.02
14	440	12.0	1.00	0.07	0.66	20.31	0.0033	0.21	21.16	0.11
15	1860	12.0	1.00	0.28	1.44	19.65	0.0144	0.47	20.43	0.26
16	530	12.0	1.00	0.08	0.82	18.21	0.0044	0.27	18.71	0.15
17	490	12.0	1.00	0.07	0.68	17.39	0.0043	0.23	17.81	0.13
18	460	12.0	1.00	0.07	4.00	16.71	0.0042	1.36	17.06	0.75
19	820	10.0	1.00	0.10	1.10	12.71	0.0082	0.38	12.99	0.21
20	650	7.0	0.66	0.04	1.55	11.61	0.0033	0.54	11.78	0.30
21	1260	4.0	0.66	0.04	0.20	10.06	0.0042	0.07	10.20	0.04
22	2900	4.0	0.66	0.10	2.86	9.86	0.0098	1.04	9.95	0.57
23	1	4.0	0.66	0.00	7.00	7.00	0.0000	2.56	7.00	1.40
TOTALS	26361			9.17	29.99		0.2743	9.17		5.03

← Contribution before move

← loss needed to remain in
Hiawatha to mitigate removal
of rights from canal

REACH = SECTION OF CHANNEL

LENGTH = LENGTH OF REACH, THE CHANNEL CAN BE DIVIDED INTO EQUAL LENGTH REACHES
OR ACTUAL LENGTHS BETWEEN DELIVERY POINTS

AVE WIDTH = AVERAGE TOP WIDTH OF WATER SURFACE IN REACH

SEEPAGE = SOIL SEEPAGE RATE OF REACH

WORSTELL LOSS = CONVEYANCE LOSS IN REACH BASED ON WORSTELL METHOD

DELIVERY = TOTAL DELIVERIES IN REACH

DELIVERY LEFT = SUM(DELIVERIES OF CURRENT AND REMAINING REACHES)

LOSS FACTOR = WORSTELL LOSS/DELIVERY LEFT

DELIVERY LOSS = SUM(LOSS FACTORS OF CURRENT AND PREVIOUS REACHES) X DELIVERY;

REPRESENTS THE LOSSES ASSIGNED TO THE DELIVERIES IN THE REACH;

IF MULTIPLE RIGHTS WITHIN REACH, DELIVERY LOSSES SHOULD BE

PRORATED BASED ON SIZE OF DELIVERY FOR EACH RIGHT WITHIN REACH

FLOW = TOTAL FLOW AT BEGINNING OF EACH REACH

Appendix E
Permissible Place Of Use



**VALLEY CLUB HOME OWNERS ASSOCIATION
VALLEY CLUB AND CUTTERS LOCATIONS
T.02N, 03N R.18E BLAINE COUNTY, ID
2006 NAIP AERIAL PHOTOGRAPH**



BROCKWAY ENGINEERING, PLLC
ZL- 3/21/08

0 1,500 3,000 6,000 Feet

F:\Projects\Valley Club H.O.A\ARC\VIEW\Valley Club and Cutters Transfer OLD AND NEW POU Map 8_8_07.mxd

Legend

- | | |
|---------------------|-----------------------------|
| Cutter Split | Valley Club P.O.A. PPU |
| Acres_to | 37-21130, 37-21137, 37-2139 |
| Cutters Retain | Parcels |
| Valley Club HOA | sections |
| | tandr |
| | Ponds |
| | Lot_Lines |




**VALLEY CLUB HOME OWNERS ASSOCIATION-
PROPOSED PLACE OF USE
T.03N R.18E. BLAINE COUNTY, ID
2006 AERIAL PHOTOGRAPHS**

1 inch = 700 FT
0 350 700 1,400 Feet
BROCKWAY ENGINEERING, PLLC.
ZL - 3/21/08

Legend
Valley Club H.O.A. PPU QQ = 221.7
Section_Lines
T03N18E





VALLEY CLUB PROPERTY OWNERS ASSOCIATION
CUTTERS AREA TO BE DRIED UP
WATER RIGHTS 37-21130, 37-21137, 37-21139
2006 NAIP AERIAL

0 200 400 800 Feet

BROCKWAY ENGINEERING, PLLC
 ALR (ZL) - 3/21/08

F:\Projects\Valley Club H.O.A\ARCV IEW 9\Cutter Split Map.mxd

Legend

- IDWR REC. POU 37-21130, 21137, 21139
- Cutter Split
- Acres_to
- Cutters Retain 6 ac.
- Valley Club HOA 60 ac. or Dry Up Area
- Ponds
- Lot_Lines
- Street_Centerlines
- Water
- t02n18e

Appendix F
Water Right Purchase Agreement

**AGREEMENT FOR PURCHASE AND SALE
OF
WATER RIGHTS**

THIS AGREEMENT is made this 11th day of MAY, 2007, by and between OLD CUTTERS, INC., an Idaho corporation, whose address is P.O. Box 4944, Ketchum, Idaho, 83340 (hereinafter "Seller") and DRY LOT, LLC., an Idaho limited liability company, whose address is c/o Woody Friedlander, 116 Valley Club Dr., Hailey, Idaho 83333 (hereinafter "Buyer").

RECITALS

A. Seller is the owner and holder of Water Rights Nos. 37-21130, 37-21137 and 37-21139 as currently recommended in the Director's Report for Basin 37 Part 3 filed in *In Re the General Adjudication of Rights to the Use of Water from the Snake River Basin Water System*, Twin Falls County District Court Civil No. 39576 (the "SRBA"), which entitle Seller to irrigate sixty-six (66) acres of land on Seller's property within the City of Hailey described in **Exhibit A** attached hereto (the "Seller's Property") with 4.0 cubic feet per second ("cfs") of water from the Big Wood River via the Hiawatha Canal, with a priority date of March 24, 1883 (the "Seller Water Rights").

B. Buyer is an Idaho limited liability company whose members own real property situated in Blaine County, Idaho, located in the following subdivision ("Subdivision"):

Lots 1 through 99 of The Valley Club, a planned unit development created by the Official Plat filed as Instrument No. 36515 in the records of Blaine County, Idaho on May 5, 1994.

(hereinafter referred to as the "Buyer's Property").

C. Buyer desires to purchase from Seller a portion of the Seller's Water Rights used to irrigate sixty (60) acres of the Seller's Property (the "Water Rights"), and Sellers are willing to sell the Water Rights to Buyer, subject to approval by the Idaho Department of Water Resources (hereinafter referred to as the "Department") of: 1) the Buyer's application for permit to divert ground water from the two (2) wells which are part of its public water supply system and to irrigate sixty (60) acres of the Buyer's Property and other land located in the Subdivision, using the Water Rights for mitigation; and 2) any other applications for permit or transfer required by the Department to fulfill the purpose and use identified in C.1 (the "Applications"); and to all other terms and conditions hereinafter set forth.

TERMS AND CONDITIONS

1. **INCORPORATION OF RECITALS.** The Recitals set forth above are an integral part of this Agreement and are fully incorporated herein by this reference.

2. **SALE.** The Seller, for and in consideration of the payments to be made and the covenants and conditions to be kept and performed by the Buyer, as hereinafter set forth, does hereby contract and agree to sell and convey to Buyer, and the Buyer does hereby agree to buy from the Seller, the Water Rights.

3. **PURCHASE PRICE AND TERMS OF PAYMENT.** The total purchase price of the

Water Rights shall be One Million Eight Hundred Thousand Dollars (\$1,800,000). The purchase price shall be paid as follows:

a. Earnest Money. Within three (3) business days of the mutual execution of this Agreement by Seller and Buyer, Buyer shall deposit into escrow with Sun Valley Title Company (the "Closing Agent") the sum of One Hundred Thousand Dollars (\$100,000) to be held as earnest money and applied to the purchase price at the Closing.

b. Cash Payment. The balance of the purchase price shall be delivered to the Closing Agent in immediately available funds not less than one (1) business day prior to the Closing.

4. TITLE; QUITCLAIM DEED. Seller shall transfer all of its right, title and interest in and to the Water Rights to Buyer by quitclaim deed (the "Quitclaim Deed"). Buyer may submit to the Department as a part of its Application a copy of this Agreement with the purchase price redacted.

5. FILING AND APPROVAL OF APPLICATION. Within twenty (90) days of the date of execution of this Agreement, Buyer shall file the Applications with the Department and thereafter diligently pursue its approval. This Agreement for purchase and sale of the Water Rights is contingent upon and subject to approval by the Department of the Applications within two hundred and seventy (270) days of the date of execution of this Agreement, for the irrigation of not less than fifty (50) acres of the Buyer's Property and other land located in the Subdivision using the Water Rights as mitigation. Upon such approval(s) the earnest money shall become non-refundable. If the Applications are not so approved by the Department within this time period, the Buyer will have the option to tender an additional \$50,000 in earnest money to give the Department an additional ninety (90) days for approval of the Applications. If the Applications are not so approved by the Department after the additional 90 day extension, this Agreement shall become null and void, and the earnest money shall be returned to Buyer, unless the parties hereto agree to extend the time for Buyer to obtain approval of the Applications by the Department. In the event the Department approves the Applications for the irrigation of less than fifty (50) acres of the Buyer's Property and other land located in the Subdivision, Buyer may waive the above contingency and proceed with the Closing at its discretion.

6. COOPERATION WITH APPLICATIONS EFFORTS. Seller hereby grants to Buyer permission to make the Applications and agrees to sign any documentation to that effect required by the Department pertaining to the Applications. At Buyer's request, Seller shall cooperate with Buyer in Buyer's pursuit of the Applications, and shall provide Buyer with any information that Seller has concerning the Water Rights that Buyer may reasonably request in pursuit of the approval of the Applications, including historical water use records.

7. CLOSING. The closing of this transaction and the delivery of the executed Quitclaim Deed to Buyer and the entire purchase price to Sellers shall take place at the offices of the Closing Agent, within ten (10) days of the date the final order(s) by the Department approving the Applications becomes non-appealable (the "Closing Date").

8. POSSESSION; PRORATIONS. The Buyer shall be given possession and use of the Water Rights on the Closing Date. Taxes and assessments, if any, on the Water Rights shall be prorated as of the Closing Date. The Sellers shall pay all such taxes and assessments which have

accrued prior to the Closing Date and the Buyer shall pay for all subsequent taxes and assessments upon the Water Rights.

9. PROTECTION OF WATER RIGHTS / 2007 IRRIGATION SEASON. Until final approval of the Applications by the Department, Seller is authorized to continue to use the Water Rights on the authorized place of use for irrigation purposes during the 2007 irrigation season or any time thereafter. However, in the event the Department approves the Applications during the 2007 irrigation season or at any time thereafter, and Closing takes place, Seller shall transfer possession of the Water Rights to Buyer and cease diverting the Water Rights, unless otherwise agreed to by Buyer. If Seller does not intend to use the Water Rights for the 2007 irrigation season, Seller shall notify Buyer and take any actions necessary to protect the Water Rights from a forfeiture finding due to non-use in 2007, including placing the Water Rights in the State Water Supply Bank if necessary.

10. DUTY TO DEFEND WATER RIGHTS IN SRBA. In the event the Applications are not approved by the Department by January 15, 2008, and an objection(s) is filed to the Water Rights' recommendations in the SRBA, Seller shall provide Buyer (and Buyer's attorney) with copies of all objections and shall file the necessary responses and defend the Water Rights in the SRBA. Seller shall consult with Buyer as to any actions taken with respect to the Water Rights in the SRBA. In the event Closing has not occurred and objections to the Water Rights are unresolved, this Agreement is voidable at Buyer's discretion.

11. NO COMMISSIONS. The parties agree that no real estate broker's or other commission shall be paid to anyone as a result of the transfer and sale of the Water Rights from Seller to Buyer pursuant to this Agreement, other than a consulting fee to be paid by the Seller to Matthew Luck.

12. GENERAL PROVISIONS.

a. Severance and Validity. In the event any provision of this Agreement or any part thereof shall be determined by any court of competent jurisdiction to be invalid, void, or otherwise unenforceable, the remaining provisions hereunder, or party thereof, shall remain in fully force and effect, and shall in no way be affected, impaired, or invalidated thereby, it being agreed that such remaining provision shall be construed in a manner most closely approximately the intention of the parties with respect to the invalid, void, or unenforceable provision or part thereof.

b. Attorney Fees. In the event of any suit or proceeding by either party herein against the other party, in any way arising out of this Agreement, or attempting to enforce any right herein granted, the losing party, in such suit or proceeding shall pay to the prevailing party such sum or sums as the court shall adjudge reasonable, in such suit or proceeding, for attorney's fees, including such fees on appeal, for such prevailing party.

c. Governing Law. The validity, meaning and effect of this Agreement shall be determined in accordance with the laws of the State of Idaho applicable to contracts made and performed in that state.

d. Captions to Paragraphs. The captions to the paragraphs of this Agreement are for convenience only and shall not be deemed to enlarge, diminish, explain or in any manner affect the meaning of such paragraphs.

e. Binding Contract. This Agreement shall be binding upon and inure to the benefit of the heirs, personal representative, administrators, successors, and assigns of the parties hereto.

f. Notices. All notices and communications under this Agreement shall be in writing and shall be (i) delivered in person or (ii) mailed, postage prepaid, either by registered or certified mail, return receipt requested, or by overnight express carrier, addressed in each case to the party's address set forth in the introductory paragraph of this Agreement, or (iii) sent by facsimile with the original to follow by mail in the manner described above. It is provided, however, that any party may change its respective address for purposes of receipt of any such communication by giving ten (10) days prior written notice of such change to the other party hereto in the manner provided above. All notices sent pursuant to the terms of this paragraph shall be deemed received (x) if sent by overnight, express carrier, on the next business day immediately following the day sent, (y) if sent by registered or certified mail, on the third business day following the day sent or (z) if sent by facsimile on the date so sent.

IN WITNESS WHEREOF, the parties have caused their names to be subscribed on the dates set forth below.

"SELLER"

OLD CUTTERS, INC.

DATE: 5/9/07

By: J. G. Hill
John Campbell, President

"BUYER"

DRY LOT, LLC

DATE: 5-11-07

By: Danell Rubel

EXHIBIT A

Lots 1A, 2A, 3 and 4, Block 1 of a REPLAT OF DREXLER RANCH SUBDIVISION, BLAINE COUNTY, IDAHO, as shown on the official plat thereof, recorded February 8, 1999, as Instrument No. 423951, records of Blaine County, Idaho; and

A parcel of land within the SW1/4NE1/4, Section 4, T.2N., R.18E., B.M. and also within Lot 4, Buckhorn Subdivision Second Addition, Blaine County, Idaho, more particularly described as follows:

Commencing at a BLM brass cap marking the Southeast Corner of said SW1/4NE1/4, which corner is also the CE 1/16 corner of said Section 4 and which point is the REAL POINT OF BEGINNING:

thence North 89°42'50" West 291.01 feet to the Northwest corner of the Drexler Ranch;

thence North 23°17'51" West 37.31 feet along the centerline of the Hiawatha Canal and along the Southerly boundary of said Lot 4, Buckhorn Subdivision Second Addition;

thence North 89°50'20" East 306.07 feet along a fence to the East boundary of said SW1/4NE1/4, said Section 4;

thence South 0°27'55" West 36.58 feet along said East boundary of the SW1/4NE1/4, Section 4 to the point of beginning, containing 0.24 acres, more or less, also known as Tax Lot 6804.

5000

5-11-07 92-376/1241

PAY TO THE ORDER OF Sun Valley Title Trust Account \$ 100,000.00

One Hundred Thousand, 00/100 DOLLARS

[Signature]

FOR First Bank of Idaho

314 Third Street • Idaho • (208) 338-1320

1:124103760: 3 3300 76311