



11. Map of proposed project: show clearly the proposed point of diversion, place of use, section number, township and range number.



Scale: 2 inches equal ~~xxxx~~ 1320'

BE IT KNOWN that the undersigned hereby makes application for permit to appropriate the public waters of the State of Idaho as herein set forth.

BRUNEAU CATTLE CO.

by 
(Applicant) Eugene C. Davis
President

STATE OF IDAHO
DEPARTMENT OF WATER RESOURCES
BENEFICIAL USE FIELD REPORT

RECEIVED
JAN 17 1988

Department of Water Resources

A. GENERAL INFORMATION


1. Owner: BRUNEAU CATTLE CO. Permit No. 51-7118
Current Address: % EUGENE C. DAVIS, BRUNEAU, ID. 83604 Phone No. 845-2762
2. Accompanied by: EUGENE DAVIS EXAM. DATE: 06/14/88
Address: _____ Phone No. _____
Relationship to Permit Holder: OWNER
3. Source: GROUNDWATER tributary to _____

B. OVERLAP REVIEW

1. Other water rights with same place of use: NONE ☐ Copies Attached
2. Other water rights with same point of diversion: 51-2164 51-7013
☒ Copies Attached ☒ Copies of Field Exam's Attached

C. SYSTEM DESCRIPTION

1. **Diversion System Diagram:** Indicate all major components and distances between components. Indicate weir size/ditch size/pipe i.d. as applicable. ☐ Alternative diagram attached



Scale: 1" = _____

2. ☒ Copy of U.S.G.S. Quadrangle Attached Showing location(s) of point(s) of diversion and place(s) of use (required).
☒ Photo of Diversion and System Attached (required for all but single household domestic groundwater, and stockwater).
☐ Aerial Photo Attached (required for irrigation of 10 acres or more).

RECEIVED
JUL 26 1994

REPORT OF WELL DRILLER
State of Idaho

RECEIVED
JUL 22 1967

Department of Reclamation

State law requires that this report shall be filed with the State Reclamation Engineer within 30 days after completion or abandonment of the well.

WELL OWNER:

Name Davis, Eugene and Skully

Address Bureau, Idaho

51-2164 Ricard 51-7013 (11.8)

Owner's Permit No. 6-112

NATURE OF WORK (check): Replacement well ☐

New well ☒ Deepened ☐ Abandoned ☐

Water is to be used for: Irrigation

METHOD OF CONSTRUCTION: Rotary ☐ Cable ☒

Dug ☐ Other ☐ (explain)

CASING SCHEDULE: Threaded ☐ Welded ☒

16 "Diam. from 0 ft. to 200 ft.

14 "Diam. from 133 ft. to 690 ft.

"Diam. from ft. to ft.

"Diam. from ft. to ft.

Thickness of casing: .350 Material:

Steel ☒ concrete ☐ wood ☐ other ☐

(explain)

PERFORATED? Yes ☐ No ☒ Type of

perforator used:

Size of perforations: " by "

perforations from ft. to ft.

perforations from ft. to ft.

perforations from ft. to ft.

perforations from ft. to ft.

WAS SCREEN INSTALLED? Yes ☐ No ☐

Manufacturer's name

Type Model No.

Diam. Slot size Set from ft. to ft.

Diam. Slot size Set from ft. to ft.

CONSTRUCTION: Well gravel packed? Yes ☐

No ☒ size of gravel Gravel

placed from ft. to ft. Surface seal

provided? Yes ☐ No ☐ To what depth?

 ft. Material used in seal:

Did any strata contain unusable water? Yes ☐

No ☒ type of water:

Depth of strata ft. Method of sealing

strata off:

Surface casing used? Yes ☒ No ☐

Cemented in place? Yes ☒ No ☐

Locate well in section

 Sec. 8

 T. 7 S. 5 E.

 SW

 NW

 NE

 SE

LOCATION OF WELL: County Blaine

 W. Sec. 8 T. 7 S. 5 E.

 NW

 NW

 NW

 NW

Size of drilled hole: 16-13 Total
depth of well: 1500 Standing water
level below ground: Temp.

Fahr. 105 Test delivery: gpm

cfs Pump? ☐ Bail ☐

Size of pump and motor used to make test:

Length of time of test: Hrs. Min.

Drawdown: ft. Artesian pressure: ft.

above land surface 50 GIVE flow 6 cfs

or gpm. Shutoff pressure: Unknown

Controlled by: Valve ☒ Cap ☐ Plug ☐

No control ☐ Does well leak around casing?

Yes ☐ No ☒

DEPTH MATERIAL WATER

FROM TO YES OR NO

FEET FEET

0 690 Clay shale W 50'

690 720 Basalt. Bkls.

720 725 Basalt. Bkls.

725 730 Basalt. Bkls.

730 1135 Comp. shale. Shale formation

1135 1160 Clay rock. Shale

1160 1320 Light. brownish clay sand

1320 1500 Pyritic. Sulfate. Sandstone

1500 Siltstone. Aquifer

Work started:

Work finished:

Well Driller's Statement: This well was

drilled under my supervision and this report

is true to the best of my knowledge.


Name: John K. K. K.

Address: Bureau, Idaho

Signed by:

License No. 401 Date: 7/1/67

Use other side for additional remarks




MISSISSIPPI


JUL 26 1994

FISH RACEWAY.

TOP VIEW



SIDE VIEW



DASH LINES INDICATE
WATER LEVEL


WATER OVER FLOWS INTO NEXT PEN. EACH SECTION OF
4 PENS IS SEPERATED WATER WISE ONCE IT ENTERS THE FIRST
PEN UNTIL IT COMBINES AT THE END.

MAINTENANCE

JUL 26 1994


ACRE FEET CALCULATIONS FOR THE
3 WATER COOLING PONDS.
FOR POND IDENTIFICATION SEE FIELD REPORT FORM

POND A.




$$150' \times 360' \times 4.5' = \frac{243,000 \text{ cuft}}{43,560 \text{ cuft}} = \underline{\underline{5.6 \text{ ACRE FEET}}}$$

POND B



$$150' \times 180' \times 3.5' = \frac{94,500 \text{ cuft}}{43,560 \text{ cuft}} = \underline{\underline{2.17 \text{ ACRE FEET}}}$$

POND C




$$\begin{aligned} \text{SECTION X} \\ 545' \times 4.5' \times 150' &= \frac{367,875 \text{ cuft}}{43,560 \text{ cuft}} = \underline{\underline{8.45 \text{ ACRE FEET}}} \end{aligned}$$

$$\begin{aligned} \text{SECTION Y} \\ \frac{545' \times 4' \times 150'}{2} &= \frac{163,500 \text{ cuft}}{43,560 \text{ cuft}} = \underline{\underline{3.75 \text{ ACRE FEET}}} \end{aligned}$$

$$\text{TOTAL} = \underline{\underline{12.2 \text{ ACRE FEET}}}$$

RECEIVED
JUL 26 1994



BRUNEAU 4.3 MI.
MOUNTAIN HOME

51-32/18

75-SE
SEC 8
SE/SE

Gulch

Artesian Wells
Creek

DITCH

Jacks
Artesian Well

SEEDLING
POND P.V.
FISH PEN

COOLING
POND

PD

RECORDED

JUL 26 1994

Artesian Well

Abandoned
mine

(SUGAR VALLEY)
2869 IV SE

51- 7118

PICTURE LOOKING EAST

DISCHARGE
MEASUREMENT
LOCATION

DITCH FROM
P/U TO
SETTLING
POND



DISCHARGE MEASUREMENT LOCATION



PICTURE LOOKING NORTH

MAINTENANCE

JUL 26 1994

51-7118

P/U

PICTURE LOOKING NORTH EAST



BARRELS
IN THE
PENS ARE
SELF FEEDERS

PICTURE LOOKING SOUTH WEST



JUL 26 1994

51-7118

PICTURE LOOKING SOUTH EAST



COOLING PONDS BEFORE P/4

RECEIVED

JUL 26 1994

1-7118

P/D

PICTURE LOOKING NORTH EAST SOUTH



SETTLING POND PICTURE LOOKING NORTH WEST



JUL 26 1994

PROOF OF PUBLICATION

STATE OF IDAHO

County of Owyhee

s.s.

I, RODNEY A. HAWES, being first duly sworn, on oath says that he is the Publisher of the OWYHEE NUGGET, a newspaper of general circulation, published weekly by Rodney A. Hawes, publisher and printer thereof, at Marsing, County of Owyhee, State of Idaho;

That the annexed notice was published in said newspaper once each week and every week for 2 consecutive weeks, the first publication being on the 19 day of May, 1977, and the last publication being on the 26 day of May, 1977;

That the said newspaper has been published continuously and uninterruptedly in said county during a period of more than seventy-eight consecutive weeks prior to the first publication of the attached notice.

Rodney A. Hawes
PUBLISHER

Subscribed and sworn to before me this 26 day of May, 1977.

Rodney A. Hawes
NOTARY PUBLIC

My commission expires 9-10-80

(SEAL)

NOTICE OF APPLICATION FOR WATER PERMIT

Notice is hereby given that BRUNEAU CATTLE CO. c/o Eugene C. Davis, Bruneau, ID has on May 11, 1977 submitted Application No. 51 - 7118 for a permit to appropriate 6.78 cubic feet per second of water from A GROUNDWATER SOURCE by means of well, pipeline, cooling ponds, and concrete raceways within the SW $\frac{1}{4}$ -SW $\frac{1}{4}$ Sec. 8 T7S - R5E B. M., Owyhee County to be used from Jan. 1 to Dec. 31 for fish culture purposes within the SW $\frac{1}{4}$ -SW $\frac{1}{4}$ Sec. 8 T7S - R5E B. M.,

If issued, this permit will be subject to all prior water rights. Protests against the granting of the permit must be filed with the Director of the Idaho Department of Water Resources, 92 South Cole Road, Boise, Idaho 83705 on or before June 6, 1977.

C. STEPHEN ALLRED,
Director.

Published in the Owyhee Nugget, Marsing, ID on May 19, 1977 and May 26, 1977.

OK 448
6-3-77

RECEIVED

Department of Water Resources
Western Regional Office

State of Idaho
Department of Water Resources

WATER RIGHT LICENSE
WATER RIGHT NO. 51-07118

Priority: January 12, 1978

Maximum Diversion Rate: 3.20 CFS
Maximum Diversion Volume: 2316.7 AF

This is to certify, that BRUNEAU CATTLE CO
C/O EUGENE C DAVIS
RT B BOX 138
BRUNEAU ID 83604

has complied with the terms and conditions
of the permit, issued pursuant to Application for Permit dated May 11, 1977; and
has submitted Proof of Beneficial Use on March 4, 1983. An examination indicates
that the works have a diversion capacity of 9.600 cfs of water from a GROUNDWATER
source, and a water right has been established as follows:

<u>BENEFICIAL USE</u>	<u>PERIOD OF USE</u>	<u>RATE OF DIVERSION</u>	<u>ANNUAL VOLUME</u>
FISH PROPAGATION	01/01 to 12/31	3.20 CFS	2316.7 AF

LOCATION OF POINT(S) OF DIVERSION: SWSW , Sec. 8, Township 07S, Range 05E
OWYHEE County

PLACE OF USE: FISH PROPAGATION
TWN RGE SEC

07S 05E 8 SWSW

CONDITIONS/REMARKS:

1. The maximum diversion volume is defined as the maximum allowable volume of water that may be diverted annually from the source under this right. The use of water confirmed by this right is limited to the amount which can actually be beneficially used. The maximum diversion volume may be adjusted to more accurately describe the beneficial use or to implement accepted standards of diversion and use efficiency.
2. This water right is appurtenant to the described place of use.
3. This right is subject to all prior water rights and may be forfeited by five years of non-use.
4. Modifications to or variance from this license must be made within the limits of Section 42-222, Idaho Code, or the applicable Idaho law.
5. A measuring device of a type approved by this Department shall be maintained as a part of the diverting works.
6. Water used under this right if discharged into a natural channel shall meet Idaho Water Quality Standards.

RECORDED

JUL 26 1994

State of Idaho
Department of Water Resources

WATER RIGHT LICENSE
WATER RIGHT NO. 51-07118

This license is issued pursuant to the provisions of Section 42-219, Idaho Code,
Witness the seal and signature of the Director, affixed at Boise, this 15th
day of July, 1994.

Acting for 
R. Keith Higginson, Director


JUL 26 1994

BEFORE THE DEPARTMENT OF WATER RESOURCES
OF THE
STATE OF IDAHO

IN THE MATTER OF PERMIT NO. 51-7118 IN THE)
NAME OF BRUNEAU CATTLE CO.) ORDER OF REINSTATEMENT
_____)

WHEREAS, the Department has issued the above-captioned permit with the condition that proof of construction of works and application of water to beneficial use be submitted on or before July 1, 1982; and,

WHEREAS, the Department has notified the permit holder by certified mail that proof was due and instructed the permit holder as to the steps to be taken to make said proof; and,

WHEREAS, the Department has notified the permit holder that the permit has lapsed for failure of the permit holder to submit proof of beneficial use; and,

WHEREAS, Section 42-218a of the Idaho Code provides that a permit may be reinstated upon a showing of reasonable cause within sixty days of the date of the notice of lapsing; and,

WHEREAS, the permit holder has provided a reasonable showing as to why said permit should be reinstated by submitting proof of beneficial use on March 4, 1983;

IT IS, THEREFORE, HEREBY ORDERED that Permit No. 51-7118 be REINSTATED and the priority advanced to January 12, 1978.

Dated this 17th day of March, 1983.



L. GLEN SAXTON

Chief, Operations Bureau

RECEIVED
MAR 17 1983
WATER RESOURCES
DIVISION

BEFORE THE DEPARTMENT OF WATER RESOURCES
OF THE
STATE OF IDAHO

IN THE MATTER OF CHANGING THE MEASURING
DEVICE REQUIREMENT FOR PERMIT NO. 51-7118

ORDER

WHEREAS, the above numbered permit was approved with the condition that a measuring device of a type approved by the Department be permanently installed and maintained as part of the diverting works; and,

WHEREAS, on July 1, 1978, the Department adopted a new water measurement condition which states: "An access port or other device as specified by the Department shall be installed by the permit holder to provide for the installation of measuring equipment and the determination of the rate of diversion by the Department"; and,

WHEREAS, the former condition required the permit holder to purchase and install a measuring device or hire a professional engineer to certify the rate of diversion; and,

WHEREAS, the measuring device condition effective July 1, 1978, requires less capital expenditure by the permit holder; and,

WHEREAS, to be equitable to holders of permits issued prior to July 1, 1978, the new condition should be retroactive;

NOW THEREFORE, it is hereby ordered that the condition of approval of this permit related to water measurement is hereby changed as follows:

"The permit holder shall either install a measuring device or provide a certified measurement by a professional engineer or install an access port or other device as specified by the Department".

Dated this 1st day of June 1981.

Glen Saxton

GLEN SAXTON
Chief, Operations Bureau

Identification No. _____

Application No. 51-7118

STATE OF IDAHO
DEPARTMENT OF WATER RESOURCES

APPROVED

APPLICATION FOR PERMIT

Power of attorney:

Joseph Thackaberry

Box 1405 Boise, Idaho 83701

To Appropriate the Public Waters of the State of Idaho
(TYPE OR PRINT IN INK)

1 Name of applicant Bruneau Cattle Co. Phone 845-2762
post office address c/o Eugene C. Davis, Bruneau, Idaho 83604

2 Source of water supply Ground water which is a tributary of _____

3 a Location of point of diversion is SW $\frac{1}{4}$ of SW $\frac{1}{4}$ of Section 8 Township 7 S
Range 5 E B M Owyhee County; additional points of diversion if any _____

b If water is not consumed, it will be discharged into Settling Pond at a point in SW $\frac{1}{4}$
of SW $\frac{1}{4}$ of Section 8 Township 7 S Range 5 E B.M. _____

4 Water will be used for the following purposes

Amount 6.78 ^{cfs} for fish culture purpose from 1/1 to 12/31 (both dates inclusive)
(cfs or acre-feet per annum)

Amount _____ for _____ purpose from _____ to _____ (both dates inclusive)
(cfs or acre-feet per annum)

Amount _____ for _____ purpose from _____ to _____ (both dates inclusive)
(cfs or acre-feet per annum)

5. Total quantity to be appropriated

a 6.78 cubic feet per second and/or

b _____ acre feet per annum

6 Proposed diverting works

a Description of ditches, flumes, pumps, headgates, etc 1,500 ft. well, 98° F. Hot
water artesian flow, with pipeline leading to cooling ponds and to
concrete raceways.

b Height of storage dam _____ feet, active reservoir capacity _____ acre feet, total reservoir
capacity _____ acre feet, materials used in storage dam _____
Period of year during which storage will occur _____ to _____ inclusive
(Mo Day) (Mo Day)

c Proposed well diameter is 16-13" inches, proposed depth of well is 1500 feet

7 a Time required for the completion of the works and application of the water to the proposed beneficial use
is 5 years

b Estimated construction cost is \$ 45,000.

8 Description of proposed uses Fish Culture

a If water is **not** for irrigation

(1) Give the place of use of water SW $\frac{1}{4}$ of SW $\frac{1}{4}$ of Section 8 Township 7 S
Range 5 E B M _____

(2) Amount of power to be generated _____ hp under _____ feet of head

(3) List number of each kind of livestock to be watered _____

(4) Name of municipality to be served _____, or number of families to be
supplied with domestic water _____

(5) If water is to be used for other purposes describe Entire flow, 6.78 cfs., is used
for fish culture from January 1st to December 31st.

MICROFILMED

b If water is for irrigation, indicate acreage in each subdivision in the tabulation below

TWP	RANGE	SEC	NE1/4				NW1/4				SW1/4				SE1/4				TOTALS
			NE1/4	NW1/4	SW1/4	SE1/4	NE1/4	NW1/4	SW1/4	SE1/4	NE1/4	NW1/4	SW1/4	SE1/4	NE1/4	NW1/4	SW1/4	SE1/4	


Total number of acres to be irrigated_____

c Describe any other water rights used for the same purposes as described above._____
None

- 9 a Who owns the property at the point of diversion_____Applicant
b. Who owns the land to be irrigated or place of use_____Applicant
c If the property is owned by a person other than the applicant, describe the arrangement enabling the applicant to make this filing_____

10. Remarks The entire flow is used for fish culture from January 1st to December 31st. During the irrigation season, usually from March 15th to November 15th, the flow into the settling pond is pumped for irrigation purposes under License No. 51-7013 and the overflow from the settling pond goes through a ditch and pipeline and is discharged into Little Valley Creek and rediverted under License No. 51-2164. For the period of time outside the irrigation season the water is released from the settling pond into Little Valley Creek.

11 Map of proposed project show clearly the proposed point of diversion, place of use, section number, township and range number



Scale 2 inches equal ~~xxxx~~ 1320'

BE IT KNOWN that the undersigned hereby makes application for permit to appropriate the public waters of the State of Idaho as herein set forth

BRUNEAU CATTLE CO.

by ✓
(Applicant)

Eugene C. Davis
Eugene C. Davis
President

Proposed Priority 5/11/77

Received by BDF Date 5-11-77 Time 10:15 am

Preliminary check by BDF Fee \$ 85.00

Receipted by KTN Date 5-11-77 # 7846

Publication prepared by CS Date May 12, 1977

Published in Owyhee Nugget

Publication dates May 19, 1977 - May 26, 1977

Publication approved [Signature] Date 6-3-77

Priority reduced to _____ Reason _____

Protests filed by _____

Copies of protests forwarded by _____

Hearing held by _____ Date _____

Recommended for approval denial by [Signature]

ACTION OF THE DIRECTOR, DEPARTMENT OF WATER RESOURCES

This is to certify that I have examined Application for Permit to appropriate the public waters of the State of Idaho No 51-7118, and said application is hereby APPROVED.

1 Approval of said application is subject to the following limitations and conditions

- a SUBJECT TO ALL PRIOR WATER RIGHTS.
- b Proof of construction of works and application of water to beneficial use shall be submitted on or before July 1, 19 82.
- c Other: A measuring device of a type approved by this Department shall be permanently installed and maintained as part of the diverting works.

Witness my hand this 11 day of July 19 77.

[Signature]
Deputy Director

STATE OF IDAHO
DEPARTMENT OF WATER RESOURCES

POWER OF ATTORNEY

The undersigned holder(s) of Permit/Application No. _____ attached _____ of the Department of Water Resources of the State of Idaho hereby nominates Joseph J. Thackaberry, whose address is P.O.Box 1405, Boise, Idaho 83701 as attorney-in-fact, with full authority to act for and on behalf of the undersigned in all matters pertaining to the above numbered permit or application. Such acts shall include, but not be limited to, the filing of application, receiving of all notices, the signing and filing of applications for extension of time and for amendments of said permits, and the submission of proofs of completion of works and beneficial use of water.

Dated this 10th day of May, 19 77.

BRUNEAU CATTLE CO.

by Eugene C. Davis

Eugene C. Davis, President

STATE OF IDAHO)
County of Ada) ss.

On this 10th day of May, 19 77, personally appeared before me the signer(s) of the above instrument, who duly acknowledged to me that he (she) (they) executed the same.

[Signature]
Notary Public
Residing at Boise, Idaho

a 1

Commission expires:

7/23/79



State of Idaho

DEPARTMENT OF WATER RESOURCES

1301 North Orchard Street, Statehouse Mail, Boise, Idaho 83720-9000

Phone: (208) 327-7900 FAX: (208) 327-7866

CECIL D. ANDRUS
GOVERNOR

R. KEITH HIGGINSON
DIRECTOR

July 18, 1994

BRUNEAU CATTLE CO
C/O EUGENE C DAVIS
RT B BOX 138
BRUNEAU ID 83604

RE: WATER RIGHT NO. 51-07118

Dear Water Right Holder(s):

Enclosed herewith is a copy of the Water Right License issued on the above referenced permit. If you have any questions, please contact me within 10 days of receipt of this license.

Sincerely,

A handwritten signature in black ink, appearing to read 'Jim Johnson', with a long horizontal line extending to the right.

JIM JOHNSON, Manager
Water Right Permits Section

JJ:dc

Enclosure

A faint, dark stamp, possibly a date or administrative mark, located in the bottom right corner of the page.

JUL 26 1994

WR0749NP
No. L51-07118

IDAHO DEPARTMENT OF WATER RESOURCES
WATER RIGHT PROFILE REPORT
(REGIONAL)

DATE: 09/01/93
PAGE: 1

OWNER CODE	NAME & ADDRESS	PRIORITY DATE	WATER USE	USE PERIOD FROM TO	DIVERSION RATE	DIVERSION VOLUME
C	BRUNEAU CATTLE CO C/O EUGENE C DAVIS RT B BOX 138 BRUNEAU ID 83604 (206) 845-2762	01/12/1978	FISH PROPAGATION	01-01 12-31	3.20 CFS	2316.7 AFA
TOTAL DIVERSION:					3.20 CFS	2316.7 AFA

Water Source: GROUNDWATER

Tributary to:

Stage: LICENSE

Point(s) of Diversion Capacity: 9.60 CFS

Point(s) of Diversion: T07S R05E S08 SW SW

Place of use Legal Description for: FISH PROPAGATION

				NE				NW				SW				SE				
T	R	S	:	Lt	Ac	Lt	Ac	Lt	Ac	Lt	Ac	Lt	Ac	Lt	Ac	Lt	Ac	Lt	Ac	:
07S	05E	8	:	:	:	:	:	:	:	:	:	:	:	:	:	:	:	:	:	:
												F								

Pou County: OMYREE

Conditions of Approval:

- R01 - A measuring device of a type approved by this Department shall be maintained as a part of the diverting works.
- 09D - Water used under this right if discharged into a natural channel shall meet Idaho Water Quality Standards.

Dates:	App. Received:	05/11/1977	Priority Date:	01/12/1978	(Priority Date Advanced.)
	Proof Due Date:	07/01/1982	Proof Made Date:	03/04/1983	(Proof Received Late.)
	Exam Made Date:	06/14/1988	Exam Sent to S.O.:	01/14/1992	
	Licensed Date:				

Misc: Water District Number: Field Exam Fee: R (Received)

Comments: Date: 09/01/1993 User-ID: CHAPMAN Subject: RATE REDUCTION
The rate was reduced on this permit at the time of licensing because according to F & G officials, 3 changes per hour is adequate for "talapia" even in warm water.

Audit: 09/01/93 CHAPMAN

LICENSE REVIEW CHECKLIST

Permit # 51-7118

Date 8-27-93

Brenda Chapman

NAME Yes No Or Address Change?

PRIORITY DATE Advance? Done Memo to Advance
 Order to Reinstate Needed? Done

SOURCE Changes? Clarification of **Originally**
Intended source
(LOW TEMP Notice of Intent to Void - Source change.
(GEO THERMAL
WELL
P/D Amendment Needed?
 Is Overlap Analysis a Consideration?

P/U Amendment Needed?
 Is Overlap Analysis a Consideration?

TOTAL CFS Incorrect Fee for rate recommended?
 Disagree/Measurement Unsub 5.63 CFS
 Pumping Theoretical (8.8 x .70 x 75)
 (25 + 2.31 x 10) = 9.6 CFS
 System Capacity 9.6
 Allowable Amount: SEE CALC CHART FOR 3

TOTAL VOLUME Rate/ac AFA Irr. Season
 Standard Irr. Season
 Season Recommended
 Disagree with Examiner's Calculations?
 Difference because .088 v .09 for factor.
 Flow limit: 3.2 x 365 x 1.9835 = 2316.7

USES Change(s) in Nature of Use?
 Amendment Needed?

REMARKS Multiple P/Ds in 1/4 1/4?
 Non-Irr. Uses FISH PROPAGATION
 Special Overlap Condition
 Other

CONDITIONS Measuring/Locking Devices Misc/Dates
 W/Master Control Water Dist
 Irrigation Overlap 5-11-77 App Rec'd
 Water Quality 6-14-88 Exam Made

COMMENTS: REDUCE RATE - F & G stated 3 changes per hr for
"talapia" is adequate.

RECOMMENDED	CFS	VOL
<u>Fish</u>	<u>3.2</u>	<u>2316.7</u>
<u>PROPAGATION</u>	<u> </u>	<u> </u>
<u> </u>	<u> </u>	<u> </u>
<u> </u>	<u> </u>	<u> </u>

LICENSE
AMEND

CLAIM FILED
* NO "R" FILE CREATED

FISH PROPAGATION CALCULATIONS

FILE: 51-07118
DATE: August 30, 1993

INPUT:

Fish Facility Volume
Flow into Facility

3840 cubic feet
3.2 cubic feet per second

CALCULATIONS:

Cubic feet in one hour (cubic feet per second* 3600seconds per hour) =
Number of times flow will fill the facility in one hour (Facility Volume cubic feet/flow cubic feet)=

11520 cubic feet
3.0 times/hour

Find how many changes can occur in one year:

Changes per hour=
One year =
Number of changes per year =

3.00 hours
8760
26280 changes

Find one year diversion volume in acre feet:

1 acre foot =
Facility Volume =
Facility Volume =

43560 cubic feet
3840 cubic feet
0.088 acre feet

Annual Volume =
(Total Diversion Volume = Facility Volume * changes)

2316.7 acre feet

RECEIVED

JUL 26 1994

FISH PROPAGATION CALCULATIONS

FILE: 51-07118
DATE: August 30, 1993

INPUT:

Fish Facility Volume
Flow into Facility

3840 cubic feet
5 63 cubic feet per second

CALCULATIONS:

Cubic feet in one hour (cubic feet per second* 3600seconds per hour) =
Number of times flow will fill the facility in one hour (Facility Volume cubic feet/flow cubic feet)=

20268 cubic feet
5.3 times/hour

Find how many changes can occur in one year:

Changes per hour=
One year =
Number of changes per year =

5 28 hours
8760
46236 changes

Find one year diversion volume in acre feet:

1 acre foot =
Facility Volume =
Facility Volume =

43560 cubic feet
3840 cubic feet
0.088 acre feet

Annual Volume =

(Total Diversion Volume = Facility Volume * changes)

4075.9 acre feet

RECEIVED
JUL 26 1993

* 5.3 too many changes
PER HOUR. REDUCE RATE

STATE OF IDAHO
DEPARTMENT OF WATER RESOURCES
BENEFICIAL USE FIELD REPORT

RECEIVED
JAN 17 1988

Department of Water Resources

A. GENERAL INFORMATION


1 Owner BRUNEAU CATTLE CO. Permit No. 51-7118
Current Address: % EUGENE C. DAVIS, BRUNEAU, ID. 83604 Phone No. 845-2762
2 Accompanied by: EUGENE DAVIS EXAM. DATE. 06/14/88
Address. _____ Phone No. _____
Relationship to Permit Holder: OWNER
3 Source. GROUNDWATER tributary to _____

B. OVERLAP REVIEW

1 Other water rights with same place of use: NONE ☐ Copies Attached
2. Other water rights with same point of diversion: 51-2164 51-7013
☒ Copies Attached ☒ Copies of Field Exam's Attached

C. SYSTEM DESCRIPTION

1. **Diversion System Diagram:** Indicate all major components and distances between components. Indicate weir size/ditch size/pipe i.d. as applicable. ☐ Alternative diagram attached



Scale: 1" = _____

- 2 ☒ Copy of U.S.G.S. Quadrangle Attached Showing location(s) of point(s) of diversion and place(s) of use (required). ☐ Aerial Photo Attached (required for irrigation of 10 acres or more).
☒ Photo of Diversion and System Attached (required for all but single household domestic groundwater, and stockwater)

JUL 26 1994

System Description (continued)

3. **Narrative:** Description (As operating at time of measurement. Indicate pressure, number of sprinklers, etc.)

SYSTEM IS AN ARTESIAN WELL WITH A 75 HP BOOSTER PUMPING INTO A SYSTEM OF 3 COOLING PONDS. ALL 3 PONDS CONTAIN FLOW CONTROL BOXES ALLOWING THE WATER CIRCULATION TO BE ALTERED TO CONTROL THE TEMP OF WATER ENTERING THE FISH PENS. WATER ENTERS THE PENS ON THE EAST AND FLOWS THROUGH 2 SECTIONS OF 4 PENS EACH. FLOW THEN DUMPS INTO AN OPEN DITCH WHICH CARRIES THE WATER TO THE SETTLING POND. THE WATER IS

☒ See Remarks on page 4 for continuation

4

Well or Diversion Identification No.*	Motor Make	Hp	Motor Serial No.	Pump Make	Pump Serial No. or Discharge Size
	GENERAL ELECTRIC	75	NW119131-WJ	LAYNE	

*Code to correspond with No. on map and aerial photo

5. **Point(s) of Diversion:**

Ident. No.	Gov't. Lot	1/4	1/4	1/4	Sec.	Twp.	Rge.	County	Method of Determination/Remarks
			SW	SW	8	75	5E	OWYHEE	QUAD MAP

6. **Place(s) of Use:**

Indicate Method of Determination QUAD MAP

Twp.	Rge.	Sec.	NE 1/4				NW 1/4				SW 1/4				SE 1/4				Totals
			NE 1/4	NW 1/4	SW 1/4	SE 1/4	NE 1/4	NW 1/4	SW 1/4	SE 1/4	NE 1/4	NW 1/4	SW 1/4	SE 1/4	NE 1/4	NW 1/4	SW 1/4	SE 1/4	
75	5E	8											X						

MISSOURI

JUL 26 1994

Do not use this space

Do not use this space

D. FLOW MEASUREMENTS

☐ Additional Data Sheets Attached

1

Measurement Equipment	Type	Make	Model No.	Serial No.	Size	Calib. Date
ANNULAR				091432		
PIGMY METER				090194		
MANOMETER		IDWRS				

2. Measurements:

WELL FLOW TAKEN APPROXIMATELY FIVE FEET FROM THE END OF THE DISCHARGE. A BOARD WAS USED TO CREATE BACK PRESSURE. PER EUGENE DAVIS BOWLS ARE SET AT APPROXIMATELY 30 FEET.

E. FLOW CALCULATIONS

☒ Additional Computation Sheets Attached

1. Measured Method:

$$Q = \frac{(11.89)^2 (720) (3.99)}{448.8} = 5.63 \text{ CFS}$$

if this was taken against created back pressure, how can this be accurate?

2. Alternate Method for Checking Purposes:

NORMAL ARTESIAN FLOW

EST LIFT OF 10 FT WITH BOOSTER

OPEN DISCHARGE? PSF = 0

$$\frac{75 \text{ HP} \times 8.8 \times .8}{10 + (2.3 \times 0)} = \frac{46.2}{52.8} = 0.87 \text{ CFS}$$

F. PUMP EFFICIENCY DATA (Optional)

Discharge Pressure: _____ psi x 2.31 = _____ ft (1); Dynamic pumping level: _____ ft (2)

Total Head: (1) + (2) = _____ (3)

: Flow rate: _____ cfs (4)

Water HP: (3) x (4) ÷ 8.8 = _____ (5)

Meter Input KW: 3.6 x _____ KH x _____ CTR or _____ MULT x _____ PTR x _____ N/ _____ T = _____ (6)

Meter Input HP: (6) x 1.34 = _____ (7)

Panel Input KW: _____ Ave PF x _____ Ave Volts x _____ Ave Amps x .001732 = _____ (6)

Panel Input HP: (6) x 1.34 = _____ (7) Efficiency: (5)/(7) x 100 = _____ %

assuming only 60% efficiency & 25' TDH, Q = 15.84 cfs

G. VOLUME CALCULATIONS

1. Volume Calculations for Irrigation:

$V_{IR} = (\text{Acres Irrigated}) \times (\text{Irrigation Requirement}) = \text{N/A}$

$V_{DR} = [\text{Diversion Rate (cfs)}] \times (\text{Days in Irrigation Season}) \times 1.9835 = 5.63 \text{ CFS} \times 365 \times 1.9835 = 4076 \text{ AFA}$

$V = \text{Smaller of } V_{IR} \text{ and } V_{DR} =$

2. Volume Calculations for Other Uses: RACEWAYS: 8 cells, each 24' x 10' x 2' = .09 AF total

$V_{REQ} = .09 \text{ AF} \times 3 \text{ changes/hr} \times 24 \text{ hr/day} \times 365 \text{ days/yr} = 2365.2 \text{ AFA}$

$V_{DIV} = 5.63 \times 365 \times 1.9835 = 4076.0$

$V_{RECOMMEND} = 2365.2$

* Per Dave Parish of F&G, 3 water changes/hr adequate for tolapia even in warm H₂O

JUL 26 1994

H. REMARKS AND OVERLAP REVIEW ANALYSIS

THEN PUMPED INTO AN IRRIGATION SYSTEM UNDER THE LICENSES LISTED UNDER P/D OVERLAP REVIEW. DISCHARGE FROM FISH RACEWAYS WAS MEASURED BY USING PIGMY METER. (SEE OPEN CHANNEL DISCHARGE MEASUREMENT NOTES) CFS MEASURED WAS 1.71 CFS.

FISH RAISED ARE TALAPIA. ALL PENS WERE IN USE WITH THE FISH SEPERATED INTO 3 SIZE CATEGORIES.

Comments: examiner is no longer available, exam was done in 1988 & ASRBA exam pending next year. ^{for related irrigation uses.} Recommend licensing at this rate with modified volume based on actual use. Well log in 1967 rates artesian flow at 6 cfs, exam in 1968 stated system capacity to be 3.37 cfs. System has since been modified to include booster pump. SRBA claim has been filed for this water right.

I. RECOMMENDATIONS

1. Recommended Amounts

Beneficial Use	Period of Use		Rate of Diversion	Annual Volume
	From	To	Q (cfs)	V (afa)
FISH CULTURE	1-1	12-31	5.63 CFS	4076 AFA
(propagation)				2365.2
Totals:			5.63 CFS	4076 AFA
				2365.2

2. Recommended Amendments

- ☐ Change P.D. as reflected above
 ☐ Add P.D. as reflected above
 ☒ None
- ☐ Change P.U. as reflected above
 ☐ Add P.U. as reflected above
 ☐ Other


J. AUTHENTICATION

Field Examiner's Name KELLY K CHRISTENSEN

Signature Kelly K Christensen

Certification Date 12/31/91

Field Report Preparation Date 12-20-88



K. Licensing recommendation shall be prepared by an Idaho Department of Water Resources employee on a computer printout attached hereto.

UNAPPROVED

JUL 26 1994

State of Idaho
DEPARTMENT OF WATER RESOURCES
SUPPLEMENTAL FIELD REPORT FOR ANNUBAR MEASUREMENT

Measured by: QUENTIN NESBITT Date 6/14/38
Owner: LOWEA COTLE COMPANY Permit No. 51-7118

Description of well &/or measuring site

- Include any clarifications of the sketch
- Include legal description if more than one p.d. is described in the Field Report

MEASURED INSIDE-PIPE DIAMETER IN INCHES (ID)

CIR = Pipe Circumference in Inches = 12

T = Pipe Thickness in Inches = 1/8

ID = $2 [(0.1592 \times \text{CIR}) - T] = \dots\dots\dots 11.89$

ANNUBAR DESCRIPTION & CONSTANT (C)

Size Used in Test 12"

State ID No. _____

Select C based on size from Table below.

Nominal Pipe Size	C
4"	4.23
6"	3.75
8"	3.87
10"	3.94
12"	3.99
14"- 16"	4.01
18"- 24"	4.02
30" or larger	4.03

C selected 3.99

DIFFERENTIAL PRESSURE READING IN INCHES OF H₂O (H)

High Reading = 34

Low Reading = 14


High - Low = H = 20

CALCULATION OF DISCHARGE IN CFS (Q)

$$Q = \frac{(ID)^2 (\sqrt{H}) (C)}{448.8}$$

$$Q = \frac{(11.89)^2 (\sqrt{20}) (3.99)}{448.8} = 5.63 \text{ CFS} \quad \text{--- 28" ICHES}$$

SKETCH (If not shown on Field Report)



MISSOURI

JUL 26 1994

WATER SUPPLY SYSTEM

NAME OF PROJECT: [illegible] LOCATION: [illegible]

DATE: [illegible] DRAWING NO.: [illegible]

DESIGNED BY: [illegible] CHECKED BY: [illegible]

TYPE OF WORK: ☒ Replacement well ☐ New well

SIZE OF PUMP AND MOTOR: [illegible]

METHOD OF CONSTRUCTION: ☒ Drilled ☐ Cased

Length of time of test: [illegible]

BASED SCHEDULE: ☒ Threaded ☐ Welded

Drawdown: [illegible]

1/2" diam from [illegible] ft. to [illegible] ft.

Controlled by valve: ☒ Yes ☐ No

1/2" diam from [illegible] ft. to [illegible] ft.

No control: ☐ Does not [illegible]

1/2" diam from [illegible] ft. to [illegible] ft.

FROM: [illegible] TO: [illegible]

1/2" diam from [illegible] ft. to [illegible] ft.

YES OR NO

1/2" diam from [illegible] ft. to [illegible] ft.

FROM: [illegible] TO: [illegible]

1/2" diam from [illegible] ft. to [illegible] ft.

FROM: [illegible] TO: [illegible]

1/2" diam from [illegible] ft. to [illegible] ft.

FROM: [illegible] TO: [illegible]

1/2" diam from [illegible] ft. to [illegible] ft.

FROM: [illegible] TO: [illegible]

1/2" diam from [illegible] ft. to [illegible] ft.

FROM: [illegible] TO: [illegible]

1/2" diam from [illegible] ft. to [illegible] ft.

FROM: [illegible] TO: [illegible]

1/2" diam from [illegible] ft. to [illegible] ft.

FROM: [illegible] TO: [illegible]

1/2" diam from [illegible] ft. to [illegible] ft.

FROM: [illegible] TO: [illegible]

1/2" diam from [illegible] ft. to [illegible] ft.

FROM: [illegible] TO: [illegible]

1/2" diam from [illegible] ft. to [illegible] ft.

FROM: [illegible] TO: [illegible]

1/2" diam from [illegible] ft. to [illegible] ft.

FROM: [illegible] TO: [illegible]

1/2" diam from [illegible] ft. to [illegible] ft.

FROM: [illegible] TO: [illegible]

1/2" diam from [illegible] ft. to [illegible] ft.

FROM: [illegible] TO: [illegible]

1/2" diam from [illegible] ft. to [illegible] ft.

FROM: [illegible] TO: [illegible]

1/2" diam from [illegible] ft. to [illegible] ft.

FROM: [illegible] TO: [illegible]

1/2" diam from [illegible] ft. to [illegible] ft.

FROM: [illegible] TO: [illegible]

1/2" diam from [illegible] ft. to [illegible] ft.

FROM: [illegible] TO: [illegible]

51-7118
Water Right No.
(if applicable)

.90

1. Name of stream or ditch: DISCHARGE BELOW FISH RACEWAYS .92
2. Location: 100 FT DOWN STREAM FROM DGS FROM PENS
3. Person conducting measurement: QUENTIN NESBIT & KELLY CHRISTENSEN .94
4. Date and time of measurement: 6-14-88 2:11 PM
5. Accompanied by: EUGENE DAVES .96
6. Measuring device size and ID no. ' _____
7. Spin test before measurement OK? YES after measurement OK? YES .97
8. Purpose of measurement: DETERMINE VOLUME DIFF. THROUGH SYSTEM .98

.99

[illegible]

REC'D
JUL 26 1994

JUL 26 1994

[Signature]

SIGNATURE OF PERSON CONDUCTING MEASUREMENT

DATE

6-17-88


3. Width: 5.5' Area: 9.35 Discharge in cubic feet per second: 1.70 CFS

2. Remarks:

D. SUMMARY INFORMATION

1. Measurement rated

excellent ☒ good ☐ fair ☐ poor




NOT TO SCALE

2. Cross-Section of Measurement

TO SETTING POND

MEASUREMENT LOCATION




F - 2 K.P.C. UNIT

1. Measurement Location


C. DIAGRAMS

FISH RACEWAY.

TOP VIEW



SIDE VIEW




DASH LINES INDICATE
WATER LEVEL

WATER OVER FLOWS INTO NEXT PEN. EACH SECTION OF
4PENS IS SEPERATED WATER WISE ONCE IT ENTERS THE FIRST
PEN UNTIL IT COMBINES AT THE END.

[Signature]
JUL 26 1994


ACRE FEET CALCULATIONS FOR THE
3 WATER COOLING PONDS.
FOR POND IDENTIFICATION SEE FIELD REPORT FORM

POND A.




$$150' \times 360' \times 4.5' = \frac{243,000 \text{ cuft}}{43,560 \text{ cuft}} \\ \underline{\underline{5.6 \text{ ACRE FEET}}}$$

POND B



$$150' \times 180' \times 3.5' = \frac{94,500 \text{ cuft}}{43,560 \text{ cuft}} \\ \underline{\underline{2.17 \text{ ACRE FEET}}}$$

POND C



SECTION X


$$545' \times 4.5' \times 150' = \frac{367,875 \text{ cuft}}{43,560 \text{ cuft}} \\ \underline{\underline{8.45 \text{ ACRE FEET}}}$$

SECTION Y

$$\frac{545' \times 4' \times 150'}{2} = \frac{163,500 \text{ cuft}}{43,560 \text{ cuft}} \\ \underline{\underline{3.75 \text{ ACRE FEET}}}$$


TOTAL = 12.2 ACRE FEET

MICROFILMED
JUL 26 1994



51- 7118

PICTURE LOOKING EAST



DISCHARGE
MEASUREMENT
LOCATION

DITCH FROM
P/U TO
SETTLING
POND

DISCHARGE MEASUREMENT LOCATION



PICTURE LOOKING NORTH

M-100-1000

JUL 26 1994

51-7118


P/U

PICTURE LOOKING NORTH EAST



BARRELS
IN THE
PENS ARE
SELF FEEDERS


PICTURE LOOKING SOUTH WEST



JUL 26 1994

51-7118

PICTURE LOOKING SOUTH EAST




COOLING PONDS BEFORE P/4

JUL 26 1994

1-7118

P/D

PICTURE LOOKING NORTH EAST
SOUTH



SETTLING POND PICTURE LOOKING NORTH WEST



81994

KEYWORD

4/86

RECEIVED

JUN 1 1987

Department of Water Resources
Western Regional Office

STATE OF IDAHO

DEPARTMENT OF WATER RESOURCES

EXAMINATION FEE INFORMATION

 OK BP
 For Office Use Only
 Fee Received \$ 250.00
 Date 6-3-87
 Receipt # 44899
 Receipt by J. A.

RECEIVED

JUN 18 1987

1. Permit No. 51-7118

Department of Water Resources

ONE OF THE FOLLOWING BOXES SHOULD BE MARKED TO DESIGNATE YOUR CHOICE:

☒ I choose to have the department make the field examination of this permit; attached is the examination fee. (If this box is marked, complete items 1 thru 8.)
2. Permit Holder: BRUNEAU CATTLE Co.3. Post Office Address: HC 85, Box 138BRUNEAU, IDAHO 83604 Telephone No. (208) 845-27624. Source of Water: WELL

5. Extent of Use:

Domestic _____ (No. of households) Stockwater _____ (No. and type of stock)

Irrigation _____ (acres) Other/Remark FISH CULTURE6. Total rate &/or volume for which proof is submitted 6.78 cfs _____ acre-feet

7. Show the date water was first diverted and beneficially used under this permit:

5-11-77

8. Person to contact to accompany the department representative during the field examination:

GENE DAVIS (Name)HC 85, Box 138 BRUNEAU IDAHO (Address)JUL 26 1987 845-2762 (Telephone Number)
☐ I choose to have the field examination conducted by a certified water right examiner. Attached is a statement from the certified examiner I have selected verifying that he has been retained to conduct the examination. (If this box is marked, complete items 1 thru 7.)
Date May 30, 1987Signature of Permit Holder (and title, if appropriate) Bruneau Cattle Co. by: Eric R. Davis

State of Idaho

Department of Water Resources

LICENSE EXAMINATION FEE SCHEDULE

(c.f.s. = cubic feet per second
AF = acre feet)

cfs	AF	Fee
0 - 0.04	0 - 4	\$ 0
.05 - 0.20	5 - 20	50.00
.21 - 1.0	21 - 100	100.00
1.01 - 2.0	101 - 200	125.00
2.01 - 3.0	201 - 300	150.00
3.01 - 4.0	301 - 400	175.00
4.01 - 5.0	401 - 500	200.00
5.01 - 6.0	501 - 600	225.00
6.01 - 7.0	601 - 700	250.00
7.01 - 8.0	701 - 800	275.00
8.01 - 9.0	801 - 900	300.00
9.01 - 10.0	901 - 1000	325.00
10.01 - 11.0	1001 - 1100	350.00
11.01 - 12.0	1101 - 1200	375.00
12.01 - 13.0	1201 - 1300	400.00
13.01 - 14.0	1301 - 1400	425.00
14.01 - 15.0	1401 - 1500	450.00
15.01 - 16.0	1501 - 1600	475.00
16.01 - 17.0	1601 - 1700	500.00
17.01 - 18.0	1701 - 1800	525.00
18.01 - 19.0	1801 - 1900	550.00
19.01 - 20.0	1901 - 2000	575.00
20.01 & over	2001 & over	600.00

Checks should be made payable to the
Department of Water Resources

No fee is required for single family
domestic use or stockwater use.



Cecil D. Andrus
Governor

State of Idaho
DEPARTMENT OF WATER RESOURCES
Western Region

2735 Airport Way
Boise, Idaho 83705
(208) 334-2190

51-7118
BRUNEAU CATTLE CO.
C/O EUGENE G. DAVIS
RT. 8 BOX 138
BRUNEAU, ID 83604

138041

April 3, 1987

CERTIFIED MAIL

EXAMINATION FEE NOTICE

Dear Permit Holder:

Department records show that proof of beneficial use has been submitted for the above-referenced permit, but that a field examination has not yet been conducted to determine the extent of beneficial use of the water for licensing purposes.

House Bill 671 (effective April 4, 1986) enacted by the 1986 Idaho Legislature requires the payment of a fee before this department can conduct the field examination needed to issue a license confirming use of water under the permit. This letter is notification that the license examination fee is due within sixty (60) days of the date of this letter. The examination fee information sheet (enclosed) must be returned with the fee.

As an alternative to submitting the fee, the department will accept a field examination report completed by a certified water right examiner from the private sector. If you choose to have the examination done by a certified water right examiner, you need not submit the license examination fee to the department, but you must within sixty (60) days of the date of this letter return to the department, the examination fee information set showing appropriate information together with a statement from the certified examiner to verify that you have retained a certified examiner to conduct the field examination. If you choose this alternative, a completed field examination report must be submitted within one year of the date of this letter. You cannot later change your decision to use this alternative and submit the fee needed for the department to conduct the field examination, but you may change to another certified examiner.

JUL 26 1984

STATE OF IDAHO
DEPARTMENT OF WATER RESOURCES
Western Region

Statehouse
Boise, Idaho 83720
(208) 334-2190

APRIL 25, 1983

BRUNEAU CATTLE CO.
RT. 8 BOX 138
BRUNEAU ID 83604

RE: Permit No. 51-7118

Dear Permit Holder:

We acknowledge receipt of your statement submitted as proof of beneficial use for the above referenced permit.

Enclosed please find a copy of an order involving your permit.

Before a license can be issued, a field examination must be made by a representative of this department.


A condition of approval of your original permit required the installation of an access port which, according to the proof card submitted by you, has not been installed. An access port must be installed prior to the time a field examination is made.

A field examiner will contact you to arrange to examine your system.

If you have any questions regarding the field examination, please contact this office by phone at 334-2190 or in person in the third floor State Towers Building, 450 West State Street, Boise.

Sincerely,
s/Judy Pense
Secretary

Enclosure


JUL 26 1984

Gene D. [unclear]
RT. 13 Box 138
Bruney, ID 83604



RECEIVED

MAR 4 1983



IDAHO DEPARTMENT OF WATER RESOURCES
STATEHOUSE
BOISE, IDAHO 83720

DEPARTMENT OF WATER RESOURCES

The Idaho Department of Water Resources will consider this card statement that the permit holder(s) has completed development to the extent shown below. Permit No. 51-1118

Name(s) of Permit Holder: Brunson Cattle Co

Post Office Address: PO B, Box 138
Brunson, Ida. 83604 Tel. No. 208-845-2762

Source of Water: Underground (Well)

Extent of Use:

- ☐ Domestic _____ (number of households)
- ☐ Stockwater _____ (number and type of stock)
- ☐ Irrigation _____ (acres)
- ☒ Other Fish Culture - per phone con. 3-15-83

Measuring Device: Required? ☐ Yes ☐ No Installed? ☐ Yes ☐ No

Access Port: Required? ☒ Yes ☐ No Installed? ☒ Yes ☐ No

The above information is a true statement of the extent to which the above numbered permit has been developed.

3-3-83
Date

Brunson Cattle Co
By Eugene P. Evans
Signature of Permit Holder

CALCULATION OF NEW PRIORITY DATE

FROM: Rita Fleck

TO: File # 51-7118

DATE: Mar 15, 1983

Date Proof Received

Proof Due

Number of Days Proof Late

246

Mar 4, 1983
July 1, 1982

Priority Date

Number of Days Proof Late

New Priority Date

131
246
377
365
12

May 11, 1977
= Jan 12, 1978

Remarks

July 1 to Dec 31
Jan 1 to Mar 4

183
63
246



CONVERSATION MEMORANDUM

DATE Mar 15, 1983

FILE 51-7118

NAME OF PARTY Mrs Eugene Davis

EMPLOYEE Pete Fleck

RE: Beneficial Use Postcard

Pursuant to my telephone conversation with Mrs Davis, the water has been put to a beneficial use of fish cultivation.

The permit can be reinstated and the priority advanced accordingly.

62-1000

WARNING

CANCELLED OR LAPSED

This permit has been officially CANCELLED or LAPSED.

Ninety days following the date of official action this file will be DESTROYED.

January 4, 1983

Bruneau Cattle Co.
c/o Eugene C. Davis
Bruneau, ID 83604

Gentlemen:

Re: Permit No. 51-7118

LAPSE NOTICE

You are hereby notified that under the provisions of Section 42-218a of the Idaho Code, Permit No. 51-7118 has lapsed. This office did not receive either an acceptable notice that you have completed the project (proof of beneficial use) by the date required on your permit or an acceptable request for an extension of time. You were provided the proper forms in our proof due notice to you dated April 30, 1982.

Your permit cannot be reinstated unless you submit the statement of beneficial use postcard or submit an extension of time request showing reasonable cause for delay. Either the completed postcard or the extension request must be received by this office within sixty days of the date of this lapse notice or the permit will no longer be of any force or effect.

A statement of beneficial use postcard and a request for extension of time form are again enclosed for your use. Please note that a fee of \$15.00 must accompany an extension of time request and that only one extension of time can be granted unless the project has not been completed because of lack of a necessary approval by a government agency or by litigation.

CERTIFICATION OF MAILING

I hereby certify that on Jan 4, 1983
a copy (an original) of this document was
deposited in the United States mail,
postage prepaid addressed to the
individual(s) named above.

L. GLEN SAXTON
Chief, Operations Bureau

Enclosures

LGS:rf

S T A T E O F I D A H O
D E P A R T M E N T O F W A T E R R E S O U R C E S

STATEHOUSE
BOISE, IDAHO 83720
(208) 334-4440
CERTIFIED MAIL

#138770

BRUNEAU CATTLE CO.
C/O EUGENE C. DAVIS
BRUNEAU, ID 83604

APRIL 30, 1982

DEAR PERMIT HOLDER:

ONE OF THE CONDITIONS OF APPROVAL OF YOUR WATER PERMIT NO. 51-7118 WAS THAT EVIDENCE OF THE EXTENT OF DEVELOPMENT MUST BE SUBMITTED TO THIS OFFICE ON OR BEFORE JULY 01, 1982. (SEE LAST PAGE OF YOUR APPROVED PERMIT). ENCLOSED IS A POST CARD WHICH MAY BE USED TO SUBMIT THE REQUIRED PROOF OF BENEFICIAL USE.

IF YOU HAVE NOT FULLY COMPLETED YOUR PROJECT, AND YOU HAVE NOT PREVIOUSLY RECEIVED AN EXTENSION OF TIME, YOU MAY REQUEST AN EXTENSION OF TIME PROVIDED THE DELAY IS FOR REASONABLE CAUSE AS INDICATED IN SECTION 42-204, IDAHO CODE, AMENDED. IF YOU HAVE BEEN PREVENTED FROM PROCEEDING BY A GOVERNMENTAL AGENCY OR BY LITIGATION, MORE THAN ONE EXTENSION OF TIME CAN BE GRANTED.

EITHER THE BENEFICIAL USE POST CARD OR A REQUEST FOR AN EXTENSION OF TIME MUST BE RECEIVED BY THIS DEPARTMENT ON OR BEFORE THE ABOVE MENTIONED DATE, OTHERWISE, THE PERMIT WILL LAPSE AND BE OF NO FURTHER FORCE OR EFFECT WITHIN 60 DAYS.

SINCERELY,

RITA FLECK
SR. SECRETARY

ENC: 1

cc: Joseph Thackaberry



State of Idaho

DEPARTMENT OF WATER RESOURCES

STATE OFFICE, 450 W. State Street, Boise, Idaho

JOHN V. EVANS

Governor

A. KENNETH DUNN

DIRECTOR

Mailing address:
Statehouse
Boise, Idaho 83720
(208) 334-4440

April 30, 1982

Dear Wateruser:

The enclosed Order changes the measuring device condition of approval on your water right permit.

The changed condition is less restrictive and provides you the option to install an access port or have your system measured and certified by a professional engineer. Instructions for access port installation are also enclosed.

If you have questions regarding this matter, please contact the regional office nearest to you.

Sincerely,

David R. Tattell Jr

DAVID R. TUTHILL JR., P. E.
Supervisor, Water Allocations Section

DRT:jg

Enclosures

NORTHERN REGION OFFICE
Route #5, Box 203, Government Way
Coeur d'Alene, Idaho 83814
Telephone 667-6484

EASTERN REGION OFFICE
150 Shoup Avenue
Idaho Falls, Idaho 83401
Telephone 525-7161

SOUTHERN REGION OFFICE
1041 Blue Lake Boulevard North
Twin Falls, Idaho 83301
Telephone 734-3578

WESTERN REGION OFFICE
92 South Cole Road
Boise, Idaho 83709
Telephone 334-2190

IDENT. NO. 51-7118

I D A H O D E P A R T M E N T O F W A T E R R E S O U R C E S

WATER RIGHT
DATA ENTRY LOG

[illegible]

Jul 12, 1977

Re: Permit No. 51-7118

Bruneau Cattle Co.
c/o Eugene C. Davis
Bruneau, ID 83604

Gentlemen:

Enclosed is a copy of your approved Application for Permit No. 51-7118. We direct your attention to the conditions of approval as listed on the fourth page.

Be sure to note that a special condition requiring you to install and maintain a measuring device at your point of diversion has been placed upon your permit. We are enclosing a letter describing different types of measuring devices accepted by this office.

Sincerely,

BOBBY D. FLEENOR
Chief, Water Rights

Enclosure: Copy of permit

RECEIVED

PROOF OF PUBLICATION

STATE OF IDAHO
County of Owyhee } s.s.

I, RODNEY A. HAWES, being first duly sworn, on oath says that he is the Publisher of the OWYHEE NUGGET, a newspaper of general circulation, published weekly by Rodney A. Hawes, publisher and printer thereof, at Marsing, County of Owyhee, State of Idaho;

That the annexed notice was published in said newspaper once each week and every week for 2 consecutive weeks, the first publication being on the 19 day of May, 1977, and the last publication being on the 26 day of May, 1977;

That the said newspaper has been published continuously and uninterruptedly in said county during a period of more than seventy-eight consecutive weeks prior to the first publication of the attached notice.



PUBLISHER

Subscribed and sworn to before me this 26 day of May, 1977.


NOTARY PUBLIC

My commission expires 9-10-80

(SEAL)



OK 8/8
6-3-77

SA 100
Regional Office



STATE OF IDAHO

DEPARTMENT OF WATER RESOURCES

WESTERN REGION

Cecil D. Andrus
Governor

R. Kerth Higginson
Director

92 South Cole Road
Boise, Idaho 83705
(208) 384-2190

May 13, 1977

RE: Notice of Application for Water Permit No. 51-7118 - Brueau Cattle Co.

Owyhee Nuggett
Marsing, Idaho 83639

Gentlemen:

Enclosed you will find a legal notice which we wish to have published on the dates indicated (once a week for two consecutive weekly issues) in your newspaper. If you cannot publish the notice on the proposed dates, please contact us immediately.

An affidavit of publication must be submitted to the Department along with the publication bill. In order to receive payment, the following certification must appear on the bill:


"I hereby certify that the foregoing account is just and correct, that the amount claimed is legally due after allowing all just credits and that no part of the same has been paid."

(Signature of Claimant)

Please send the affidavit of publication and publication billing to this office before ~~June 6, 1977~~ _____.

Sincerely,

Bill submitted
6-3-77
y



NOTICE OF APPLICATION FOR WATER PERMIT

Notice is hereby given that BRUNEAU CATTLE CO.
c/o Eugene C. Davis, Bruneau, ID
has on May 11, 1977 submitted Application No. 51-7118
for a permit to appropriate 6.78 cubic feet per second ~~none feet~~
per annum of water from A GROUNDWATER SOURCE
~~XXXXXXXXXX~~
by means of well, pipeline, cooling ponds, and concret raceways
within the SW₁SW₄ Sec 8 T7S-R5E B.M., Owyhee County

to be used from Jan 1 to Dec 31
for fish culture purposes
within the SW₁SW₄ Sec 8 T7S-R5E B.M.

If issued, this permit will be subject to all prior water rights. Pro-
tests against the granting of the permit must be filed with the Director of
the Idaho Department of Water Resources, 92 South Cole Road, Boise, Idaho
83705 on or before June 6, 1977.

C. STEPHEN ALLRED

Director

Published in the Owyhee Nugget, Marsing, ID
on May 19, 1977 and May 26, 1977.

MICROFILMED

JOSEPH J. THACKABERRY
LAND MANAGEMENT CONSULTANT

[208] 345-0975

May 11, 1977

528 Idaho Building
P. O. Box 1405
Boise, Idaho 83701

Mr. Stephen Allred
Director
Department of Water Resources
State Capitol
Boise, Idaho 83720

Dear Mr. Allred:

Enclosed herewith please find the following:

- (1) Application for Permit by Bruneau
Cattle Co. for 6.78 cfs. for fish
culture.
- (2) Power of Attorney designating myself
as nominee for such permit.
- (3) My check in the amount of \$85 to cover
the filing fees for this application.

I would appreciate receiving a copy of the Permit when
approved. Thank you in advance for your cooperation in this
matter.

Very truly yours,


Joseph J. Thackaberry

JJT/bm

Enclosure

CC: Mr. Eugene C. Davis

MICROFILMED