

NOTICE OF PROOF APPLICATION OF
WATER TO BENEFICIAL USE

Notice is hereby given that at 10 a.m. on the 12th day of Aug., 1955, at Jerome, Bannock County of Jerome, State of Idaho, before Richard H. Seeley, a notary public, proof will be submitted of the application to beneficial use of 80 acre feet per annum of the waters of an un-named stream in accordance with the terms and conditions of Permit No. R1913 heretofore issued by the Department of Reclamation of the State of Idaho.

The name and postoffice address of the person or corporation holding said permit are Herman E. Huettig, Hazelton, Idaho.

The use to which said water has been applied is irrigation.

The amount applied to beneficial use is 80 acre feet per annum.

The place where said water is used is the NW $\frac{1}{4}$ NW $\frac{1}{4}$ and SW $\frac{1}{4}$ NW $\frac{1}{4}$, Section 28, and the NE $\frac{1}{4}$, the N $\frac{1}{2}$ NW $\frac{1}{4}$ and SE $\frac{1}{4}$ NW $\frac{1}{4}$, Section 29, all in Township 10 South, Range 20 East, B. M., Jerome County, Idaho.

The name of the canal or ditch or other works by which said water is conducted to such place of use is un-named.

The right to take water from such works is based upon Permit No. R-913.


The source of supply from which such water is diverted is an un-named stream.

The date of priority which said user is prepared to establish is July 1, 1953.

R-913 MARK R. KULP,
State Reclamation Engineer.

7-14-4tc

TO HAZELTON



Area = 360 acres

See Permit 24261

**NOTICE OF PROOF APPLICATION OF
WATER TO BENEFICIAL USE**

Notice is hereby given that at 10 a.m. on the 5th day of August, 1955, at Jerome, County of Jerome, State of Idaho, before Richard H. Seeley, a notary public, proof will be submitted of the application to beneficial use of 80 acre feet per annum of the waters of an un-named stream in accordance with the terms and conditions of Permit No. R-913 heretofore issued by the Department of Reclamation of the State of Idaho.

The name and postoffice address of the person or corporation holding said permit are Herman E. Huettig, Hazelton, Idaho.

The use to which said water has been applied is irrigation.

The amount applied to beneficial use is 80 acre feet per annum.

The place where said water is used tht NW $\frac{1}{4}$ NW $\frac{1}{4}$ and SW $\frac{1}{4}$ NW $\frac{1}{4}$, Section 28, and the NE $\frac{1}{4}$, the N $\frac{1}{2}$ NW $\frac{1}{4}$ and SE $\frac{1}{4}$ NW $\frac{1}{4}$, Section 29, all in Township 10 South, Range 20 East, B. M., Jerome County, Idaho.

The name of the canal or ditch or other works by which said water is conducted to such place of use is un-named.

The right to take water from such works is based upon Permit No. R-913.

The source of supply from which such water is diverted is an un-named stream.

The date of priority which said user is prepared to establish is July 1, 1953.

MARK R. KULP,
State Reclamation Engineer.

7-14-55 R-913 7-14-4tc

**NOTICE OF PROOF APPLICATION OF
WATER TO BENEFICIAL USE**

Notice is hereby given that at 10 a.m. on the 12th day of Aug., 1955, at Jerome, County of Jerome, State of Idaho, before Richard H. Seeley, a notary public, proof will be submitted of the application to beneficial use of 80 acre feet per annum of the waters of an un-named stream in accordance with the terms and conditions of Permit No. R-913 heretofore issued by the Department of Reclamation of the State of Idaho.

The name and postoffice address of the person or corporation holding said permit are Herman E. Huettig, Hazelton, Idaho.

The use to which said water has been applied is irrigation.

The amount applied to beneficial use is 80 acre feet per annum.

The place where said water is used the NW $\frac{1}{4}$ NW $\frac{1}{4}$ and SW $\frac{1}{4}$ NW $\frac{1}{4}$, Section 28, and the NE $\frac{1}{4}$, the N $\frac{1}{2}$ NW $\frac{1}{4}$ and SE $\frac{1}{4}$ NW $\frac{1}{4}$, Section 29, all in Township 10 South, Range 20 East, B. M., Jerome County, Idaho.

The name of the canal or ditch or other works by which said water is conducted to such place of use is un-named.

The right to take water from such works is based upon Permit No. R-913.

The source of supply from which such water is diverted is an un-named stream.

The date of priority which said user is prepared to establish is July 1, 1953.

MARK R. KULP,
State Reclamation Engineer.

8-4-55 R-913 7-14-4tc

AFFIDAVIT of PUBLICATION

State of Idaho, }
County of Jerome } SS.

W. J. MacKnight, being first duly sworn, deposes and says that he is the printer (publisher) of the Jerome North Side News, a newspaper published every week in Jerome, County of Jerome, State of Idaho; that said newspaper has been continuously and uninterruptedly published for a period of seventy-eight consecutive weeks prior to the first publication of the annexed notice, and is a newspaper qualified to publish legal notices as provided by act of the 1919 session of the legislature of the State of Idaho. known as House Bill 145; that the annexed advertisement was published once

each week for 5 consecutive issues in said newspaper proper and not in a supplement; that the date of the first publication

of said advertisement was on the 14th day of July,

1955, and the date of the last publication was on the 11th

day of August, 1955.

W. J. MacKnight

Subscribed and sworn to before me this 11th

day of August, 1955.

(SEAL)

Richard H. Seeley
NOTARY PUBLIC

JEROME NORTH SIDE NEWS COST OF PUBLICATION

Number of Lines in Notice 38

Number of Insertions 5

38 Lines at 13c 5.70

152 Lines at 60c \$15.20

TOTAL COST \$20.90

(COST COMPUTED AT RATE OF 13c PER LINE FOR FIRST INSERTION,

6c PER LINE FOR ALL SUCCESSIVE INSERTIONS)

COPY OF NOTICE

(State Here)

Notice of Proof Appl.
TITLE OF NOTICE

of Water to Ben. Use.

PLAINTIFF ATTORNEY

Herman E. Huettig
DEFENDANT

Hazelton
PLAINTIFF

R. H. Seeley
BILL TO

NOTICE OF PROOF APPLICATION OF WATER TO BENEFICIAL USE

Notice is hereby given that at 10 a.m. on the 12th day of Aug., 1955, at Jerome, County of, Jerome, State of Idaho before Richard H. Seeley, a notary public, proof will be submitted of the application to beneficial use of 80 acre feet per annum of the waters of an un-named stream in accordance with the terms and conditions of Permit No. R-913 heretofore issued by the Department of Reclamation of the State of Idaho.

The name and postoffice address of the person or corporation holding said permit are Herman E. Huettig, Hazelton, Idaho.

The use to which said water has been applied is irrigation.

The amount applied to beneficial use is 80 acre feet per annum.

The place where said water is used the NW $\frac{1}{4}$ NW $\frac{1}{4}$ and SW $\frac{1}{4}$ NW $\frac{1}{4}$, Section 28, and the NE $\frac{1}{4}$, the N $\frac{1}{4}$ NW $\frac{1}{4}$ and SE $\frac{1}{4}$ NW $\frac{1}{4}$, Section 29, all in Township 10 South, Range 20 East, B. M., Jerome County, Idaho.

The name of the canal or ditch or other works by which said water is conducted to such place of use is un-named.

The right to take water from such works is based upon Permit No. R-913.

The source of supply from which such water is diverted is an un-named stream.

The date of priority which said user is prepared to establish is July 1, 1953.

MARK R. KULP,
State Reclamation Engineer.


R-913 7-14-5tc

Nº 153


R-913

PLAN OF STORAGE AREA AND DAM SITE

Contour interval = 2 ft.
Scale: 1" = 300 ft.



PLAN
SCALE - 1" = 50'



COMPACTED VOLUME
Embankment + 1800 c.y.
Cut-off 150 c.y.


EXCAVATION VOLUMES
Spillway: Earth c.y.
Rock c.y.
Cut-off: Earth c.y.
Rock c.y.

CONCRETE VOLUMES
Encasement & Collars 6.0 c.y.
Intake structure and Pedestals c.y.
Outlet structure 4.4 c.y.


PIPE BARREL
10 inches diameter
68 lineal feet

* EMBANKMENT ENLARGEMENT

SPILLWAY DESIGN DISCHARGE 75 c.f.s.



STORAGE CAPACITY - 150 Acres Feet
Hazelton R.20E.



WATERSHED & LOCATION MAP

HERMAN HUETTIG DAM
U.S. DEPARTMENT OF AGRICULTURE
SOIL CONSERVATION SERVICE

PACIFIC REGION

RECOMMENDED <i>James E. Miller</i>	APPROVED:
ENGINEERING APPROVAL <i>M.H. Wilkins</i>	PROF. OWNER
COMPILED <i>Ray</i>	DATE 6/15/54
TRACED <i>Ray</i>	DRAWING NO. 7-N



Scale: Vert & Horiz. 1" = 10 feet




Top of new dam on face of old section




Scale: Vert. 1" = 1 ft.
 Horiz. 1" = 1 ft.




SECTION B
THRU OUTLET DITCH



SECTION X



Scale - 1" = 5'



SECTION X

SPILLWAY SECTIONS

Spillway capacity = 75 c.f.s

HERMAN HUETTIG DAM

U. S. DEPARTMENT OF AGRICULTURE
SOIL CONSERVATION SERVICE

PACIFIC REGION

APPROVED:

RECORDED:
Juni E. Miller
COLUMBIAN APPRAISE

Ms. B. 2. 1.

COMPILED

any any

6/15/54
7-N-

7-N-2

HERMAN HUETTIG DAM

I - This proposed dam is, in reality, the enlargement of an existing inadequate structure. The existing maximum height is 12.0 ft. along the center line of the top of the dam and impounds 15.85 acre ft. of water when the water level reaches the 15 ft. contour level. At this level the area impounded is 7.9 acres. It is located on an unnamed water-way and the chief source of water is waste water from land irrigated by deep wells. Mr. Huettig used this reservoir during the past irrigation season to supplement his own irrigation water with waste water from approximately 1740 acres of irrigated lands above him that are irrigated from deep wells (9). He has a ⁵⁰ ~~5~~ H.P. electric motor and pump that pumps directly into the main line of his sprinkler system. This pump is rated to deliver ¹²⁵ ~~5~~ inches. During the past season this pump operated continuously from June 1 to September 10. At the end of this period the water supply in the reservoir was practically exhausted. Therefore it is contemplated that this reservoir will not be used to hold water of any consequence except during the irrigation season.

II - Location:

This dam is located in the NW $\frac{1}{4}$ NW $\frac{1}{4}$ Section 29, T. 10 S., R. 20 E. S. 1. Jerome County, Idaho.

III - Outlet Conduit:

The outlet conduit now consists of 32 ft. of 10" Helcor pipe with a 10" #101 Calco Slide Headgate. It is contemplated to lengthen this outlet 36 ft. to the toe of the new construction on the dam. This new pipe will be encased in concrete a minimum of 4" and 2 $\frac{1}{2}$ ' cut-off collars will be spaced at 12' intervals on this new section. These collars will be battered from 6" to 10" to insure better compaction around the tube. The only function for this outlet conduit would be to drain the reservoir and this can also be accomplished by pumping. The spillway will be designed to handle all excess water.

IV - Spillway:

The present provision for spilling excess water is inadequate. The new spillway will be 10' wide and at elevation 15.0. Concrete walls 5' high with a 10' x 10' apron will be constructed. The channel below the apron will be rip-rapped with rock to stabilize the channel at slopes of $1\frac{1}{2}:1$ and hand placed.

The above provisions will provide for a drainage area of 5 to 6 square miles, which for this area, the rate of run-off will not exceed 75 c.f.s.


The above is based on the Idaho map showing zones of equal run-off.

V - Foundation and Cut-off:

Unfavorable foundation material was found in the vicinity of 1 + 75 consisting of lime and volcanic ash material over rock out-croppings.

It was decided to blanket this area by turning the dam approximately 100° towards the east and thus eliminate the possibility of piping through this layer. A cut-off trench with a 10' bottom width, $1\frac{1}{2}:1$ sides, and 2 ft. deep will be made to remove excess vegetative matter and organic matter. This will be refilled with borrow material consisting of clay loam.

NAME OF APPLICANT.....HERMAN L. HUETTIG.....



Permit Map No. R-913
As Approved
JUL 9 1953
MARK R. KULP
State Reclamation Engineer

SCALE: 2 Inches Equal 1 Mile. Draw Plan In Ink.

R-913

State of Idaho
License and Certificate of Water Right

Water License No. R-913 Amount 30 acre feet
Water District No. Priority July 1, 1953

THIS IS TO CERTIFY that HERMAN E. HUETTIG
of Hazelton, Idaho, made application for a permit to appropriate the
public waters of the State of Idaho, dated July 1, 19 53 ; that Permit No. R-913
was issued under said application; that Certificate of Completion of works, with a ^{storage} ~~reservoir~~ capacity of
30 ~~acre~~ ^{acre} feet, was issued thereunder on November 23, 19 55, showing that said works
were completed on the 24th day of June, 19 55 ; and that on the 12th
day of August, 19 55 ,
HERMAN E. HUETTIG

of Hazelton, State of Idaho, made proof to the satisfaction of the
State Reclamation Engineer of Idaho, of the right to use the waters of an un-named stream
the stone and
, a tributary of Snake River, for the purpose of irrigation
, under Use Permit No. R-913 of the Department of Reclamation
and that said right to the use of said waters has been perfected in accordance with the laws of Idaho,
and is hereby confirmed by the State Reclamation Engineer of Idaho and entered of record in Volume
9 of Licenses at page 5618, on the 23rd day of November, 1955 ;
The right hereby confirmed dates from July 1, 19 53 ;
The Point of ^{Outlet} ~~Diversion~~ is located

in the NW 1/4 NW 1/4, Sec. 29, Tp. 10 S., R. 20 E., B. M. Jerome County

That the amount of water to which such right is entitled and hereby confirmed, for the purposes
aforesaid, is limited to an amount actually needed and beneficially used for said purposes, and shall
not exceed thirty (30) ~~cubic feet per second~~ acre feet per annum.

Description and location of use:

Twp.	Range	Sec.	Forty-acre Tract	No. Acres Described in Permit	No. Acres Actually Irrigated
10 S.	20 E.	28	NW $\frac{1}{4}$ NW $\frac{1}{4}$	40	40
			SW $\frac{1}{4}$ NW $\frac{1}{4}$	40	40
		29	NE $\frac{1}{4}$ NE $\frac{1}{4}$	40	40
			NW $\frac{1}{4}$ NE $\frac{1}{4}$	40	40
			SW $\frac{1}{4}$ NE $\frac{1}{4}$	40	40
			SE $\frac{1}{4}$ NE $\frac{1}{4}$	40	40
			NE $\frac{1}{4}$ NW $\frac{1}{4}$	40	40
			NW $\frac{1}{4}$ NW $\frac{1}{4}$	40	40
			SE $\frac{1}{4}$ NW $\frac{1}{4}$	40	40
					<u>40</u>
Number of Acres Actually Irrigated				360	

The right to the use of the water aforesaid hereby confirmed is restricted to the lands or place
of use herein described, as provided by the laws of Idaho.

WITNESS the seal and signature of the State Reclamation Engineer, affixed at Boise, Idaho, this
23rd day of November, 19 55 .

MARK R. KULP
State Reclamation Engineer.

(SEAL)

State of Idaho

License and Certificate of Water Right

Water License No. 24261

Amount 2.5 second feet

Water District No.

Priority July 1, 1953

THIS IS TO CERTIFY that HERMAN E. HUETTIG
of Hazelton, Idaho, made application for a permit to appropriate the
public waters of the State of Idaho, dated July 1, 1953; that Permit No. 24261
was issued under said application; that Certificate of Completion of works, with a carrying capacity of
3 second feet, was issued thereunder on November 23, 1955, showing that said works
were completed on the 24th day of June, 1955; and that on the 12th
day of August, 1955,
HERMAN E. HUETTIG
of Hazelton, State of Idaho, made proof to the satisfaction of the
State Reclamation Engineer of Idaho of the right to use the waters of an un-named stream
(waste water), a tributary of Snake River, for the purpose of irrigation
, under Use Permit No. 24261 of the Department of Reclamation
and that said right to the use of said waters has been perfected in accordance with the laws of Idaho,
and is hereby confirmed by the State Reclamation Engineer of Idaho and entered of record in Volume
9 of Licenses at page 5617, on the 23rd day of November, 1955;
The right hereby confirmed dates from July 1, 1953;
The Point of Diversion is located
in the NW ¼ NW ¼, Sec. 29, Tp. 10 S., R. 20 E., B. M. Jerome County
That the amount of water to which such right is entitled and hereby confirmed, for the purposes
aforesaid, is limited to an amount actually needed and beneficially used for said purposes, and shall
not exceed 2.5 cubic feet per second.

Description and location of use:

Twp.	Range	Sec.	Forty-acre Tract	No. Acres Described in Permit	No. Acres Actually Irrigated
10 S.	20 E.	28	NW ¼ NW ¼	40	40
			SW ¼ NW ¼	40	40
		29	NE ¼ NE ¼	40	40
			NW ¼ NE ¼	40	40
			SW ¼ NE ¼	40	40
			SE ¼ NE ¼	40	40
			NE ¼ NW ¼	40	40
			NW ¼ NW ¼	40	40
			SE ¼ NW ¼	40	40
			Number of Acres Actually Irrigated		360

The right to the use of the water aforesaid hereby confirmed is restricted to the lands or place
of use herein described, as provided by the laws of Idaho.

WITNESS the seal and signature of the State Reclamation Engineer, affixed at Boise, Idaho, this
23rd day of November, 1955.

MARK R. KULP

State Reclamation Engineer.

(SEAL)

APPLICATION FOR PERMIT

To Construct a Reservoir and Appropriate and Store
The Public Waters of the State of Idaho

Application No. R 32056
Permit No. R 913

36-2701

1. Name of Applicant: HERMAN E. HUETTIG

Postoffice address: Hazelton

County Jerome

State Idaho

I. If applicant is a corporation, give:

(a) Date and place of incorporation:

(b) Amount of Capital Stock: \$

(c) Amount paid in: \$

(d) Names and addresses of directors:

II. The financial resources of the corporation are:

(a) Cash on hand: \$

(b) Treasury Stock: \$

(c) Bonds to be issued: \$

(d) Other resources:

2. Quantity of water to be stored: 80 acre feet per annum.

3. Source of water supply is Unnamed stream (Creek) (River) (Spring), a tributary of Snake River.

4. The outlet of the proposed reservoir is located (bearing) feet, distant from the corner of Section , Township , Range , B. M. and is in the NW ¼ of NW ¼ of Section 29 , Township 10 S. , Range 20 E. , B.M. County of Jerome

5. Fill out either (a) or (b).

(a) The reservoir is located in the channel of Unnamed stream (Creek) (River).

(b) The reservoir is to be filled through a feeder canal, the point of diversion for which is located (bearing) feet distant from the corner of Section , Township , Range , B. M., and is in the ¼ of ¼ of Section , Township , Range B. M.; width at bottom feet, width at top

feet, depth of water feet; average grade per mile feet; Capacity cubic feet per second.

6. (a) The area of the high water line of the reservoir is acres.

(b) The reservoir capacity is 80 acre feet.

7. Height of reservoir dam 15 feet, length at top 200 feet, length at bottom 100 feet, size of outlet 10" round feet by feet. The dam is to be constructed of materials as follows: Earth, lined with lava rock.

(If height will exceed 10 feet, plans must be approved by Department of Reclamation, before beginning construction.)

8. (a) Will water stored in reservoir be diverted to canal or aqueduct, thence to land to be irrigated without commingling with natural flow of (Creek) (River)? Water will be pumped directly from reservoir to land.

(b) Water stored in reservoir will be carried in the channel of Not applicable (Creek,) (River,) a distance of miles to point of diversion located (bearing) feet, distant from the corner of Section Township , Range , B. M., and in the ¼ of ¼ of Section Township , Range B. M.

9. (a) Area of watershed above dam site Two square miles

(b) Estimated maximum flow of stream 4.0 cubic feet per second.

10. Water is to be used for irrigation purposes.

11. If for mining, milling, power or manufacturing purposes give:

(a) Point of use of water (bearing) feet, distant from Corner of Section , Township , Range B. M. and is in the ¼ of ¼ of Section , Township , Range , B. M.

(b) Amount of power generated: H. P., under feet head.

(c) Water is to be returned to (Creek) (River) (Spring) at a point (bearing) feet distant from the corner of Section , Township , Range , B. M. in the ¼ of ¼ of Section , Township , Range , B.M.

12. Water stored in accordance with this Permit will be carried to place of use through a canal heretofore constructed under the terms of Permit No. , which is hereby referred to and made a part hereof.

13. Kind of diversion works: None

(Dam, canal, flume, pipe, etc.)

14. Height of diversion dam: None feet, length at top feet, length at bottom feet. The dam is to be constructed of materials as follows:

(If height will exceed 10 feet, plans must be approved by Department of Reclamation, before beginning construction.)

15. Size of headgate: Width None feet, Height feet.

16. Diversion Canal: Width at bottom none feet, width at water line feet, depth of water feet, Dimensions of Flume feet.

Diameter of Pipe inches; Length of Conduit miles. Average grade per mile feet.

17. Estimated cost of Works: Storage Works: \$ 500.00 Diversion Works: \$ None

18. Time required for completion of work Two years.

19. Time required for complete application of water to proposed beneficial use is None years.

20. The land to be irrigated is described in the following tabulation:

(Give Irrigable acreage in each 40-acre subdivision.)

Twp.	Range	Sec.	NE $\frac{1}{4}$				NW $\frac{1}{4}$				SW $\frac{1}{4}$				SE $\frac{1}{4}$				Totals
			NE $\frac{1}{4}$	NW $\frac{1}{4}$	SW $\frac{1}{4}$	SE $\frac{1}{4}$	NE $\frac{1}{4}$	NW $\frac{1}{4}$	SW $\frac{1}{4}$	SE $\frac{1}{4}$	NE $\frac{1}{4}$	NW $\frac{1}{4}$	SW $\frac{1}{4}$	SE $\frac{1}{4}$	NE $\frac{1}{4}$	NW $\frac{1}{4}$	SW $\frac{1}{4}$	SE $\frac{1}{4}$	
10 S	20 E	28						40	40										80
		29	40	40	40	40	40	40		40									280

Total Number of Acres to be Irrigated 360

21. Existing rights and/or valid permits appurtenant to lands described in Sec. 20 are 121 shares of Twin Falls North Side Canal Co's. water right for lands in Section 29, Lands in Section 28 new lands without a present water rights.

Remarks:

Applicant will pump directly out of reservoir using pump and sprinkler system.

BE IT KNOWN That the undersigned hereby makes application for permit to construct a reservoir and appropriate and store the public waters of Idaho as herein set forth, and that the enclosed map is hereby made a part of this application.

HERMAN E. HUETTIG

Applicant.

By

Agent.

Date of first receipt at Department of Reclamation: 3:00 p.m. July 1, 1953

Returned to applicant for correction

Corrected application received

APPROVAL OF STATE RECLAMATION ENGINEER

The number of this permit is R 913

Recorded in book R 4, page 913 Approved July 3, 1953

This is to certify that I have examined the within application for a permit to construct a reservoir and appropriate and store the public waters of the State of Idaho, and hereby approve the same, subject to the following limitations and conditions:

Bond in the sum of \$, to be filed on or before

Work to begin on or before September 3, 1953 and to continue diligently and uninterruptedly to completion, unless temporarily interrupted by circumstances over which the permit holder has no control.

One fifth of the work above specified to be completed on or before July 3, 1954

The whole of said work to be completed on or before July 3, 1955

Beneficial use of water stored in accordance herewith, to be made on or before July 3, 1955

Witness my hand this 3rd day of July

, 1953.

MARK R. KULP
State Reclamation Engineer.

IN TESTIMONY WHEREOF, We, LEN JORDAN

IRA H. MASTERS, Secretary of State of the State of Idaho, have caused this instrument to be executed in

the name of the State of Idaho, and caused the Great Seal of the State of Idaho to be hereunto affixed, this 3rd day of

July, 1953.

Countersigned:

STATE OF IDAHO

(SEAL)

By LEN JORDAN

By IRA H. MASTERS

Secretary of State.

Governor.

APPROVAL OF STATE RECLAMATION ENGINEER

I, Mark R. Kulp, State Reclamation Engineer of the State of Idaho, hereby extend the time for the making of proof of Beneficial Use under Permit to Appropriate the Public Waters of the State of Idaho, No. R-913, to September 3, 1955.

Witness my hand this 8th day of July, 1955.

MARK R. KULP
State Reclamation Engineer

Permit No. R-913
CERTIFICATE OF COMPLETION OF WORKS

TO ALL WHOM IT MAY CONCERN:

This is to certify that HERMAN E. HUETTIG of Hazelton, County of Jerome, and State of Idaho, the holder of Permit No. R-913, issued upon Application No. R-32050, bearing date of priority of July 1, 1953, authorizing the construction of a reservoir, with the right to appropriate and store 80 acre feet per annum of the waters of an un-named stream a tributary of Snake River, in the County of Jerome, State of Idaho, for irrigation purposes, has fully complied with the provisions of the laws of the State of Idaho relating to the proof of completion of the works set out and described in said Permit; that said works include a dam and reservoir adequate for the storage of 30 acre feet of water per annum, with adequate diversion works and conduit to the reservoir, and a conduit capable of conducting said water to the place of intended use; that the point of outlet of said reservoir is located in the NW $\frac{1}{4}$ of the NW $\frac{1}{4}$ of Section 29, Township 10 South, Range 20 E., and that the place of use, or the lands proposed to be irrigated by the use of said water, are described as follows, to-wit: W $\frac{1}{2}$ NW $\frac{1}{4}$ Section 28; NE $\frac{1}{4}$, N $\frac{1}{2}$ NW $\frac{1}{4}$, SE $\frac{1}{4}$ NW $\frac{1}{4}$ Section 29; All in Township 10 South, Range 20 East, B.M.

Witness my hand this 23rd day of November, 1955.

MARK R. KULP
State Reclamation Engineer

Proof of completion of works made August 12, 1955
Certificate of Completion of Works issued November 23, 1955.

LICENSE ISSUED FOR 30 ^{acre ft.} SEC. FT.
P-5618

March 6, 1956

RE: Permits Nos. R-913 - 24261

Mr. Richard H. Seeley
Attorney At Law
Jerome, Idaho

Dear Mr. Seeley:

In answer to your inquiry of February 18, 1956, relative to the status of Permits Nos. R-913 and 24261. The status of said Permits is as follows:

Both Permits have gone to license.

Permit No. 24261 - License No. 24261
Issued to Herman E. Huettig of Hazelton, Idaho
Source of supply, un-named stream, waste water
Amount issued by License, 2.5 cubic feet per second
Priority, July 1, 1952
Point of Diversion, NW¹/₄ NW¹/₄, Section 29, Twp. 10 South,
Range 29 East, B. M.
Place of use, W¹/₂ NW¹/₄ of Section 28 and the NE¹/₄, NW¹/₄,
E¹/₂ NW¹/₄, Sec. 29, Twp. 10 South, Range
29 East, B. M.
License issued, November 5, 1955.

- - - - -

Permit No. R-913 - License No. R-913
Amount issued in License, 30 acre feet
Priority, July 1, 1953
Point of Diversion and Place of Use, same as listed under
License No. 24261.

Very truly yours,

MARK R. KULP
State Reclamation Engineer
By

T:ou

Roy W. Thompson
Office Manager

R-913

RICHARD H. SEELEY
ATTORNEY AT LAW
JEROME, IDAHO

February 18, 1956

Mr. Mark R. Kulp
Department of Reclamation
State House
Boise, Idaho

RECEIVED
FEB 20 1956
Department of Reclamation

Dear Sir:

Will you please advise me as to the status of
the Huettig water filings, Permits No. R 913 and 24261?

Yours very truly,

Richard H. Seeley

R-913

**NOTICE OF PROOF APPLICATION OF
WATER TO BENEFICIAL USE**

Notice is hereby given that at 10 a.m. on the 12th day of Aug., 1953, at Jerome, Co. Jerome, State of Idaho, before Richard H. Sealey, a notary public, proof will be submitted of the application to beneficial use of 80 acre feet per annum of the waters of an unnamed stream in accordance with the terms and conditions of Permit No. R-813 heretofore issued by the Department of Reclamation of the State of Idaho.

The name and postoffice address of the person or corporation holding said permit are Herman E. Sealey, Hazelton, Idaho.

The use to which said water has been applied is irrigation.

The amount applied to beneficial use is 80 acre feet per annum.

The place where said water is used is the NW $\frac{1}{4}$ NW $\frac{1}{4}$ and SW $\frac{1}{4}$ NW $\frac{1}{4}$, Section 28, and the NE $\frac{1}{4}$, the NW $\frac{1}{4}$ NW $\frac{1}{4}$ and SE $\frac{1}{4}$ NW $\frac{1}{4}$, Section 29, all in Township 10 South, Range 20 East, E. M., Jerome County, Idaho.

The name of the canal or ditch or other works by which said water is conducted to the place of use is unnamed.

The right to take water from such works is based upon Permit No. R-813.

The source of supply from which such water is taken is an unnamed stream.

The date on which said user is prepared to submit proof is Aug. 1, 1953.

R-913
7-14-4tc
Herman E. Sealey, Reclamation Engineer.

October 14, 1955

RE: Permits Nos. 24261 and R-913

Mr. Herman Huettig
Hazelton
Idaho

Dear Mr. Huettig:

State law requires inspection in connection with any permit being brought to license in the State of Idaho.

I intend to make inspection in connection with Permits Nos. 24261 and R-913 on Thursday, October 20, in the morning.

Please be prepared to accompany me on the inspection.

Yours truly,

MARK R. KULP
State Reclamation Engineer
By

E. N. Humphrey
Deputy State Reclamation Engineer

H:hll

R-913

✓
August 18, 1955

RE: Permits Nos. 24251 - R-913

Mr. Richard H. Seeley
Attorney At Law
Jerome, Idaho

Dear Mr. Seeley:

We acknowledge receipt of your letter of August 15, 1955, enclosing depositions of Herman E. Huettig and two witnesses also Affidavits of Publication in the North Side News all in proof of Beneficial Use on the above numbered Permits.

Before final action is taken the law requires that a field examination be made by an engineer from this Department.

We cannot say just when this examination will be made, but our field engineer will contact Mr. Huettig at the time he makes the examination in order that he may arrange to show him over the ground.

Very truly yours,

MARK R. KULP
State Reclamation Engineer
By

Chief Clerk

A:OU

CC: Mr. Herman E. Huettig

R 913

November 29, 1955

RE: Permits Nos. 24261 & R-913

Mr. Herman E. Huettig
Hazelton
Idaho

Dear Mr. Huettig:

We enclose Certificate of Completion of Works also License and Certificate of Water Right issued on Permit No. 24261 confirming your right to the use of 2.5 second feet from an un-named stream (waste water) with priority of July 1, 1953, and point of diversion in the N¹/₄ NW¹/₄ Section 29, Township 10 South, Range 20 East, B.M. for irrigation of land in the W¹/₂ NW¹/₄ Section 28; NE¹/₄, N¹/₂ NW¹/₄ and SE¹/₄ NW¹/₄ Section 29, same Township and Range.

We also enclose Certificate of Completion of Works and License and Certificate of Water Right issued on Permit No. R-913 confirming your right to construct a reservoir and store and appropriate 30 acre feet of water from an un-named stream with point of outlet in the N¹/₄ NW¹/₄ Section 29, Township 10 South, Range 20 East, B.M., for irrigation of the same land as described in Permit No. 24261.

We also enclose departmental receipt No. 27707 for the \$10.00 fees for Certificates of Completion of Works and No. 27706 for the \$18.00 license fee.

Very truly yours,

MARK R. KULP
State Reclamation Engineer
By

Chief Clerk

Ashll
Enc.

R-913

November 15, 1955

RE: Permits Nos. 24261 and R-913

Mr. Herman E. Huettig
Hazelton
Idaho

Dear Mr. Huettig:

We now have on file the report of our field engineer on examination for beneficial use on the above numbered Permits.

The report on Permit No. 24261 shows that you have used 125 inches from an un-named stream in the NW¹/₄ Section 29, Township 10 South, Range 20 East, B.M. for the irrigation of 360 acres in the W¹/₂ NW¹/₄ Section 28; NE¹/₄, N¹/₂ NW¹/₄ and SE¹/₂ NW¹/₄ Section 29, same Township and Range.

A License can, therefore, be issued on this Permit for 125 inches or 2.5 second feet upon receipt of the statutory license fee amounting to \$18.00. This is at the rate of \$2.00 for each 40 acre subdivision in which the land is located.

The report on Permit No. R-913 shows that your reservoir is capable of storing 30 acre feet of water which has been used to irrigate the same land as described in Permit No. 24261. A License will be issued on Permit No. R-913 for 30 acre feet per annum with no additional license fee.

Very truly yours,

MARK R. KULP
State Reclamation Engineer
By

Chief Clerk

A:hll

R-913

STATE OF IDAHO
DEPARTMENT OF RECLAMATION
BOISE

REPORT OF ENGINEER

PERMIT NO. R-918

REPORT ON PROOF OF Beneficial Use

HERMAN E. HUETTIG, Hazelton, Idaho

30 ac ft
min

app. 80 a. 7.
c/w 30 a. 6.


300 acres

9-403

Same as 24261

TO HAZELTON

R-20E.



Subdivisions = nine
Area = 360 acres
Q = 30 acre feet.

See Permit 24261

STATE OF IDAHO
DEPARTMENT OF RECLAMATION
BOISE, IDAHO
REPORT OF ENGINEER

Permit No. R-913This proof is for Beneficial Use

In Water District No. _____

1. Name of applicant Herman E. Huettig, Hazelton, Idaho2. Source of water supply: An un-named stream
outlet3. Location of point of ~~diversion~~: Is in the NW $\frac{1}{4}$ NW $\frac{1}{4}$ of Section 29T. 10 S. R. 20 E. County of Jerome

4. Describe works as they exist, giving dimensions and capacities of same: This is a small reservoir built to catch waste water from adjoining farms to the East. Most of the water is well water that is being pumped and wasted. The dam is 200' long by 18' wide on the crest by 15' high. The spillway is 9' wide by 3' high by 18' long. The top 8' has been rip rapped with large lava rocks taken from a cellar that was being dug by a neighbor. Free board is 4'. Capacity of the reservoir is approximately 30 acre feet. Water is diverted onto the fields by means of a Goulds centrifugal pump 5" in by 5" out into a sprinkler system operated by a 50 hp Westinghouse lifeline motor. Serial No. S1462998. Highest lift is 45'. See companion Permit No. 24261.

5. Water is used for: Irrigation6. State whether or not water has been turned into works of diversion: Yes

7. List legal subdivisions of lands to be irrigated. If proof is for beneficial use, give exact number of acres under cultivation in each forty-acre tract. (Describe manner and place of use if other than irrigation):

N $\frac{1}{2}$ NW $\frac{1}{4}$ Section 28;NE $\frac{1}{4}$, N $\frac{1}{2}$ NW $\frac{1}{4}$, SE $\frac{1}{4}$ NW $\frac{1}{4}$ Section 29;Twp. 10 South, Range 20 East, B. M.See the map

(Submit map on attached plat, showing location and details of above description.)

8. What large stream would the water here appropriated finally reach? _____

Remarks: This is one of the newly developed farms in the Hazelton-Butte area that has purchased 161 shares of the Jerome North Side stock and is developing the waste water from other lands to the East. This is a general farm raising hay, grain, potatoes and beets.

This examination was made on the 20th day of October, 19 55(Signed) E. N. Humphrey Examiner.

R-913

A.B. Switches
480V. meters on
poles to W.
no protest

INSTRUCTIONS TO EXAMINERS

1. Always carefully note the location of the point of diversion and accurately plat same.
2. When proof is for beneficial use, carefully check up the number of acres actually irrigated in each forty and accurately plat same.
3. Make a map showing the correct location of streams and ditches, and the irrigated lands, and any adjacent permanent landmarks, such as towns, lakes, large streams and public roads.
4. If any unusual conditions are discovered, make plain statement of them under remarks.
5. Always see the holder, if possible, and go over the whole ground with him and make your report only upon actual existing facts and conditions.
6. Give general characteristics of soils, topography, and crops raised.

RECEIVED
NOV 14 1955
Department of Reclamation

Herman E. Huettig
Hazelton, Idaho
Permit No. R-913

Examination for Beneficial Use

County Jerome

29-10S.-20E.

Q = 80 Acres Feet

S = Un-named stream (waste water)

P.D. = NW. 1/4, S. 29, T. 10S. - R. 20E

Use = Irrigation

11 laterals 1/4 mi. X 4" X 3"

33 heads 3/16" X 3/32"

Priority = Jul. 1, 1953
Due = Sept. 3, 1955 (Ext.)

Dam 200' l. X 18' w X 15' h
Spillway 9' w X 3' h X 16' l
top 8' rip rap big
lava rock from neighbors
cellar

freeboard 4'

Cap = 30 a. F.

Howells Cent. pump.
5" X 5" into 8" line
8" suction into sump.

1100 gal @ 170' head cap

440V. 50 hp. W. H. Co.
life line motor

#1462998

Lift 45'

**NOTICE OF PROOF APPLICATION OF
WATER TO BENEFICIAL USE**

Notice is hereby given that at 10 a.m. on the 5th day of August, 1953, at Jerome, County of Jerome, State of Idaho, before Richard H. Seeley, a notary public, proof will be submitted of the application to beneficial use of 80 acre feet per annum of the waters of an un-named stream in accordance with the terms and conditions of Permit No. R-913 heretofore issued by the Department of Reclamation of the State of Idaho.

The name and postoffice address of the person or corporation holding said permit are Herman E. Huetting, Hazelton, Idaho.

The use to which said water has been applied is irrigation.

The amount applied to beneficial use is 80 acre feet per annum.

The place where said water is used the NW $\frac{1}{4}$ NW $\frac{1}{4}$ and SW $\frac{1}{4}$ NW $\frac{1}{4}$, Section 28, and the NE $\frac{1}{4}$, the N $\frac{1}{4}$ NW $\frac{1}{4}$ and SE $\frac{1}{4}$ NW $\frac{1}{4}$, Section 29, all in Township 10 South, Range 20 East, B. M., Jerome County, Idaho.

The name of the canal or ditch or other works by which said water is conducted to such place of use is un-named.

The right to take water from such works is based upon Permit No. R-913.

The source of supply from which such water is diverted is an un-named stream.

The date of priority which said user is prepared to establish is July 1, 1953.

Witness my hand and seal of office this 5th day of August, 1953.

7-14-4tc
R-913

**NOTICE OF PROOF APPLICATION OF
WATER TO BENEFICIAL USE**

Notice is hereby given that at 10 a.m. on the 12th day of Aug., 1953, at Jerome, County of Jerome, State of Idaho, before Richard H. Seeley, a notary public, proof will be submitted of the application to beneficial use of 80 acre feet per annum of the waters of an un-named stream in accordance with the terms and conditions of Permit No. R-913 heretofore issued by the Department of Reclamation of the State of Idaho.

The name and postoffice address of the person or corporation holding said permit are [REDACTED]

The use to which said water has been applied is [REDACTED]

The amount applied to beneficial use is 80 acre feet per annum.

The place where said water is used the NW $\frac{1}{4}$ NW $\frac{1}{4}$ and SW $\frac{1}{4}$ NW $\frac{1}{4}$, Section 28, and the NE $\frac{1}{4}$, the N $\frac{1}{4}$ NW $\frac{1}{4}$ and SE $\frac{1}{4}$ NW $\frac{1}{4}$, Section 29, all in Township 10 South, Range 20 East, B. M., Jerome County, Idaho.

The name of the canal or ditch or other works by which said water is conducted to such place of use is un-named.

The right to take water from such works is based upon Permit No. R-913.

The source of supply from which such water is diverted is an un-named stream.

The date of priority which said user is prepared to establish is July 1, 1953.

Witness my hand and seal of office this 12th day of August, 1953.

MARK R. KULP,
State Reclamation Engineer.
8-4-55 R-913 7-14-4tc

THURSDAY, JULY 28, 1955

LEGAL AD

NOTICE OF PROOF APPLICATION OF WATER TO BENEFICIAL USE

Notice is hereby given that at 10 a.m. on the 12th day of Aug., 1955, at Jerome, ~~ome~~ County of Jerome, State of Idaho, before Richard H. Seeley, a notary public, proof will be submitted of the application to beneficial use of 80 acre feet per annum of the waters of an un-named stream in accordance with the terms and conditions of Permit No. R-913 heretofore issued by the Department of Reclamation of the State of Idaho.

The name and postoffice address of the person or corporation holding said permit are Herman E. Huettig, Hazelton, Idaho.

The use to which said water has been applied is irrigation.

The amount applied to beneficial use is 80 acre feet per annum.

The place where said water is used the NW $\frac{1}{4}$ NW $\frac{1}{4}$ and SW $\frac{1}{4}$ NW $\frac{1}{4}$, Section 28, and the NE $\frac{1}{4}$, the N $\frac{1}{2}$ NW $\frac{1}{4}$ and SE $\frac{1}{4}$ NW $\frac{1}{4}$, Section 29, all in Township 10 South, Range 20 East, B. M., Jerome County, Idaho.

The name of the canal or ditch or other works by which said water is conducted to such place of use is un-named.

The right to take water from such works is based upon Permit No. R-913.

The source of supply from which such water is delivered is an un-named stream.

The date of priority which said user is prepared to establish is July 1, 1953.

MARK R. KULP,

State Reclamation Engineer.

7-28 R-913 7-14-4tc

NOTICE FOR PUBLICATION

AFFIDAVIT of PUBLICATION

State of Idaho, }
County of Jerome } SS.

W. J. MacKnight, being first duly sworn, deposes and says that he is the printer (publisher) of the Jerome North Side News, a newspaper published every week in Jerome, County of Jerome, State of Idaho; that said newspaper has been continuously and uninterruptedly published for a period of seventy-eight consecutive weeks prior to the first publication of the annexed notice, and is a newspaper qualified to publish legal notices as provided by act of the 1919 session of the legislature of the State of Idaho, known as House Bill 145; that the annexed advertisement was published once

each week for 5 consecutive issues in said newspaper proper and not in a supplement; that the date of the first publication of said advertisement was on the 14th day of July, 1955, and the date of the last publication was on the 11th day of August, 1955.

W. J. MacKnight
Subscribed and sworn to before me this 11th day of August, 1955.

(SEAL)

Richard H. Sealey
NOTARY PUBLIC

JEROME NORTH SIDE NEWS COST OF PUBLICATION

Number of Lines in Notice 38
Number of Insertions 5
38 Lines at 15¢ 5.70
152 Lines at 60¢ 15.20
TOTAL COST 20.90

(COST COMPUTED AT RATE OF 13c PER LINE FOR FIRST INSERTION.

6c PER LINE FOR ALL SUCCESSIVE INSERTIONS)

COPY OF NOTICE

(State Here)

Notice of Proof Appl.
TITLE OF NOTICE

Water to Ben. Use.
PLAINTIFF ATTORNEY

Herman E. Huntington
DEFENDANT

Hazelton
PLAINTIFF

R. H. Sealey
BILL TO

on the 21st day of Aug., 1955, at Jerome, County of Jerome, State of Idaho, before Richard H. Sealey, a notary public, proof was submitted of the application to beneficial use of 30 acre feet per annum of the waters of an unnamed stream in accordance with the terms and conditions of Permit No. B-913 heretofore issued by the Department of Reclamation of the State of Idaho.

The name and postoffice address of the person or corporation holding said permit are Herman E. Huntington, Hazelton, Idaho.

The use to which said water has been applied is irrigation.

The amount applied to beneficial use is 30 acre feet per annum.

The place where said water is used the NW 1/4 NW 1/4 and SW 1/4 NW 1/4, Section 28, and the NE 1/4, the NW 1/4 and SE 1/4 NW 1/4, Section 29, all in Township 10 South, Range 20 East, B. M., Jerome County, Idaho.

The name of the canal or ditch or other works by which said water is conducted to such place of use is unnamed.

The right to take water from such works is based upon Permit No. B-913.

The source of supply from which such water is drawn is the Snake River.

The date of priority which said user is prepared to establish is July 1, 1953.

Richard H. Sealey,
Notary Public,
State Reclamation Engineer.

R-913 7-14-55

Nº 153

R-913

NOTICE FOR PUBLICATION
NOTICE OF PROOF APPLICATION OF WATER
TO BENEFICIAL USE

Notice is hereby given that at 10 A. M. on the 5th day of August, 1955,
at Hazelton Jerome, County of Jerome, State of Idaho, before
Richard H. Seeley, a notary public, proof will be submitted of the
application to beneficial use of 80 acre feet per annum of the waters of an un-named stream
in accordance with the terms and conditions of Permit No. R-913
heretofore issued by the Department of Reclamation of the State of Idaho.

The name and postoffice address of the person or corporation holding said permit are
Herman E. Huettig, Hazelton, Idaho.

The use to which said water has been applied is irrigation.

The amount applied to beneficial use is 80 acre feet per annum.

The place where said water is used ~~is for irrigation on fall and winter crops of the land situated~~
the NW¹/₄ NW¹/₄ and SW¹/₄ NW¹/₄, Section 28, and the NE¹/₄, the N¹/₂ NW¹/₄ and SE¹/₄
NW¹/₄, Section 29, all in Township 10 South, Range 20 East, B. M., Jerome
County, Idaho.

The name of the canal or ditch or other works by which said water is conducted to such place of use is

un-named.

The right to take water from such works is based upon Permit No. R-913.

The source of supply from which such water is diverted is an un-named stream

The date of priority which said user is prepared to establish is July 1, 1953.

MARK R. KULP

State Reclamation Engineer.

R-913

August 1, 1955

RE: Permits Nos. 24261 & R-913

North Side News
Jerome
Idaho

Gentlemen:

We have checked the notice on the above numbered Permits in the name of Herman E. Huetting appearing in your issue of July 28 and the corrections have still not been made in the name of the place appearing in the first word of the third line in these notices.

In other words the word Jerome is incomplete in Permit No. 24261 and a portion is repeated in the first few lines of Permit No. R-913.

In other words it would appear that the syllable one appearing at the beginning of the third line on Permit No. R-913 should be at the beginning of the third line in Permit No. 24261.

Please make these corrections in your next issue.

Very truly yours,

MARK R. KULP
State Reclamation Engineer
By

Chief Clerk

A:eu

R-913

July 25, 1955

Re: Permits Nos. 24261 & R-913

North Side News
Jerome
Idaho

Gentlemen:

We have checked the notices on the above numbered Permits in the name of Herman E. Huettig appearing in your issue of July 21 and find that none of the corrections in Permit No. R-913 mentioned in our letter of July 18 have been made and in addition, there is another error, namely that in the second and third lines of the notice there is a duplication of the last syllable of the word Jerome.

The other errors noted in our letter of July 18 are as follows:

1. In the ninth line of the notice the Permit No. is R-913 and not R1913.
2. In the first line of the second paragraph the word postoffice is misspelled.
3. The word the in the first line of the fifth paragraph is misspelled.

In Permit No. 24261, the word Jerome at the end of the second line is incomplete.

Please make these corrections in your subsequent issues.

Very truly yours,

HARK R. KULP
State Reclamation Engineer
By

Chief Clerk

A:hl1

R-913

July 18, 1955

RE: Permits Nos. 24261 and R-913

North Side News
Jerome
Idaho

Gentlemen:

We have checked the notices on the above numbered Permits in the name of Herman E. Huetting appearing in your issue of July 14 and find several typographical errors as follows:

1. In the notice on Permit No. R-913, the ninth line of the notice gives the number as R1913 instead of R-913.
2. In the first line of the second paragraph, the word postoffice is misspelled.
3. The word the at the end of the first line of the fifth paragraph is misspelled.
4. In notice on Permit No. 24261, in the next to the last line of the fifth paragraph, the word Township is misspelled.

We are this morning in receipt of a letter from Mr. Richard H. Seeley advising that he has requested that the date for making proof be changed from August 5 to August 12 inasmuch as the notice was not included in your issue of July 7, making it impossible to have the four weeks publication prior to August 5th.

Please make these several corrections in your subsequent issues.

Very truly yours,

MARK R. KULP
State Reclamation Engineer
By

Chief Clerk

Ash11

Richard H. Seeley

R-913

STATE OF IDAHO
DEPARTMENT OF RECLAMATION
BOISE, IDAHO

Re: Permits 24261 & 4-913

Date: July 6, 1955

North Side News

Jerome, Idaho

Gentlemen:

Enclosed you will find ^{two} notice, for publication once a week for four consecutive weeks prior to **August 5, 1955** the date set for proof, the expense of the publication to be paid by the applicant, **Herman E. Huettig** of **Hazelton Idaho**, to whom you should furnish proof of publication on or prior to the date set for proof.

Please acknowledge receipt of this notice, and furnish this office with a copy of the first publication, in order that we may check same.

Very truly yours,

MARK R. KULP

State Reclamation Engineer
By

Chief Clerk

R-913

NOTICE TO ACCOMPANY THIS LETTER MUST BE MADE IN DUPLICATE

(Date) June 29, 1955

(P. O.) Hazelton, Idaho

TO THE STATE RECLAMATION ENGINEER:

Boise, Idaho

Dear Sir:

You are hereby authorized to have the attached notice published at my expense in the
North Side News Jerome,
~~Boise, Idaho~~ ~~Idaho~~ of Hazelton, Idaho, published in
the county in which the works are situated.


Herman E. Huettig

(In case of canals or other works designed to divert and carry more than 50 cubic feet of water per second, the following certificate must be signed by a well-known and competent engineer.)

I hereby certify that the facts set forth in the attached notice are true.

Engineer.

R-913

STATE OF IDAHO
DEPARTMENT OF RECLAMATION
BOISE, IDAHO

Permit No. R-913

Proof of Application of Water to Beneficial Use

Deposition of Holder

Ques. 1. State your name, residence, occupation and postoffice address.

Ans. Name - Herman E. Huettig; residence - Hazelton, Idaho; occupation - farmer; and post office address - Hazelton, Idaho.

Ques. 2. If acting in behalf of corporation, state its name, principal place of business (if a foreign corporation, give name of postoffice of statutory agent), your position with reference to same, and your authority for appearing in its behalf.

Ans. _____

Ques. 3 State number and date of permit, and date of priority you propose to establish under the permit.

Ans. R-913, date - July 3, 1953, date of priority - July 1, 1953.

Ques. 4. State source of water supply and give exact location of point of diversion.

Ans. Un-named stream. Water is diverted from reservoir by pump placed at edge of reservoir near the west side of the NW $\frac{1}{4}$ NW $\frac{1}{4}$, Section 29, Township 10 South, Range 20 East, B. M.

Ques. 5. Describe your works of diversion, and state amount of water they are capable of conveying from point of diversion to place of use, and give name of canal or ditch or other works by which water is conducted to such place of use. If a well, state depth of well, depth and size of casing and depth to water. If pump is used, state discharge of pump and tell how it was measured or determined.

Ans. Water is pumped from reservoir by pump placed on south side of reservoir, directly into pipe and sprinkler system. Discharge of pump is 125 inches measured with 170' head, by actual test; reservoir dam is constructed of earth lined with rock and has conduit outlet and spillway. The works are capable of conveying from point of diversion to place of use.

Ques. 6. State for what purpose water is used and describe place of use. (If for irrigation, name each subdivision in which used, and number of acres in each subdivision that have actually been irrigated with said water.) State whether cultivated or natural meadow land and the nature of all improvements which have been made as a direct result of said use.

Ans. For irrigation purposes, upon cultivated lands, said lands, with number of acres actually irrigated, are described as follows:
W $\frac{1}{2}$ NW $\frac{1}{4}$, Sec 28, Twp. 10 S., R. 20 E., B. M. -- 80 acres;
NE $\frac{1}{4}$, Sec. 29, Twp. 10 S., R. 20 E., B. M. ----160 acres;
N $\frac{1}{2}$ NW $\frac{1}{4}$, Sec. 29, Twp. 10 S., R. 20 E., B. M. - 80 acres;
SE $\frac{1}{4}$ NW $\frac{1}{4}$, Sec. 29, Twp. 10 S., R. 20 E., B. M.- 40 acres;

Said lands have been converted as a direct result of such use from arid to cultivated lands.

R-913

Ques. 7. If for other than irrigation purposes; state how applied, amount of horse power generated, etc.

Ans.

Ques. 8. What is the minimum amount of water required for the purpose specified above?

Ans.

Ques. 9. If you are not the person or representative of the corporation to whom above mentioned permit was originally issued, please state how ownership was acquired by present holder.

Ans.

Ques. 10. State when, how, in what amount and to what extent the water diverted under above mentioned permit has been used.

Ans. Said diverted water has been used during the farming seasons of '53, '54 & '55 upon the lands hereinbefore described, by use of pump and sprinkling equipment, in the amount of 125 inches, and applied upon all of said lands.

Ques. 11. State when, how, in what amount and to what extent waters other than those diverted under the above mentioned permit have been diverted and applied to beneficial use upon the lands herein described. Give full particulars regarding such other appropriations and rights claimed thereunder.

Ans. Also beneficially used is water right evidenced by 161 shares of stock of North Side Canal Co., Ltd., appurtenant to lands in Section 29. & 20. This water is also handled through the ~~reservoir and~~ sprinkling system hereinbefore described, but through separate pump, and not through the reservoir.

(Sign) *Herman E. Huettig*

I hereby certify that the foregoing testimony was read to the above subscribed before its signing, that I believe him to be the person he represents himself to be, and that

said testimony was subscribed and sworn to before me, at my office in Jerome,

County of Jerome, State of Idaho, on this 12th day of August,

A. D. 1955,

Richard H. Sealey
Notary Public

My commission expires 12/17/58

STATE OF IDAHO
DEPARTMENT OF RECLAMATION
BOISE, IDAHO

PERMIT NO. R-913

Proof of Application of Water to Beneficial Use

Deposition of Witness and Completion of Works

The deposition of two witnesses, on this form, taken separately, required in each case.

Ques. 1. State your name, age, residence, occupation and postoffice address.

Ans. George E. Leyer, Jr., 35, Hazelton, farmer, post office address
is Hazelton, Idaho.

Ques. 2. Are you acquainted with Herman E. Huettig, the holder of Permit No. R-913? How long have you known him and where does he reside?

Ans. Yes. I have known him for six years, and know that he resides
on his farm south of Hazelton, Idaho.

Ques. 3. Have you read or heard read said Permit No. R-913, and are you familiar with its provisions and conditions?

Ans. Yes.

Ques. 4. State source of water supply, place of diversion, and describe works for conveying water from point of diversion to place of use.

Ans. Source is an unnamed stream; place of diversion is from reservoir
near the west line of the NW $\frac{1}{4}$ NW $\frac{1}{4}$, Sec. 29, Twp. 10 S., R. 20 E., B. M.;
and works consist of earth filled rock lined dam with outlet and
spillway, reservoir, pump and sprinkling equipment.

Ques. 5. How many second feet of water do you estimate said works will safely conduct to place of use, and how much water have you seen being so conveyed?

Ans. 5 second feet. I have seen at least 4 second feet.

Ques. 6. State for what purpose water is used and at what place. (If for irrigation, give each subdivision in which water has been used and number of acres irrigated in each subdivision.) State whether cultivated or natural meadow land and the nature of all improvements which have been made as a direct result of said use.

Ans. For irrigation purposes, upon cultivated lands, said lands, with
number of acres actually irrigated, are described as follows:
W $\frac{1}{2}$ NW $\frac{1}{4}$, Sec. 28, Twp. 10 S., R. 20 E., B. M. --- 80 acres;
NE $\frac{1}{4}$, Sec. 29, Twp. 10 S., R. 20 E., B. M., --- 160 acres;
N $\frac{1}{2}$ NW $\frac{1}{4}$, Sec. 29, Twp. 10 S., R. 20 E., B. M. --- 80 acres;
SE $\frac{1}{4}$ NW $\frac{1}{4}$, Sec. 29, Twp. 10 S., R. 20 E., B. M. -- 40 acres;
Said lands have been converted as a direct result of such use
from arid to cultivated lands.

R-913

Ques. 7. If for power or other purposes than irrigation, state how water has been applied and to what extent.

Ans. _____

Ques. 8. (If for irrigation) state character of land that has been reclaimed, and give your estimate of the amount of water required for its profitable cultivation.

Ans. Reclaimed land is good agricultural land. Amount of water required for its profitable cultivation is 4 second feet.

Ques. 9. Have you any interest in the works, water or lands above mentioned? If so, in what way and to what extent?

Ans. no.

Ques. 10. State when, how, in what amount and to what extent you have witnessed the application to beneficial use of water diverted under said permit.

Ans. During the farming seasons of '53, '54 & '55,
by pumping from reservoir and distributed through sprinkling system,
and applied to fullest extent of capacity of equipment, as needed on
the lands.

(Signed) George C. Fyler Jr.

I hereby certify that the foregoing testimony was read to the above subscriber before its signing, that I believe him to be the person he represents himself to be, and that said testimony was subscribed and sworn to before me in Jerome,
County of Jerome, State of Idaho, on this 12th day of August,
A. D. 19 55.

Richard H. Seely
Notary Public.

My commission expires 12/17/58

STATE OF IDAHO
DEPARTMENT OF RECLAMATION
BOISE, IDAHO

PERMIT NO. R-913

Proof of Application of Water to Beneficial Use

Deposition of Witness and Completion of Works

The deposition of two witnesses, on this form, taken separately, required in each case.

Ques. 1. State your name, age, residence, occupation and postoffice address.

Ans. Donald R. Johnson, age, 31 years, Hazelton, farmer, Hazelton, Idaho.

Ques. 2. Are you acquainted with Herman E. Huettig, the holder of Permit No. R-913? How long have you known him and where does he reside?

Ans. Yes. I have known him for 9 years, and know that he resides on his farm south of Hazelton, Idaho.

Ques. 3. Have you read or heard read said Permit No. R-913, and are you familiar with its provisions and conditions?

Ans. Yes.

Ques. 4. State source of water supply, place of diversion, and describe works for conveying water from point of diversion to place of use.

Ans. Source is an unnamed stream; place of diversion is from reservoir near the west line of the NW $\frac{1}{4}$ NW $\frac{1}{4}$, Sec. 29, Twp. 10 S., R. 20 E., B. M.; and works consist of earth filled rock lined dam with outlet and spillway, reservoir, pump and sprinkling equipment.

Ques. 5. How many second feet of water do you estimate said works will safely conduct to place of use, and how much water have you seen being so conveyed?

Ans. 5 second feet; have seen at least 4 second feet.

Ques. 6. State for what purpose water is used and at what place. (If for irrigation, give each subdivision in which water has been used and number of acres irrigated in each subdivision.) State whether cultivated or natural meadow land and the nature of all improvements which have been made as a direct result of said use.

Ans. For irrigation purposes, upon cultivated lands, said lands, with number of acres actually irrigated, are described as follows:
W $\frac{1}{2}$ NW $\frac{1}{4}$, Sec. 28, Twp. 10 S., R. 20 E., B. M. --- 80 acres;
NE $\frac{1}{4}$, Sec. 28, Twp. 10 S., R. 20 E., B. M. --- 160 acres;
N $\frac{1}{2}$ NW $\frac{1}{4}$, Sec. 29, Twp. 10 S., R. 20 E., B. M. --- 80 acres;
SE $\frac{1}{4}$ NW $\frac{1}{4}$, Sec. 29, Twp. 10 S., R. 20 E., B. M. --- 40 acres;
Said lands have been converted as a direct result of such use from arid to cultivated lands.

R-913

Ques. 7. If for power or other purposes than irrigation, state how water has been applied and to what extent.

Ans. _____

Ques. 8. (If for irrigation) state character of land that has been reclaimed, and give your estimate of the amount of water required for its profitable cultivation.

Ans. Reclaimed land is good agricultural land. Amount of water required for its profitable cultivation is 4 second feet.

Ques. 9. Have you any interest in the works, water or lands above mentioned? If so, in what way and to what extent?

Ans. no.

Ques. 10. State when, how, in what amount and to what extent you have witnessed the application to beneficial use of water diverted under said permit.

Ans. During the farming seasons of '53, '54 & '55,
by pumping from reservoir and distributed through sprinkling system,
and applied to fullest extent of capacity of equipment, as needed on
the lands.

(Signed) Donald R Johnson

I hereby certify that the foregoing testimony was read to the above subscriber before its signing, that I believe him to be the person he represents himself to be, and that said testimony was subscribed and sworn to before me in Jerome,
County of Jerome, State of Idaho, on this 12 day of August,
A. D. 19 55.

Richard X Seely
Notary Public.

My commission expires 12/17/58

STATE OF IDAHO
Department of Reclamation

Permit No. R913

Application for Extension of Time for Beneficial Use Proof

STATE OF IDAHO }
County of Jerome } ss

Herman E. Huettig, of Hazelton,

State of Idaho, being first duly sworn, upon his oath deposes and says:

That he is the owner and holder of Permit to Appropriate the Public Waters of the State of Idaho, No. R913

That, under the terms and conditions of said permit, proof of beneficial use thereunder was required to be made by July 3, 19 55.

That he has heretofore put to beneficial use 3.0 second feet of water and has irrigated 360 acres.

That, for the following reasons, he is unable to put to beneficial use within the required time the remainder of the water appropriated under his permit, to-wit: publication of notices for beneficial use not completed.

WHEREFORE, He asks that the Commissioner of Reclamation extend the time for the making of proof of beneficial use under said permit to September 3, 19 55.

Subscribed and sworn to before me this 2nd day of July, 19 55.

My commission expires 12/17/58

Herman E. Huettig
Richard H. Deely Notary Public.

Date of receipt at office of Department of Reclamation _____

~~STATE RECLAMATION ENGINEER~~
~~APPROVAL OF COMMISSIONER OF RECLAMATION~~
State Reclamation Engineer

I, Mark R. Kulp, of the State of Idaho, hereby extend the time for the making of proof of Beneficial Use under Permit to Appropriate the Public Waters of the State of Idaho, No. R-913, to September 3, 19 55.

Witness my hand this 8th day of July, 19 55

Mark R. Kulp
State Reclamation Engineer R. 913

✓
July 8, 1955

RE: Permits Nos. 24261 - R-913

Mr. Richard H. Seeley
Attorney At Law
Jerome, Idaho

Dear Mr. Seeley:

We return Approval of the State Reclamation Engineer of Herman E. Huettig's Application for Extension of Time for Beneficial Use proof on the above numbered Permits to September 8, 1955.

These should be attached to the original Permits of which they now form a part.

In reply to your inquiry as to the required number of publications, this Department has considered that publication once a week for four weeks answers the legal requirements.

Very truly yours,

MARK R. KULP
State Reclamation Engineer
By

Chief Clerk

A:cu
Enc.

R-913

July 6, 1955

RE: Permits Nos. 24261 & R-913

Mr. Richard H. Seeley
Attorney at Law
Jerome, Idaho

Dear Mr. Seeley:

We have your letter of July 2 enclosing notices for beneficial use on the above numbered Permits to be made August 5, 1955, and authorization to publish in the North Side News.

We have completed the notice on Permit No. R-913 to show beneficial use to be made on 80 acre feet of water from the unnamed stream which is the amount of storage applied for.

You are correct in assuming that the priority date is the date of filing, or July 1, 1953.

Since these proofs were due July 3, 1955, if the original priority is to be retained, the enclosed application for extension of time for making proof of beneficial use should be executed by Mr. Huettig and returned to this department for approval and record.

We shall send a copy of these notices to the North Side News with instructions to publish once a week for four weeks prior to August 5 and to send Mr. Huettig the affidavits of publication together with statement of costs.

Meanwhile, we enclose the forms of deposition to be executed by Mr. Huettig and two disinterested witnesses in making these proofs.

Very truly yours,

MARK R. KULP
State Reclamation Engineer
By

Chief Clerk

A:hl1
Enc.

R-913

Permit No. R-913

Proof of Completion of Works

DEPOSITION OF HOLDER

Ques. 1. State your name, residence, occupation and postoffice address.

Ans. Herman E. Huettig, Hazelton, Idaho, Farmer, Hazelton, Idaho.

Ques. 2. If acting on behalf of a corporation, state its name, principal place of business, your position with reference to same, and your authority for appearing in its behalf.

Ans.

Ques. 3. State number and date of permit, acre feet of water you claim for storage, and source of same.

Ans. Permit No. R-913, acre feet of water - 30, source - Un-named Stream.

Ques. 4. Under terms of permit construction was required to be completed by July 3, 1955.
19

Ques. 5. Construction was actually completed on the date of May 10, 19 55

Ques. 6. Does the construction fully comply with the specifications? Yes

Ques. 7. Of what material was the dam built? dirt and rock.

Ques. 8. State whether or not the water has been turned into your reservoir, and if so, when and to what extent.

Ans. Yes. It is full.

Ques. 9. The capacity of the reservoir is 30 acre feet.

Ques. 10. The area of the high water line of the reservoir is 7.9 acres.

Ques. 11. The height of the dam above bottom of reservoir is 12 feet, above low water is feet. (will be kept full).

Ques. 12. The dimensions of the spillway are 10' ^{wide} ~~high~~ 5' high and the bottom of the spillway is 6 feet below the top of the dam.

Ques. 13. Dimensions of the reservoir outlet are 10" headgate & pipe.

Ques. 14. Describe the gate and control unit.

Ans. Armco manually controlled gate.

Ques. 15. The reservoir outlet is made of Galvanized steel pipe encased in 4" concrete.

Ques. 16. Is the reservoir filled through a feeder canal? No.

Ques. 17. If so, where is the point of diversion for same?

Ans. 1/4 1/4 Section, Twp. Range

R-913

Ques. 18. Does the feeder canal comply with the specifications in the permit?

Ques. 19. If not, explain

Ques. 20. Cost of constructing feeder canal? \$..... Cost of reservoir? \$.....

Ques. 21. State whether or not the works from reservoir outlet to place of use are fully completed, and whether or not they comply with the specifications in permit. If not, explain.

Ans. Yes.

Ques. 22. Water has ~~(has not)~~ been delivered to place of intended use? Yes

Ques. 23. Give description of dam, state dimensions, and give slope of face both upstream and downstream. Also method and material for protecting against wave action.

Ans. See attached instruments for complete answer to this question and more particular answer to other applicable questions herein. By this reference said attached instruments are made a part of this Deposition.

Ques. 24. State the purpose for which the water is to be used and give the place of use, and if for irrigation, state the number of acres, and give the legal description of same.

Ans. Water to be used for irrigation, through sprinkler system, of 360 acres. Legal description: NW $\frac{1}{4}$ NW $\frac{1}{4}$ and SW $\frac{1}{4}$ NW $\frac{1}{4}$, Sec. 28, and NE $\frac{1}{4}$ and NE $\frac{1}{4}$ NW $\frac{1}{4}$ and NW $\frac{1}{4}$ NW $\frac{1}{4}$, / Sec. 29, all in Twp. 10 S., R. 20 E., B. M., Jerome County, Idaho.

(Sign here)

Herman E. Kuetting

I hereby certify that the foregoing testimony was read to the above subscriber before its signing, that I believe him to be the person he represents himself to be, and that said testimony was subscribed and sworn to before me in Jerome, County of Jerome, State of Idaho, on this 24th day of June, A.D. 19 55.

Richard H. Seely
Notary Public

My commission expires 12/17/58

June 28, 1955

RE: Permits Nos. R-913 - 24261

Mr. Richard H. Sealey
Attorney At Law
Jerome, Idaho

Dear Mr. Sealey:

Note
We have your letter of June 24 enclosing Affidavit of Herman E. Huettig for proof of Completion of Works on the above numbered Permits accompanied by Plans and Specifications and his two checks for \$5.00 each in connection with these proofs.

Before Certificate of Completion of Works can be issued an inspection by a field engineer from this Department will be necessary.

Meanwhile, we enclose the forms of notice in connection with Beneficial Use proofs on these two Permits.

Notice should be made in duplicate on each Permit separately setting the time and place and naming the Notary Public before whom these proofs are to be made.

All four copies of Form 10 to be return to this Department together with two copies of Form 11 which is authorization for us to have each notice published in the designated newspaper at Permit holders expense.

We shall then send a copy of the notices to the designated newspaper with instructions in regard to publishing and shall send you the forms of deposition to be executed by Mr. Huettig and two disinterested witnesses in making these proofs.

Very truly yours,

MARK R. KULP
State Reclamation Engineer
By

A:cu

Chief Clerk

R-913

RICHARD H. SEELEY
ATTORNEY AT LAW
JEROME, IDAHO

July 2, 1955

RECEIVED
JUL 5 1955

Department of Reclamation

Mr. Mark R. Kulp
State Reclamation Engineer
State House
Boise, Idaho

Re: Permit Nos. 24261 & R 913 - Huettig

Dear Sir:

Enclosed you will find Notices, in duplicate, and authorization for their publication, in each of the above. We had planned for publication in the Hazelton paper but its plant was destroyed by fire and I have, therefore, changed the publication authorizations to the Jerome paper.

I have figured the first publication to be in the July 7th issue and for the publication to run five times.

In the notices, I have made the date of priority the same as the date of filing. If it should be date of approval, will you correct? RL

You will note that on the notice pertaining to R 913, I left unfilled certain blanks pertaining to quantity of water claimed and used and source of supply. I haven't been able to figure out if the information desired pertains to the amount of water applied to the land or the storage capacity of the reservoir. I would appreciate it if you would fill in these blanks or furnish me with the proper information.

If you want to return the notices to me, I'll see that they get to the newspaper.

I note that the Approvals on the back of the Applications give July 3, 1955, as beneficial use date. Are we all right on our timing or should we ask for extension of time to submit proof of beneficial use?

If you wish, you may call me at 186, Jerome, collect.


Yours very truly,

Richard H. Seeley


R-913

PLAN OF STORAGE AREA AND DAM SITE

Contour interval = 2 ft.
Scale: 1" = 300 ft.




PLAN
SCALE - 1" = 50'



COMPACTED VOLUME		CONCRETE VOLUMES	
Embankment +	1800 c.y.	Encasement & Collars	6.0 c.y.
Cut-off	150 c.y.	Intake structure and Pedestals	c.y.
EXCAVATION VOLUMES		Outlet structure	4.4 c.y.
Spillway:	Earth c.y.	PIPE BARREL	
Rock	c.y.	10 inches diameter	
Cut-off:	Earth c.y.	68 lined feet	
Rock	c.y.	SPILLWAY DESIGN DISCHARGE	
EMBANKMENT ENLARGEMENT		75 c.f.s.	

STORAGE CAPACITY - Acre Feet
Hazelton R.20E




HERMAN HUETTIG DAM

U.S. DEPARTMENT OF AGRICULTURE
SOIL CONSERVATION SERVICE
PACIFIC REGION

RECOMMENDED J. E. Miller District Engineer	APPROVED:
COMPLETED M. H. Williams District Engineer	DATE 6/15/54
TRACED O. J.	PROJ. OWNER 7-N

CROSS SECTION THRU FILL
STA 1+00

Scale: Vert 8 Horiz 1" = 10 feet



ELEV. IN FEET

Profile of new dam on face of old section

PROFILE ON AXIS OF DAM

Scale: Vert. 1" = 10 ft. Horiz. 1" = 10 ft.

SECTION "A"
THRU INTAKE DITCH

SECTION "B"
THRU OUTLET DITCH

SPILLWAY PROFILE

SPILLWAY SECTIONS

Spillway capacity F. 75 C.F.S.

HERMAN HUETTIG DAM

U.S. DEPARTMENT OF AGRICULTURE
SOIL CONSERVATION SERVICE

PACIFIC REGION

James E. Mullen

APPROVED:

Mr. J. J. Williams

PROF. OWNER

COMPILED BY

DATE 6/15/54

SPECIFICATIONS

HERMAN HEUTTIG DAM North Side SCD - Idaho

Clearing and Stripping

The entire area to be occupied by the structure, the ponded area and borrow pits must be cleared of all trees, brush, logs and other such material which will float, and the material disposed of.

The foundation and borrow pit areas must be stripped of all sod and other vegetable matter to firm mineral soil.

The entire foundation and abutment area shall be left in a roughened condition to provide a good bonding surface.

Cut-off Trench

The cut-off trench shall be excavated into firm impervious material. The side slopes of the trench excavation shall not be steeper than 1:1. The bottom width shall not be less than 10 feet.

Placing of Material

The cut-off trench shall be backfilled with impervious material. The material shall be spread in layers approximately 4 inches thick and properly compacted.

The fill material shall be mineral soil free from all brush, roots, sod or other perishable material. No stones having maximum dimensions of more than 4 inches shall be placed in the compacted portion of the fill. The fill shall be raised in approximately level plane surfaces free from local depressions and humps, ridges or any abrupt differences in elevation. The fill shall be placed in thin layers not to exceed 6 inches and each layer properly compacted.

Portions of the fill which cannot be properly compacted by rolling equipment, such as around structures, shall be compacted by hand operated mechanical or hand tamps.

All fill material and foundation material shall have proper moisture content for good compaction and bonding.

The embankment shall be constructed to lines and grades shown on the plans and staked on the ground; this includes a 10% over-fill to allow for settling.

Outlet Conduit

The excavation for the outlet conduit shall be shaped so as to make a suitable form for the concrete encasement and cut-off collars.

The outlet conduit shall consist of 10-inch corrugated metal pipe encased in concrete with a minimum thickness of 4 inches. Cut-off collars shall extend beyond the conduit 2-1/2 feet and be battered 1:12 from the top down. They shall be placed as shown on the plan.

Herman Meuttig Dam/2

The gate shall be a Calce model 101 or equivalent and placed according to the manufacturer's recommendations and the plans.

Spillway

The approach to the concrete spillway control section shall be excavated according to the plans and stakes on the ground.

The concrete control section of the spillway shall be placed as shown on the plan. The cut-off wall under the control section shall be extended to bedrock. The dimensions of all sections of the spillway shall be as shown on the plans and there shall be a smooth transition between sections.

The section of spillway below the control section shall be shaped and lined with hand placed riprap, concrete or rubble masonry.

Protection

Vegetative cover should be established as soon as possible on the fill. Deep rooted or tap root plants, shrubs or trees should not be allowed to grow on the fill.

✓
April 28, 1955

RE: Permits Nos. 24261 & R-913

Mr. Richard H. Seeley
Attorney at Law
Jerome, Idaho

Dear Mr. Seeley:

We have your letter of April 27 requesting forms and instructions for submitting proof of completion of works in connection with the above numbered Permits.

Proof of completion of works on Permit No. 24261 should be made on Form 6 enclosed and on Permit No. R-913 on Form 15-R.

These should be executed before a Notary Public and returned with the statutory fee of \$5.00 each.

Very truly yours,

MARK R. KULP
State Reclamation Engineer
By

Chief Clerk

A:hll
Enc.

R-913

larger than the one at the old level. The surface of the new
reservoir. The existing maximum height is 12.0 ft. above the center line
of the old level. The existing maximum height is 14.35 above ft. of water when the water
level is raised to 14.35 ft. above the old level. At this level the area inundated
is 4.3 acres. The reservoir is located on an assumed water-way and the chief source
of water is waste water from the irrigation of deep wells. Mr. Mustley
uses this reservoir during the past irrigation season to supplement his own
irrigation water and waste water from a approximately 1740 acres of irrigated
lands. The water is used for irrigated from deep wells (9). He has a ⁵⁰ H.P.
electric motor and pump that pumps directly into the main line of his
irrigation system. This pump is rated to deliver ¹²⁵ inches. During the
past season this pump operated continuously from June 1 to September 10.
At the end of this period the water supply in the reservoir was practically
exhausted. It is contemplated that this reservoir will not be
used to hold water of any consequence except during the irrigation season.

1 - Location:

This area is located in the NW 1/4 Section 29, T. 10 S., R. 20 E., S. 1.
Jerome County, Idaho.

" - United States:

The outlet conduit now consists of 31 ft. of 10" Helcor pipe with a 10" 2101 Galva Steel flange. It is completed in length to this outlet 10 ft. to the top of the new construction on the dam. This new pipe will be encased in concrete a minimum of 4" and 2' cut-off collars will be spaced at 10' intervals on this new section. These collars will be tapered from 4" to 10" to insure better connection around the tube. The only function for this outlet conduit would be to drain the reservoir and this can also be accomplished by pumping. The spillway will be used for this purpose in all cases.

R. 913

IV - Spillway:

The present provision for spilling excess water is inadequate. The new spillway will be 10' wide and at elevation 15.0. Concrete walls 5' high with a 10' x 10' apron will be constructed. The channel below the apron will be rip-rapped with rock to stabilize the channel at slopes of $1\frac{1}{2}:1$ and hand placed.

The above provisions will provide for a drainage area of 5 to 6 square miles, which for this area, the rate of run-off will not exceed 75 c.f.s. The above is based on the Idaho map showing zones of equal run-off.

V - Foundation and Cut-off:

Unfavorable foundation material was found in the vicinity of 1 + 75 consisting of lime and volcanic ash material over rock out-croppings. It was decided to blanket this area by turning the dam approximately 100° towards the east and thus eliminate the possibility of piping through this layer. A cut-off trench with a 10' bottom width, $1\frac{1}{2}:1$ sides, and 2 ft. deep will be made to remove excess vegetative matter and organic matter. This will be refilled with borrow material consisting of clay loam.

✓
April 23, 1955

RE: Permits Nos. 24261 and R-913

Mr. Richard H. Seelley
Attorney at Law
Jerome, Idaho

Dear Mr. Seelley:

In reply to your letter of April 21 inquiring as to the status of the above numbered Permits in the name of Herman E. Huettig.

According to our records, proof of completion of work and beneficial use are due on both these Permits on or before July 3, 1955 and if Mr. Huettig is prepared to make them at that time, we shall be glad to send the necessary forms and instructions upon request.

Very truly yours,

MARK R. KULP
State Reclamation Engineer
By

Chief Clerk

A:hl1

R-913

July 13, 1953

RE: Permits Nos. 24261 and R-913

Mr. Herman E. Huettig
Hazelton
Idaho

Dear Mr. Huettig:

We enclose Permits Nos. 24261 and R-913 and direct your attention to the limitations and conditions as given on the fourth page under approval of the State Reclamation Engineer.

Since the dam described in Permit No. R-913 is over 10 feet high, it will be necessary for you to furnish plans and specifications in duplicate for approval by this department before construction is commenced, or else obtain approval from the State Reclamation Engineer of an application for a waiver of this condition.

Very truly yours,


MARK R. KULP
State Reclamation Engineer
By

Chief Clerk

A:fg
Enc.

R-913

NAME OF APPLICANT HERMAN E. HUETTIG



SCALE: 2 Inches Equal 1 Mile. Draw Plan in Ink.

R-913